

SOIL AND GROUNDWATER MANAGEMENT PLAN

Eversource Seacoast Reliability Project Gundalow Landing to Portsmouth Substation Newington, New Hampshire

1. Introduction

This document presents the requirements and procedures to be undertaken by Eversource personnel or hired contractors that excavate soil or manage soil or groundwater during installation of a new electric transmission line from Gundalow Landing to the Portsmouth Substation in Newington, New Hampshire (the Project Area; Fig. 1). The new transmission line is being installed as part of Eversource's Seacoast Reliability Project (SRP). The SRP will replace existing above-ground electric lines and towers in the Project Area. The Project Area is approximately 4.25 miles long and begins at Gundalow Landing adjacent to Little Bay, in the west and terminates at the Portsmouth Substation in the east (Fig. 1). This Soil and Groundwater Management Plan excludes the Darius Frink Farm property. A separate Soil and Water Management Plan has been prepared for the Darius Frink Farm. A summary of GEI's soil and water investigation activities and the Groundwater Management Plan for the Darius Frink Farm are included in Appendix A.

2. Background and Regulatory History

The SRP alignment in Newington begins at Gundalow Landing and proceeds northeast for approximately 1.8 miles where it then turns southeast and continues along Spaulding Turnpike for approximately 1.5 miles. The SRP then proceeds east under Spaulding Turnpike and continues for 1 mile, terminating at the Portsmouth Substation. A portion of the 1.5 mile stretch of the SRP is within the disposal site boundary associated with Pease Air Force Base (Pease). Several historical releases are being managed at Pease including releases of jet fuel and other petroleum constituents, chlorinated solvents, and perfluorinated compounds (PFCs). PFCs have been detected in groundwater and surface water and are associated with former firefighting activities at Site 8. In addition, other portions of the Project Area outside of the Pease Site Boundary are located downgradient of the Pease Site 8 contaminated groundwater plume. Since the work will include excavation to support construction of underground sections and above ground structures, there is potential to encounter contaminated soil and groundwater during construction activities. Eversource has requested an Area of Special Notice (ASN) determination from the Pease Development Authority (PDA) that could be used to provide soil and water management requirements for portions of the SRP that pass through the Pease Site Boundary. As of the submission date of this plan, Eversource has not received an approved ASN from PDA.

Proper procedures for on-site management and off-site disposal of soil and groundwater are necessary to reduce the potential for exposure to oil and hazardous materials (OHM) and be protective of workers and the public. The objectives of this Soil and Groundwater Management Plan are to:

- a) Ensure that soil and groundwater is managed appropriately on-site or disposed of appropriately off-site if necessary; and
- b) Specify procedures to limit exposures to contaminated soil or groundwater via dermal contact, inhalation, and/or ingestion.

2.1 *NHDES Emergency Rule for PFCs*

In May 2016, NHDES enacted Emergency Rule 05-31-16 under Env-Or-600 which includes the addition of perfluorooctanoic acid (PFOA) and perfluorooctane sulfonate (PFOS) to the New Hampshire state

ambient groundwater quality standards (AGQS). The AGQS for PFOA, PFOS, and the combined concentration of PFOA and PFOS is 0.07 µg/L. Env-Or-600 does not currently include soil standards or regulations for PFOA or PFOS. These standards will be applied, where applicable, for groundwater management during the project.

3. Preconstruction Requirements

The following must be completed before subsurface work commences, and approved by Eversource:

- **Notify Eversource Personnel:** The Eversource Project Manager shall be notified at least 10 business days prior to performing planned (non-emergency) soil excavation or other subsurface work that will require management of soil or groundwater. Also, Eversource shall be notified immediately (within one hour) if unanticipated conditions are encountered such as buried debris including drums, tanks or other containers.
- **Health and Safety Plan (HASP):** The contractor selected to perform the work in the Project Area is expected to prepare a HASP for its workers and the public to address the anticipated contaminants of concern, specifically PFOA, PFOS, and arsenic. The HASP shall include historical site characterization data. The HASP shall be prepared by a Certified Industrial Hygienist or other qualified individual appropriately trained in worker health and safety procedures and requirements. The contractor is solely responsible for conducting the work in a manner that is protective of workers and the public. Employees that will be handling contaminated or potentially contaminated soil or water are required to have OSHA HAZWOPER 40-hour training.
- **Regulatory Review and Submittals:** A review of other federal, state, or local regulatory requirements (e.g., National Pollutant Discharge Elimination System permits) shall be conducted before work commences depending on the location and type of planned activity.

4. Construction Worker Screening Levels for PFCs

General screening levels for construction worker exposure to PFOA and PFOS in soil and groundwater are not available. Based on information from the United States Environmental Protection Agency (USEPA) and New Hampshire Environmental Health Program (EHP) we have derived the following construction work screening levels for this project, where applicable:

4.1 Soil

GEI Consultants, Inc. derived a human health risk-based screening level (SL) for a construction worker exposure to PFOA and PFOS in soil based on the EHP and NHDES methodology applied to derive a Direct Contact Risk-Based (DCRB) soil concentration for PFOA and PFOS in soil. Exposure assumptions used to derive these soil SLs were similar to NHDES Soil Category S-3 exposures considered protective of adult exposures to soil during short but intense exposures, such as during excavation work. These risk-based soil SLs account for exposure to impacted soil as a result of incidental ingestion and dermal contact during excavation work. Table 1 presents the soil SL derived for both PFOA and PFOS of 0.5 mg/kg.

The adult construction worker was assumed to be exposed to outdoor soil a total of 250 days a year. This assumption was based on an excavation worker exposed to soil 5 days per week for a 1-year excavation project (350 days) assuming a worker takes 2 weeks of vacation in a year. Based on NHDES guidance,

the adult excavation worker was assumed to ingest 480 mg of soil per day of intense excavation work. Also based on NHDES guidance, a soil adherence factor equal to 0.2 mg/cm² was assumed and an exposed skin surface area of 3,104 cm² was assumed, which includes hands, forearms, face and neck. Additional exposure parameters based on NHDES guidance are presented in Table 1. USEPA applies different exposure assumptions for the construction worker exposure scenario in the derivation of Regional Screening Levels (RSLs) for soil. Based on USEPA exposure assumptions for the construction worker, which are noted in Table 1, a slightly higher Construction Worker Soil Screening Level for PFOA and PFOS of 0.7 mg/kg could be derived.

The USEPA derived a Reference Dose (RfD) to evaluate non-cancer effects for PFOA and PFOS of 2×10^{-5} mg/kg-day, based on developmental effects. USEPA also derived a Cancer Slope Factor (CSF) for PFOA of 0.07 (mg/kg-day)⁻¹; however, according to USEPA, the non-cancer developmental endpoint for PFOA represented by the RfD is protective of the cancer endpoint. In addition, because the critical effect identified for PFOA and PFOS is a developmental endpoint and can potentially result from a short-term exposure during a critical period of development, USEPA concludes that the chronic RfD is applicable to both short-term and chronic risk assessment scenarios. Therefore, it is appropriate to use the chronic RfD derived for both PFOA and PFOS to estimate short-term or subchronic risk-based SLs for a construction worker. As a result, it is GEI's opinion that a conservative SL for construction workers of 0.5 mg/kg be used for both PFOA and PFOS as stated above and shown in Table 1.

4.2 Water

USEPA derived a drinking water Health Advisory (HA) and NHDES derived the AGQS for PFOA and PFOS of 0.07 µg/L. This HA is considered protective of lifetime exposures to PFOA and PFOS from residential ingestion of drinking water. This HA does not consider potential exposure to PFOA and PFOS as a result of dermal exposure or inhalation exposure. However, USEPA notes that neither PFOA nor PFOS are volatile and are therefore not expected to be present in air except if bound to particulate matter. According to USEPA's Health Effects Support Document for PFOA (May, 2016), there is evidence that PFOA is absorbed following dermal exposure. The EPA document presents a permeability coefficient for PFOA of 9.49×10^{-7} cm/hour for human skin. USEPA risk based equations for deriving RSLs (May, 2016) for dermal exposure to water were used to derive the Construction Worker Groundwater Screening Level for PFOA and PFOS of 1,000 µg/Liter.

5. Soil Management

5.1 Soil Excavation

Excavated material shall be handled in general accordance with *The New Hampshire Code of Administrative Rules, Chapter Env-Or 600 - Contaminated Site Management (Env-Or-600)* and all other applicable federal, state, and local laws, regulations, and bylaws.

- **Dust Control:** As needed, the contractor shall employ control measures to minimize airborne particulates during excavation or soil management (e.g. water sprays, mists, etc.).
- **Materials Management Area:** If excavated materials are to be stored or stockpiled in the Project Area, an Excavated Material Management Area will be established by the contractor and approved by Eversource, ensuring it is in accordance with NHDES Env-Or 611.05(b). The Materials Management Area shall be within the Eversource Project Area.

Excavated soils shall be placed on 20-mil polyethylene sheeting and covered with properly secured 6-mil polyethylene sheeting at the end of each work day (or more frequently if rain or wind events present the potential for stockpile erosion, dust blow off, or odor migration). Stockpile sheeting shall be ultraviolet resistant, cold crack resistant to -40 degrees Fahrenheit, and free of holes and foreign matter. Stockpiles shall not contain free liquids.

5.2 Soil Classification

5.2.1 On-site Reuse

Excess excavated material should be reused within excavations to the extent feasible if the visual/olfactory, chemical, or geotechnical properties of the excavated soil are suitable for reuse. This option may be refined, as necessary, based on the ASN from Pease and input from NHDES.

As soil is excavated, Eversource or their consultant's Professional Engineer (PE) or Professional Geologist (PG) shall observe and field screen the material for visual or olfactory indications of contamination. If visual or olfactory evidence of contamination is observed, soil will be screened for the presence of VOCs with a photoionization detector (PID) using the jar-headspace method. A minimum of one sample should be screened for visual or olfactory evidence of contamination per foundation element or open length of trench. Soils shall be screened more frequently if visual or olfactory indications of contamination are observed. Soil shall be segregated, if necessary, based on results of field screening.

5.2.2 Characterization for Off-site Reuse, Recycling, or Disposal (if necessary)

If excess soil cannot be placed on-site, the Contractor shall recommend a location for off-site reuse, recycling, or disposal and submit to Eversource for approval. The PE or PG will sample and test the soil based on the acceptance criteria of the approved receiving facility.

Excess excavated material shall be loaded and transported to an appropriate off-site reuse, recycling or disposal location. Person(s) transporting the excavated materials shall be licensed and permitted to transport such material in state(s) having jurisdiction. Trailers used for transport shall have covers to prevent dust blow-off.

The contractor shall prepare disposal documentation and shall provide Eversource with material tracking and disposal records and certifications. Project documentation shall be maintained, including accurate records of material tracking, disposal transportation manifests (e.g., Straight BOL), and if necessary, additional environmental testing required by the receiving location.

6. Dewatering

6.1 Groundwater Management – On-Site Recharge

We have assumed that groundwater generated during excavation dewatering is acceptable for recharge within the Project Area. This option may be refined, as necessary, based on the ASN from Pease and input from NHDES. Additionally, Eversource will acquire a Groundwater Discharge Permit for portions of the project where it is required by the ASN or by NHDES. Based on our discussion with NHDES, we understand that Groundwater Discharge Permits only need to be acquired for areas located in Groundwater Management Zones (GMZs) or where AGQS are exceeded.

The contractor's proposed method of recharge and locations must be approved by Eversource. All recharge must be to the ground and must be performed within the Project Area and approximately upgradient of the excavation area. Groundwater cannot be discharged, including runoff, to storm drains or to surface water without an appropriate permit (See section 6.2).

6.2 Alternative Groundwater Management Options

If the quantity of groundwater to be managed exceeds the capacity of onsite recharge, other potential groundwater management options may be used with approval by Eversource. Additional testing would be required to evaluate the potential type of contaminants that may be associated with dewatering influent and effluent. Any testing required for the following management options should be conducted by the PE/PG. These options include:

- **On-Site Surface Water Discharge:** On-site surface water discharge would require use of a water treatment system, including equipment such as fractionation (frac) tanks and carbon units, to adequately treat groundwater before discharge. It may be possible to discharge dewatering effluent into storm drains or surface water bodies under a NPDES Dewatering General Permit (DGP) with minimal treatment. Additional water testing for NPDES DGP requirements and approval from NHDES, and treatment for, at a minimum, total suspended solids (TSS) would be necessary. If, based on NHDES requirements or NPDES DGP testing results, a NPDES DGP is not appropriate, a NPDES Remediation General Permit (RGP) would likely be required to discharge dewatering effluent. Additional water treatment requirements would also likely apply.
- **Off-site Treatment of PFC Contaminated Water and Recharge at Pease:** Dewatering effluent contaminated with PFCs may be collected in a tanker truck or other appropriate containers, and transported off-site for treatment and recharge at Pease. Pease currently operates a groundwater treatment system at Site 8 that treats and recharges PFOA and PFOS contaminated groundwater. If Pease is selected for off-site treatment, the Contractor shall coordinate with Pease for accepting and treating the groundwater collected from the Project Area including obtaining any required permits.
- **Off-Site Disposal:** If on-site recharge or treatment or offsite water treatment for PFCs at Pease (if applicable) is not feasible, the contractor shall identify an appropriate off-site groundwater disposal method and facility. Dewatering effluent may be pumped into a tanker truck or other appropriate containers, and transported off-site to the selected facility. All receiving facilities must be pre-approved by Eversource. No excess effluent may be recharged or disposed of at an uncontrolled location.

Attachments:

Table 1 – Derivation of Soil Screening Levels for PFCs

Figure 1 – Site Location Map

Appendix A – Darius Frink Farm Soil and Water Investigation Report and Soil and Water Management Plan

Table 1. Derivation of Soil Screening Levels for PFCs
Eversource NH Seacoast Reliability Project
Newington, New Hampshire


Development of NHDES Direct Contact Risk-Based Concentration (DCRB) for PFOA and PFOS in Soil

Soil Category	S-3	
Sensitive Receptor	Adult Construction/Excavation Worker	
RSCF	0.2	NHDES = Relative Source Contribution Factor
RfD (mg/kg-day)	2.00E-05	USEPA, 2016
CF (mg/kg)	1.00E+06	conversion factor
IR (mg/day)	480	MADEP uses 100 mg/day and USEPA uses 330 mg/day for CW
RAFo	1	NHDES
RAFd	0.1	NHDES
SA (cm2)	3,104	NHDES; USEPA uses 3,527 cm2 for CW
AF (mg/cm2)	0.2	NHDES; USEPA uses 0.3 mg/cm2 for CW
EF (days per year)	250	12 month project (5 days/week for 350 days in a year)
ED (years)	1	professional judgement
AT (days)	250	averaging period for a subchronic exposure is the subchronic period
BW (kg)	70	NHDES; USEPA uses 80 kg
S-3 DCRB Soil Concentration (mg/kg)=	0.5	

Concentration in Soil (mg/kg) =
$$\frac{RSCF * RfD * CF}{[(IR * RAFo) + (SA * AF * RAFd)] * [(EF * ED)/(AT * BW)]}$$

Notes:

1. NHDES Soil S-1 = 0.5 mg/kg for PFOA and PFOS
2. NHDES Soil S-2 = 4.3 mg/kg for PFOA and PFOS



Soil and Groundwater Management Plan
Gundalow Landing to Portsmouth Substation
Newington and Portsmouth, New Hampshire

Eversource Energy
Manchester, New Hampshire

GEI Consultants

Project 1607530

SITE LOCATION MAP

June 2017

Fig. 1

Appendix A

Darius Frink Farm Soil and Water Investigation Report and Soil and Water Management Plan



Consulting June 29, 2017
Engineers and Project 1607530
Scientists

VIA EMAIL: Kurt.Nelson@eversource.com

Mr. Kurt I. Nelson
Eversource Energy
13 Legends Way
Hookset, NH 03106

Dear Mr. Nelson:

Re: **Soil and Water Investigation and Management Plan
Darius Frink Farm
Newington, New Hampshire**

GEI Consultants, Inc. prepared this letter report to summarize the results of our soil, groundwater, and surface water investigations and to provide recommendations for soil and water management to support Eversource Energy's installation of a new electric transmission line at Darius Frink Farm in Newington, New Hampshire (the Property; Fig. 1). The new transmission line is being installed as part of Eversource Energy's Seacoast Reliability Project (SRP).

The Property consists primarily of farm land and wetlands. Eversource has a Right of Way (ROW) through the Property that is currently used for an above-ground electric distribution line. The current design of the SRP consists of the construction of a new 115 kilovolt (kV) overhead transmission line through the Property. However, Eversource is seeking to acquire permission to install the transmission line underground. These investigations were conducted to develop appropriate soil, groundwater, and surface water management practices to support either the overhead or the underground design.

The Property is located within the downgradient contaminant plume of Site 8 located at Pease Air Force Base (Pease; Fig. 1). Therefore, soil and water management must be performed in accordance with State of New Hampshire Department of Environmental Services (NHDES) regulatory requirements. NHDES does not provide specific guidance for utility related work; therefore, the process for investigation, cleanup, and reporting for this project was performed in general accordance with *The New Hampshire Code of Administrative Rules, Chapter Env-Or 600 - Contaminated Site Management* (Env-Or-600). Our recommendations for soil and water management are in Appendix A.

Our scope of work included the following tasks:

- Reviewing project information provided by Eversource.
- Advancing three borings on the Property which were completed as monitoring wells.
- Collecting soil, groundwater, and surface water samples for laboratory analytical testing.
- Performing hydraulic conductivity testing.
- Developing recommendations for management of soil and water generated during construction.
- Preparing a Soil and Water Management Plan for the Property.

1. Summary & Findings

GEI's investigation indicated the following:

- Perfluorinated compounds (PFCs) were not present in the soil tested.
- PFC concentrations in groundwater, where encountered, were less than New Hampshire state ambient groundwater quality standards (AGQS) of 0.07 µg/L.
- PFC concentrations in surface water from Knight's Brook tributary exceeded the NH AGQS of 0.07 µg/L.
- Soils at the Property are primarily silts underlain by clay. Based on hydraulic conductivity testing, the estimated dewatering rates for the trench range from approximately 45 to 1,500 gallons per day.

1.1. Soil, Groundwater, & Surface Water Management

Based on the results of our investigation, GEI recommends the following for soil, groundwater, and surface water management:

- **Soil:** Soil should be reused in the excavation to the extent feasible. Excess soil can be reused as fill at the Property at locations approved by the Property owner and Eversource.
- **Groundwater:** Groundwater from Stations 496+75 to 498+00 and 500+00 to 511+00 should be recharged within the Project Area. Groundwater between Stations 498+00 and 500+00 should be transported Pease for treatment and recharge.
- **Surface Water:** Surface water should be diverted during construction in a manner that does not produce excess water or require additional water management, treatment, or offsite disposal.

Station locations are shown on Fig. 2 and the Soil and Water Management Plan for Darius Drink Farm is in Appendix A.

2. Background

2.1. Site Description

Eversource proposes to pass the SRP through an existing overhead transmission line corridor on the Darius Frink Farm, located to the north of Pease (Fig. 1) in Newington, NH. Darius Frink Farm consists of several buildings, a cultivated vegetable garden, a cow pasture, and an uncultivated field. The work will be performed within an uncultivated field, which is currently maintained for haying operations (the Project Area; Fig. 2). The Project Area is approximately 1,600 feet long and begins at the riser structure on the western edge of the property and ends at Nimble Hill Road (Fig. 2). If permission is granted to install the SRP transmission line underground, the proposed trench in the Project Area will be approximately 5-foot-wide and up to 8-foot-deep.

2.2. Regulatory History

There have been no releases of oil or hazardous material (OHM) reported at the Property, which has been owned by the Frink family for five generations. However, the Property and Project Area are located downgradient of the Pease Site 8 contaminated groundwater plume which contains PFCs associated with former firefighting activities. Since the portion of the SRP in the Project Area may be underground, there is potential to encounter contaminated soil and groundwater during construction activities. PFCs have also been detected in surface water in Knight's Brook along the eastern edge of the Project Area and within the proposed SRP alignment.

In May 2016, NHDES enacted Emergency Rule 05-31-16 under Env-Or-600 which includes the addition of PFCs to the New Hampshire AGQS. The AGQS for perfluorooctanoic acid (PFOA), perfluorooctane sulfonate (PFOS), and the combined concentration of PFOA and PFOS is 0.07 µg/L. Env-Or-600 does not currently include soil standards or regulations for PFOA or PFOS.

2.3. Chemicals of Concern

PFOA and PFOS are the primary contaminants of concern in the Project Area. PFOA and PFOS are PFCs and part of a group of man-made chemicals that have been used to manufacture a large range of products including nonstick cookware, carpets, some food packaging, paints, cleaning products, and firefighting foams. PFCs are very persistent in the environment, and are known to travel long distances in groundwater.

PFOA and PFOS contamination has been previously identified downgradient of Pease Site 8 in surface water in local streams (e.g. Knight's Brook tributary, Knights Brook, and Pickering Brook; Fig. 1). The presence of PFOA and PFOS downgradient of Site 8 has been associated with the historic use of aqueous film forming foam (AFFF) at Site 8 at Pease. Around 1970, the US Air Force began using aqueous AFFF for extinguishing petroleum fires during firefighting training activities at the current Site 8 location. Site 8 was used to simulate aircraft crash fires in a pit area using jet fuel, mixed waste oils, and solvents. The mixture was burned before being extinguished with AFFF. Excess fuels and AFFF were discharged from the burn pit into a drainage ditch at the northern end of Site 8.

Prior to this investigation, there was limited information on the presence of PFOA or PFOS at the Property or in the Project Area. The results of our investigation are summarized below and our recommendations for managing soil and water are presented in Appendix A.

3. Site Characterization

In August and September 2016 and April and June 2017, GEI performed an investigation to characterize soil groundwater, and surface water within the Project Area to assess conditions that may be encountered during construction activities. GEI performed soil borings, sampled soil, installed monitoring wells, sampled groundwater, performed hydraulic conductivity tests, and sampled surface water. During sampling, we took special precautions to prevent potential PFC cross-contamination from outside sources including:

- No use of Teflon[®]-containing materials (i.e. Teflon[®] tubing, bailers, tape, plumbing paste);
- No Tyvek[®] clothing was worn;
- Clothes treated with stain- or rain-resistant coatings were avoided or had gone through several washings; no PostIt[®] Notes were handled or brought on site;
- No fast food wrappers, disposable cups or microwave popcorn were brought on site during sampling;
- Hands were washed after handling such items and prior to any sampling activities;
- No use of chemical (blue) ice packs was allowed; and
- Nitrile gloves were worn during all sample collection activities.

3.1. Soil Boring Advancement and Monitoring Well Installation – August 2016

On August 26, 2016, GEI observed DrillEx Environmental (DrillEx) of West Boylston, Massachusetts advance three borings and install three groundwater monitoring wells (B101[MW], B102[MW], and B103[MW]) to evaluate environmental site conditions in the Project Area. Borings were advanced to approximately 8 feet below grade, consistent with the proposed trench depth, using hollow stem augers

with continuous split spoon sampling. Boring locations are shown on Fig. 2. Boring and monitoring well installation logs are included in Appendix B.

GEI collected two soil samples from each boring consisting of composite samples from the 0 to 4 foot interval and the 4 to 8 foot interval (B101[S1-S2], B101[S3-S4], B102 [S1-S2], B102 [S3-S4], B103[S1-S2], B103[S3-S4]). GEI submitted the soil samples to Alpha Analytical, Inc. (Alpha) of Westborough, Massachusetts to be tested for PFOA, PFOS, and offsite disposal characterization parameters including: volatile organic compounds (VOCs), semi-volatile organic compounds (SVOCs), total petroleum hydrocarbons (TPH), polychlorinated biphenyls (PCBs), RCRA 8 Metals (arsenic, barium, cadmium, chromium (total), lead, mercury, selenium, silver), conductivity, corrosivity, ignitability, and reactivity (cyanide and sulfide). Soil chemical testing results are summarized in Table 1 and the laboratory data report is in Appendix C.

Based on conditions we observed during our subsurface investigation, the shallow subsurface in the Project Area generally consists of silt underlain by clay. The soils encountered during our subsurface investigation are described below, starting at the ground surface. The soil conditions are known only at the boring locations. Conditions between borings may differ significantly from those described below.

- Silt: A sandy silt with mostly non-plastic fines, composes the upper layer of the soil profile.
- Clay: A lean and sandy clay with low plasticity fines.
- Gravel (in B103[MW] only): Widely graded gravel with silt and sand.

3.2. Hand Auger Borings – April 2017

On April 7, 2017, GEI advanced two shallow borings (HA1 and HA2) in the vicinity of Knight's Brook tributary to assess soil stratigraphy in the proposed trench alignment. Borings HA1 and HA2 were advanced to 6.5 feet and 6 feet, respectively and consistent with the proposed trench depth. The borings were sampled continuously using hand auger techniques. Boring locations are shown on Fig. 2. Boring logs are included in Appendix B.

Based on the conditions we observed, the shallow subsurface in the Knight's Brook tributary area generally consists of sandy silt underlain by clay. The soils encountered during our subsurface investigation are described below, starting at the ground surface. The soil conditions are known only at the boring locations. Conditions between borings may differ significantly from those described below.

- Organic Soil: A layer of organic soil composed of low plasticity fines and organic matter at the surface.
- Sandy Silt: A sandy silt with mostly non-plastic fines, composes the upper layer of the soil profile.
- Clay: A lean and sandy clay with low plasticity fines.

We prepared a cross-section of the Knight's Brook tributary based on and interpolated from the information collected from the hand augers and previous investigations by GEI and others. Based on the available boring information, the general subsurface conditions appear to be consistent between F107-109 and GEI-101 with silty sands overlying clay layer. Boring logs are included in Appendix B and the cross-section is shown on Fig. 3

3.3. Groundwater & Surface Water Sampling – 2016

On August 29, 2016, GEI developed monitoring wells B101(MW) and B102(MW). Groundwater was measured at 4.79 feet and 3.77 feet in B101(MW) and in B102(MW), respectively. B103(MW) was

not developed because the well was dry. GEI developed the wells by surging and removing water using a dedicated Watera® check valve and tubing. A well was considered developed when either:

- 10-well volumes were removed; or
- Water removed from the well was relatively free of fine-grained material; or
- The well ran dry.

Wells B101(MW) and B102 (MW) ran dry after removing approximately 2.25 gallons and 6 gallons, respectively.

On September 1, 2016, GEI returned to the Property to collect groundwater samples from B101(MW) and B102(MW) using low-flow methods. Groundwater was not detected in B103(MW); therefore, a groundwater sample was not collected. GEI used peristaltic pumps for low flow purging. Dedicated tubing was lowered to the mid-point of the saturated screen interval and a water level was used to periodically measure the water level in the well during purging. Purge rates were adjusted to minimize drawdown to the extent feasible. During low flow purging a YSI Sonde 6200 was used to measure temperature, pH, specific conductivity, dissolved oxygen, oxidation reduction potential, and turbidity. GEI collected a groundwater sample from the well when each of the parameters was stable for a minimum of three consecutive readings. Additionally, we collected a surface water sample (SW1) from Knight's Brook. Groundwater and surface water samples were submitted to Alpha to be tested for PFOA and PFOS.

Groundwater and surface water chemical testing results are summarized in Table 2 and the laboratory data report is in Appendix C. Groundwater measurements observed during each visit are included in Table 3.

3.4. Groundwater Sampling – 2017

On April 7, 2017, GEI returned to the property to gauge wells during spring conditions. At that time, we observed the field was flooded due to spring melt and heavy rains. As a result, groundwater levels in all three wells (B101[MW], B102[MW], and B103[MW]) was at approximately the ground surface. Due to these flooding conditions groundwater sampling was not performed.

On June 2, 2017 GEI returned to the property to collect groundwater level information and samples from the three monitoring wells under normalized spring conditions. During this groundwater sampling event water was detected in all three wells and groundwater samples were collected from each using the methods described in Section 3.3. Groundwater was measured at 0.83 feet, 1.12 feet, and 2.31 feet in B101(MW), B102(MW), and B103(MW), respectively. Groundwater and surface water samples were submitted to Alpha to be tested for PFOA and PFOS.

Groundwater and surface water chemical testing results are summarized in Table 2 and the laboratory data report is in Appendix C. Groundwater measurements observed during each visit are included in Table 3.

3.5. Hydraulic Conductivity Testing

On September 15, 2016, GEI conducted rising head well permeability tests on B101(MW) and B102(MW). The tests were performed using dedicated In-Situ Level TROLL 700 data loggers. Prior to starting the test, GEI collected water level and total depth readings from the wells. Groundwater was measured at 4.92 feet and 4.39 in B101(MW) and B102(MW), respectively. Groundwater was not detected in B103(MW). The data loggers were then placed near the bottom of each well and a peristaltic pump was used to draw down the water level. The water was then allowed to recharge to approximately the pre-purge level while the data loggers recorded the rebound in water level. GEI collected manual water level measurements throughout the duration of each test in order to perform

quality control checks on the TROLL readings. We performed two tests on B101(MW) and three tests on B102(MW). B103(MW) was not tested because it was dry. Groundwater measurements observed during each visit are included in Table 3. The hydraulic conductivity testing results are summarized in Table 4.

4. Results

4.1. Soil Analytical Results

Soil samples did not contain detectable levels of PFOA, PFOS, VOCs, SVOCs, or PCBs. Soil chemical testing results indicated that presence of the following compounds above the laboratory detection limits:

- TPH
- Metals: arsenic, barium, chromium and lead.

TPH was detected above laboratory detection limit in samples B101(S1-S2); however, the concentration was well below the NHDES Method 1 Soil Standard (NH S-1). Barium, chromium, and lead were detected in all the soil samples at concentrations less than NH S-1. Arsenic was detected in B102(S1-S2) and B102(S3-S4) at 12 milligrams per kilogram (mg/kg). This is slightly above the NH S-1 standard and the NHDES Background Concentration of 11 mg/kg but is still likely attributable to background conditions at the Property. Soil testing results are summarized in Table 1 and the laboratory data report is in Appendix C.

4.2. Groundwater & Surface Water Analytical Results

Groundwater and surface water testing results indicated the following:

- PFOA and PFOS were not detected in B101(MW) in September 2016. PFOA and PFOS were detected in B101(MW) in June 2017 but at concentrations below the NH AGQS of 0.07 µg/L.
- PFOA and PFOS were detected in B102(MW) in both September 2016 and June 2017 but at concentrations below the NH AGQS of 0.07 µg/L.
- PFOA was not detected in B103(MW). PFOS was detected in B103(MW) but at concentrations below the NH AGQS of 0.07 µg/L.
- PFOA and PFOS were detected in sample SW1 from Knight's Brook at 0.842 µg/L and 2.91 µg/L, respectively. The total PFOA/PFOS concentration was 3.752 µg/L. Both the individual and total concentrations exceed the NH AGQS of 0.07 µg/L.
- PFOA and PFOS were not detected in a field blank sample collected during the June 2017 groundwater sampling event.

Groundwater and surface water testing results are summarized in Table 2 and the laboratory data report is in Appendix C.

4.3. Hydraulic Conductivity

Based on the testing results, we estimated the following average hydraulic conductivities:

- B101(MW) has an average hydraulic conductivity of 0.062 feet/day which is likely due to the silt and clay observed during installation of the well.
- B102(MW) has an average hydraulic conductivity of 0.222 feet/day which is likely due to the sand seam observed within the well screen interval. The sand seam was observed in the boring at approximately 5 feet below the ground surface.

- B103(MW) hydraulic conductivity was not calculated because the well was dry at the time of testing.

The hydraulic conductivity testing results are summarized in Table 4.

4.4. Groundwater Model & Dewatering Estimate

Assuming an underground design is implemented, GEI calculated expected dewatering rates of groundwater within the proposed trench alignment. GEI calculated dewatering rates based for both a low and high groundwater conditions, as experienced in the fall of 2016 and spring of 2017, respectively. Based on our calculations, we estimate dewatering may range from 45 to 1,500 gallons per day (gpd) depending on the location of the excavation and groundwater levels. Our calculations are based on the limited geologic information observed during installation of B101(MW), B102(MW), and B103(MW). The estimated dewatering rates are as follows:

- Near B101(MW): Approximately 45 to 82 gpd during a low water condition and approximately 486 to 770 gpd during a high groundwater condition.
- Near B102(MW): Approximately 104 to 187 gpd during a low groundwater condition and approximately 942 to 1466 gpd during a high groundwater condition.
- Near B103: Based on the soil encountered in B103(MW), we estimate the dewatering rates near B103(MW) will likely be between the estimated ranges for B101(MW) and B102(MW). The trench near B103(MW) may also be dry if construction takes place during low groundwater conditions similar August and September of 2017.

The groundwater flow model and dewatering estimate is in Appendix D.

5. Construction Worker Screening Levels

General screening levels for construction worker exposure to PFOA and PFOS in soil and groundwater are not available. Based on information from the United States Environmental Protection Agency (USEPA) and New Hampshire Environmental Health Program (EHP) we have derived the following construction work screening levels for this project, where applicable:

5.1. Soil

GEI derived a human health risk-based screening level (SL) for a construction worker exposure to PFOA and PFOS in soil based on the New Hampshire Environmental Health Program (EHP) and NHDES methodology applied to derive a Direct Contact Risk-Based (DCRB) soil concentration for PFOA and PFOS in soil. Exposure assumptions used to derive these soil SLs were similar to NHDES Soil Category S-3 exposures considered protective of adult exposures to soil during short but intense exposures, such as during excavation work. These risk-based soil SLs account for exposure to impacted soil as a result of incidental ingestion and dermal contact during excavation work. Table 5 presents the soil SL derived for both PFOA and PFOS of 0.5 mg/kg.

The adult construction worker was assumed to be exposed to outdoor soil a total of 250 days a year. This assumption was based on an excavation worker exposed to soil 5 days per week for a 1-year excavation project (assumes 350 total days of excavation) and assuming a worker takes 2 weeks of vacation in a year. Based on NHDES guidance, the adult excavation worker was assumed to ingest 480 mg of soil per day of intense excavation work. Also based on NHDES guidance, a soil adherence factor equal to 0.2 mg/cm² was assumed and an exposed skin surface area of 3,104 cm² was assumed, which includes hands, forearms, face and neck. Additional exposure parameters based on NHDES guidance are presented in Table 5. USEPA applies different exposure assumptions for the construction worker exposure scenario in the derivation of Regional Screening Levels (RSLs) for soil.

Based on USEPA exposure assumptions for the construction worker, which are noted in Table 5, a slightly higher Construction Worker Soil Screening Level for PFOA and PFOS of 0.7 mg/kg could be derived.

The USEPA derived a chronic Reference Dose (RfD) to evaluate non-cancer effects for PFOA and PFOS of 2×10^{-5} mg/kg-day, based on developmental effects. USEPA also derived a Cancer Slope Factor (CSF) for PFOA of $0.07 \text{ (mg/kg-day)}^{-1}$; however, according to USEPA, the non-cancer developmental endpoint for PFOA represented by the RfD is protective of the cancer endpoint. In addition, because the critical effect identified for PFOA and PFOS is a developmental endpoint and can potentially result from a short-term exposure during a critical period of development, USEPA concludes that the chronic RfD is applicable to both short-term and chronic risk assessment scenarios. Therefore, it is appropriate to use the chronic RfD of 2×10^{-5} mg/kg-day derived for both PFOA and PFOS to estimate short-term or subchronic risk-based SLs for a construction worker.

5.2. Water

USEPA derived a drinking water Health Advisory (HA) and NHDES derived the AGQS for PFOA and PFOS of $0.07 \text{ }\mu\text{g/L}$. This HA is considered protective of lifetime exposures to PFOA and PFOS from residential ingestion of drinking water. This HA does not consider potential exposure to PFOA and PFOS as a result of dermal exposure or inhalation exposure. However, USEPA notes that neither PFOA nor PFOS are volatile and are therefore not expected to be present in air except if bound to particulate matter. According to USEPA's Health Effects Support Document for PFOA (May, 2016), there is evidence that PFOA is absorbed following dermal exposure. The EPA document presents a permeability coefficient for PFOA of 9.49×10^{-7} cm/hour for human skin. USEPA risk based equations for deriving RSLs (May, 2016) for dermal exposure to water were used to derive the Construction Worker Water Screening Level for PFOA and PFOS of $1,000 \text{ }\mu\text{g/Liter}$.

6. Soil and Water Management

Since the work is being performed in the downgradient plume of Site 8, proper procedures for on-site management and off-site disposal of soil and groundwater are necessary to reduce the potential for exposure to PFOA and PFOS and be protective of workers and the public. GEI prepared a Soil and Water Management Plan that presents the requirements and procedures to be undertaken by Eversource personnel or hired contractors that excavate soil or manage soil, groundwater, or surface water during installation of a new overhead or underground electric transmission line at Darius Frink Farm. The Soil and Water Management Plan is in Appendix A.

Based on the results of our investigation, GEI recommends the following for soil, groundwater, and surface water management:

- **Soil:** Soil should be reused in the excavation to the extent feasible. Excess soil can be reused as fill at the Property at location approved by the Property owner and Eversource.
- **Groundwater:** Groundwater from Stations 496+75 to 498+00 and 500+00 to 511+00 should be recharged within the Project Area. Groundwater between Stations 498+00 and 500+00 should be transported Pease for treatment and recharge or treated and discharged to surface water in accordance with National Pollutant Discharge Elimination System (NPDES) requirements.
- **Surface Water:** Surface water should be diverted during construction in a manner that does not produce excess water or require additional water management, treatment, or offsite disposal.


7. Limitations

This report was prepared for the exclusive use of Eversource Energy. The conclusions provided by GEI in this report are based on the information contained in this report. Additional information not available to GEI at the time this report was prepared may result in a modification of our conclusions. This report has been prepared in accordance with generally accepted engineering and geohydrological practices. No warranty, express or implied, is made.

Please contact Jim Ash at JAsh@geiconsultants.com or 781-721-4018 or Mike Sabulis at MSabulis@geiconsultants.com or 781-721-4114 if you have any questions.

Sincerely,

GEI CONSULTANTS, INC.



James R. Ash, P.E., LSP
Senior Vice President



Michael Sabulis
Project Manager

CRC/MWS/JRA:jam

Attachments:

- Table 1 – Laboratory Testing Results – Soil
- Table 2 – Laboratory Testing Results – Groundwater and Surface Water
- Table 3 – Water Level Measurements
- Table 4 – Hydraulic Conductivity Test Results
- Table 5 – Derivation of Soil Screening Levels
- Fig. 1 – Site Location Map
- Fig. 2 – Project Area Plan
- Fig. 3 – Cross Section – Knight’s Brook Tributary
- Appendix A – Soil and Water Management Plan
- Appendix B – Boring and Monitoring Well Installation Logs
- Appendix C – Laboratory Test Reports
- Appendix D – Groundwater Model Description

Tables

Table 1. Laboratory Testing Results - Soil
Darius Frink Farm
Eversource NH Seacoast Reliability Project
Newington, New Hampshire

Analyte	Method	Units	NH S-1	NHDES Background	B101		B102		B103	
					S1-S2	S3-S4	S1-S2	S3-S4	S1-S2	S3-S4
					0-4	4-8	0-4	4-6.8	0-4	4-8
					8/26/2016	8/26/2016	8/26/2016	8/26/2016	8/26/2016	8/26/2016
Perfluorinated Compounds (PFCs)	537	ng/g								
Perfluorooctanoic Acid (PFOA)			NS	NS	< 1.96	< 1.96	< 1.95	< 1.95	< 1.93	< 2.02
Perfluorooctane Sulfonate (PFOS)			NS	NS	< 1.96	< 1.96	< 1.95	< 1.95	< 1.93	< 2.02
Volatile Organic Compounds (VOCs)	8260C	mg/kg								
Total VOCs			NS	NS	ND	ND	ND	ND	ND	ND
Semi-Volatile Organic Compounds (SVOCs)	8270D	mg/kg								
Total SVOCs			NS	NS	ND	ND	ND	ND	ND	ND
Total Petroleum Hydrocarbons (TPH)	8015	mg/kg								
Total Petroleum Hydrocarbons			10000	NS	39.0	< 39.8	< 39.5	< 39.9	< 35.5	< 34.1
Polychlorinated Biphenyls (PCBs)	8082A	mg/kg								
Total PCBs			1	NS	ND	ND	ND	ND	ND	ND
Total Metals		mg/kg								
Arsenic	6010C		11	11	7.4	5.6	12	12	9.0	7.1
Barium	6010C		1,000	NS	28	33	44	31	30	18
Cadmium	6010C		33	2	< 0.47	< 0.48	< 0.47	< 0.49	< 0.42	< 0.42
Chromium (Total)	6010C		1,000	33	14 F-,G	16 F-,G	19 F-,G	18 F-,G	30 F-,G	26 F-,G
Lead	6010C		400	51	5.7 F-	4.6 F-	6.8 F-	8.9 F-	7.2 F-	8.6 F-
Mercury	7471B		7	0.3	< 0.08	< 0.08	< 0.08	< 0.08	< 0.07	< 0.07
Selenium	6010C		180	5	< 0.94	< 0.96	< 0.94	< 0.98	< 0.85	< 0.84
Silver	6010C		89	NS	< 0.47	< 0.48	< 0.47	< 0.49	< 0.42	< 0.42
Other										
Conductivity	EPA 120.1M	umhos/cm	NS	NS	< 10	< 10	< 10	28 G	< 10	44 G
Corrosivity (pH)	9045D	S.U.	NS	NS	6.2 A	6.4 A	6.3 A	7.4 A	5.7 A	0.3
Oxidation-Reduction Potential	ASTM D1498-76M	mv	NS	NS	180 A	170 A	170 A	190 A	170 A	150 A
Flashpoint	1030	deg F	NS	NS	NI	NI	NI	NI	NI	NI
Reactive Cyanide	CHAP7	mg/kg	NS	NS	< 10	< 10	< 10	< 10	< 10	< 10
Reactive Sulfide	CHAP7	mg/kg	NS	NS	< 10	< 10	< 10	< 10	< 10	< 10
Percent Solids	SM 2540G-97 MOD	%	NS	NS	84.2	80.9	83.6	79.2	93.3	92.4

General Notes

- In general, analytes detected in at least one sample are reported here. For a complete list of analytes see the laboratory data sheets.
- "<" = The analyte was not detected at a concentration above the specified laboratory reporting limit.
- NH S-1 and NHDES Background standards from The New Hampshire Code of Administrative Rules, Chapter Env-Or 600 - Contaminated Site Management.
- Values in bold exceed the NH S-1 and/or NDHES Background values.
- NS = No standard or criteria has been established for this analyte.
- NI = Not Ignitable
- ND = Not detected.
- Soil samples for VOC analysis were preserved in the field with methanol.
- mg/kg = milligrams per kilogram.
- umhos/cm = micromhos per centimeter.
- S.U. = standard units.
- mv = millivolts.
- deg F = degrees Fahrenheit.
- ng/g = nanograms per gram.

Qualifying Notes

- A The result is estimated due to exceedance of holding time criteria.
- F- The result has a low bias due to matrix spike recovery below lower control limits.
- G The result is estimated due to duplicate precision outside control limits.

Table 2. Laboratory Testing Results - Groundwater and Surface Water
Darius Frink Farm
Eversource NH Seacoast Reliability Project
Newington, New Hampshire

				Sample Location:		1607530-B101(MW)		1607530-B102(MW)		1607530-B103(MW)	1607530-SW1
				Sample Date:	Screen Interval:	9/1/2016	6/2/2017	9/1/2016	6/2/2017	6/2/2017	9/1/2016
				2-8'	2-8'	2-7'	2-7'	2-8'	NA		
Analyte	Method	Units	NH AGQS								
Perfluorinated Compounds (PFCs)				537	ug/L						
Perfluorooctanoic Acid (PFOA)			0.07	< 0.00786	0.00248	0.0112	0.00711	< 0.00185	0.842		
Perfluorooctane Sulfonate (PFOS)			0.07	< 0.00786	0.00305	0.0161	0.0142	0.00187	2.91		
Total PFCs			0.07	ND	0.00553	0.0273	0.02131	0.00187	3.752		

General Notes:

1. In general, analytes detected in at least one sample are reported here. For a complete list of analytes see the laboratory data sheets.
2. "<" = The analyte was not detected at a concentration above the specified laboratory reporting limit.
3. NH AGQS = New Hampshire Ambient Groundwater Quality Standards
4. NH AGQS for PFOA and PFOS from Emergency Rule 05-31-16 to Amend The New Hampshire Code of Administrative Rules Env-OR 603.03(b), eff 6-1-15
5. Values in bold exceed the NH AGQS values.
6. ND = Not detected.
7. ug/L = milligrams per liter.

Table 3. Water Level Measurements
Darisu Frink Farm
Eversource NH Seacoast Reliability Project
Newington, New Hampshire

Well ID	August 26, 2016		August 29, 2016		September 1, 2016		September 15, 2016		April 7, 2017		June 2, 2017	
	Depth to GW from Top of PVC (ft)	Depth to GW from Ground Surface (ft)	Depth to GW from Top of PVC (ft)	Depth to GW from Ground Surface (ft)	Depth to GW from Top of PVC (ft)	Depth to GW from Ground Surface (ft)	Depth to GW from Top of PVC (ft)	Depth to GW from Ground Surface (ft)	Depth to GW from Top of PVC (ft)	Depth to GW from Ground Surface (ft)	Depth to GW from Top of PVC (ft)	Depth to GW from Ground Surface (ft)
MW101	ND	ND	7.91	4.79	7.79	4.67	8.04	4.92	3.41	0.29	3.95	0.83
MW102	7.29	4.39	6.67	3.77	6.79	3.89	7.18	4.28	3.61	0.71	4.02	1.12
MW103	NM	NM	ND	ND	ND	ND	ND	ND	At ground surface		2.11	2.31

Notes:

1. ft = feet
2. GW = groundwater
3. NM = Not measured
4. ND = Not detected

Table 4. Hydraulic Conductivity Test Results - Rising Head Test
Darius Frink Farm
Eversource NH Seacoast Reliability Project
Newington, New Hampshire

Well ID	Hydraulic Conductivity (ft/day)			
	Test 1	Test 2	Test 3	Average
B101(MW)	0.08	0.05	NA	0.062
B102(MW)	0.23	0.22	0.22	0.222
B103(MW)	NT	NT	NT	

Notes:

1. NA = Not applicable
2. NT = Not tested due to dry well
3. ft = feet

Table 5. Derivation of Soil Screening Levels for PFCs

Darius Frink Farm
 Eversource NH Seacoast Reliability Project
 Newington, New Hampshire

Development of NHDES Direct Contact Risk-Based Concentration (DCRB) for PFOA and PFOS in Soil

Soil Category	S-3	
Sensitive Receptor	Adult Construction/Excavation Worker	
RSCF	0.2	NHDES = Relative Source Contribution Factor
RfD (mg/kg-day)	2.00E-05	USEPA, 2016
CF (mg/kg)	1.00E+06	conversion factor
IR (mg/day)	480	MADEP uses 100 mg/day and USEPA uses 330 mg/day for CW
RAFo	1	NHDES
RAFd	0.1	NHDES
SA (cm2)	3,104	NHDES; USEPA uses 3,527 cm2 for CW
AF (mg/cm2)	0.2	NHDES; USEPA uses 0.3 mg/cm2 for CW
EF (days per year)	250	12 month project (5 days/week for 350 days in a year)
ED (years)	1	professional judgement
AT (days)	250	averaging period for a subchronic exposure is the subchronic period
BW (kg)	70	NHDES; USEPA uses 80 kg
S-3 DCRB Soil Concentration (mg/kg)=	0.5	


Concentration in Soil (mg/kg) =

$$\frac{RSCF * RfD * CF}{[(IR * RAFo) + (SA * AF * RAFd)] * [(EF * ED)/(AT * BW)]}$$

Notes:

1. NHDES Soil S-1 = 0.5 mg/kg for PFOA and PFOS
2. NHDES Soil S-2 = 4.3 mg/kg for PFOA and PFOS

Figures



This Image from U.S.G.S. Topographic 7.5 Minute Series
 Portsmouth, NH - ME Quadrangle, 1981.
 Datum is National Geodetic Vertical Datum of 1929 (NGVD29).
 Contour Interval is 20 Feet.



Soil and Water Investigation
 Darius Frink Farm
 Newington, New Hampshire
 Eversource Energy
 Manchester, New Hampshire




SITE LOCATION MAP

Project 1607530

June 2017

Fig. 1




LEGEND:

--- INTERPOLATED STRATA BOUNDARIES

NOTES:

1. ELEVATION APPROXIMATED FROM PROJECT PLANS, CIVIL DRAWINGS.
2. TERRACON BORING ELEVATIONS AND SOIL PROFILE FROM TERRACON BORING LOG.



Soil and Water Investigation Darius Frink Farm Newington, New Hampshire		CROSS SECTION - KNIGHT'S BROOK TRIBUTARY
Eversource Manchester, New Hampshire	Project 1607530	June 2017 Fig. 3

Appendix A

Soil and Water Management Plan

SOIL AND WATER MANAGEMENT PLAN

Eversource Seacoast Reliability Project Darius Frink Farm Newington, New Hampshire

1. Introduction

This document presents the requirements and procedures to be undertaken by Eversource personnel or hired contractors that excavate soil or manage soil, groundwater, or surface water during installation of a new underground electric transmission line at Darius Frink Farm in Newington, New Hampshire (the Property; Fig. 1). The new transmission line is being installed as part of Eversource's Seacoast Reliability Project (SRP). The new transmission line will be installed in Eversource's Right of Way (ROW) through the Property (the Project Area; Fig. 1) that is currently used for above-ground electric lines and towers. The Project Area is approximately 1,600 feet long and begins at the riser structure on the western edge of the property (Station 496+75) and ends at Nimble Hill Road (Station 511+00) (Fig. 2). This Soil and Water Management Plan is applicable only to the Project Area shown on the plan, not the entire Property.

2. Background and Regulatory History

There have been no releases of oil or hazardous material (OHM) reported at the Property, which has been owned by the Frink family for five generations. However, the Property and Project Area are located downgradient of the Pease Site 8 contaminated groundwater plume which contains perfluorinated compounds (PFCs) associated with former firefighting activities. Since the portion of the SRP in the Project Area will be underground, there is potential to encounter contaminated soil and groundwater during construction activities. Additionally, PFCs have been detected in surface water along the eastern edge of the Project Area in Knight's Brook.

In May 2016, NHDES enacted Emergency Rule 05-31-16 under Env-Or-600 which includes the addition of perfluorooctanoic acid (PFOA) and perfluorooctane sulfonate (PFOS) to the New Hampshire state ambient groundwater quality standards (AGQS). The AGQS for PFOA, PFOS, and the combined concentration of PFOA and PFOS is 0.07 µg/L. Env-Or-600 does not currently include soil standards or regulations for PFOA or PFOS.

Proper procedures for on-site management and off-site disposal of soil and water are necessary to reduce the potential for exposure to oil and hazardous materials (OHM) and be protective of workers and the public. The objectives of this Soil and Water Management Plan are to:

- a) Ensure that soil and water are managed appropriately on-site or disposed of appropriately off-site if necessary; and
- b) Specify procedures to limit exposures to contaminated soil or water via dermal contact, inhalation, and/or ingestion.

3. Preconstruction Requirements

The following must be completed before subsurface work commences, and approved by Eversource:

- **Notify Eversource Personnel:** The Eversource Project Manager shall be notified at least 10 business days prior to performing planned (non-emergency) soil excavation or other subsurface work that will require management of soil, groundwater, or surface water. Also, Eversource shall be notified immediately (within one hour) if unanticipated conditions are encountered such as buried debris including drums, tanks or other containers.

- **Health and Safety Plan (HASP):** The contractor selected to perform the work in the Project Area is expected to prepare a HASP for its workers and the public to address the anticipated contaminants of concern, specifically PFOA, PFOS, and arsenic. The HASP shall include historical site characterization data. The HASP shall be prepared by a Certified Industrial Hygienist or other qualified individual appropriately trained in worker health and safety procedures and requirements. The contractor is solely responsible for conducting the work in a manner that is protective of workers and the public. Employees that will be handling contaminated soil or water are required to have OSHA HAZWOPER 40-hour training.
- **Regulatory Review and Submittals:** A review of other federal, state, or local regulatory requirements (e.g., National Pollutant Discharge Elimination System permits) shall be conducted before work commences depending on the location and type of planned activity.

4. Soil Pre-Characterization and Classification

GEI conducted soil pre-characterization in August 2016. Based on the results of GEI's soil pre-characterization, soil in the Project Area is suitable for onsite reuse within the Property boundary. The contractor shall determine a suitable place on the Property, in conjunction with the Property owner and Eversource, to stockpile or spread the excess soil. Excess soil can only be stockpiled or spread in upland locations and in a manner that will not detrimentally affect nearby wetlands. All backfill activities shall be in accordance with the *Soil Management Plan for Easement* prepared by Gove Environmental Services (Attachment A-1).

If a suitable on-site location is not available, off-site disposal may be required. The Contractor shall identify an appropriate off-site reuse or disposal facility and submit the facility name and location to Eversource for review and approval. GEI's pre-characterization data may be sufficient to meet acceptance criteria for offsite reuse, recycling or disposal. If required by the selected reuse, recycling or disposal location, additional characterization for waste profiling of Project Area soil may be performed in-situ or from excavated or stockpiled material.

Based on the proposed Project Area trench dimensions of 5-feet wide by up to 8-feet-deep and 1,600-feet-long, a total of approximately 1,925 cubic yards of soil may be generated during trenching activities on Frink Farm. The new underground duct bank for the transmission line must be covered with at least 4 feet of native material. We have estimated that up to approximately 1,235 cubic yards of soil may be reused within the trench as cover as cover fill and that approximately 690 cubic yards of excess soil will be available for onsite reuse in other areas of the Property.

5. Soil Excavation

Excavated material shall be handled in general accordance with *The New Hampshire Code of Administrative Rules, Chapter Env-Or 600 - Contaminated Site Management* (Env-Or-600) and all other applicable federal, state, and local laws, regulations, and bylaws.

- **Materials Management Area:** If excavated materials are to be stored or stockpiled in the Project Area, an Excavated Material Management Area will be established by the contractor and approved by Eversource, ensuring it is in accordance with NHDES Env-Or 611.05(b). The Materials Management Area shall be within the Eversource Project Area.
- **Dust Monitoring:** As needed, the contractor shall employ control measures to minimize airborne particulates during excavation or soil management (e.g. water sprays, mists, etc.).
- **Offsite Transport and Documentation (If Necessary):** If excess soil cannot be placed on-site, the Contractor shall select a location for off-site reuse and submit to Eversource for approval. Excess excavated material shall be loaded and transported to an appropriate off-site reuse, recycling or

disposal location. Person(s) transporting the excavated materials shall be licensed and permitted to transport such material in state(s) having jurisdiction. Trailers used for transport shall have covers to prevent dust blow-off.

The contractor shall prepare disposal documentation and shall provide Eversource with material tracking and disposal records and certifications. Project documentation shall be maintained, including accurate records of material tracking, disposal transportation manifests (e.g., Straight BOL), and if necessary, additional environmental testing required by the receiving location.

6. Dewatering

- **Groundwater Pre-characterization and Classification:** GEI tested groundwater for PFOA and PFOS in September 2016 and June 2017. Groundwater testing results indicated the following:
 - PFOA and PFOS were not detected in B101(MW) in September 2016. PFOA and PFOS were detected in B101(MW) in June 2017 but at concentrations below the NH AGQS of 0.07 µg/L.
 - PFOA and PFOS were detected in B102(MW) in both September 2016 and June 2017 but at concentrations below the NH AGQS of 0.07 µg/L.
 - PFOA was not detected in B103(MW). PFOS was detected in B103(MW) but at concentrations below the NH AGQS of 0.07 µg/L.

Prior to the start of construction, additional groundwater samples will be collected, if possible, from B101(MW), B102(MW), and B103(MW), to assess site conditions at the time of construction.

- **Groundwater Management Stations 496+75 to 498+00 and 500+00 to 511+00 – On-Site Recharge:** Based on the laboratory analytical results and estimates of dewatering rates, groundwater generated during excavation dewatering from Stations 496+75 to 498+00 and 500+00 to 511+00 is acceptable for recharge within the Project Area. This option will be refined, as necessary, based on the ASN from Pease and input from NHDES. Additionally, Eversource will acquire a Groundwater Discharge Permit for portions of the project where it is required by the ASN or by NHDES. Based on our discussion with NHDES, we understand that Groundwater Discharge Permits only need to be acquired for areas located in Groundwater Management Zones (GMZs) or where AGQS are exceeded. The contractor's proposed method of recharge and locations must be approved by Eversource. All recharge areas must be within the Project Area.

GEI conducted hydraulic conductivity testing and calculated expected dewatering rates of groundwater within the trench. The estimated dewatering rates are as follows:

- Near B101(MW): Approximately 45 to 82 gpd during a low water condition and approximately 486 to 770 gpd during a high groundwater condition.
- Near B102(MW): Approximately 104 to 187 gpd during a low groundwater condition and approximately 942 to 1466 gpd during a high groundwater condition.
- Near B103: Based on the soil encountered in B103(MW), we estimate the dewatering rates near B103(MW) will likely be between the estimated ranges for B101(MW) and B102(MW). The trench near B103(MW) may also be dry if construction takes place during low groundwater conditions similar August and September of 2017.

Our calculations are based on the limited geologic information observed during installation of B101(MW) and B102(MW). Actual dewatering rates may be higher or lower depending on site-specific and seasonal conditions.

The option to recharge is based on limited site data collected during GEI's 2016 and 2017 investigations which indicated that dewatering rates may be low and the groundwater does not exceed the NH AGQS of 0.07 µg/L. Geologic conditions between the borings may vary significantly, which could result in zones of higher permeability (e.g. sand seams) and higher dewatering rates. In addition, groundwater measurements during our investigation were collected during low groundwater (i.e., drought) conditions in the area. A significant rise in the groundwater table could increase the actual required dewatering rates. If actual dewatering rates are higher than anticipated, onsite recharge may not be feasible.

Alternative Groundwater Management Options Stations 496+75 to 498+00 and 500+00 to 511+00

If the quantity of groundwater to be managed exceeds the capacity of onsite recharge, other potential groundwater management options may be used with approval by Eversource. These options include:

- **On-Site Surface Water Discharge:** On-site surface water discharge would require use of a water treatment system, including equipment such as fractionation (frac) tanks and carbon units, to adequately treat the groundwater for contaminants before discharging into Knight's Brook. Since groundwater did not exceed the AGQS for PFOA/PFOS, it may be possible to discharge dewatering effluent into Knight's Brook under a NPDES Dewatering General Permit (DGP) with minimal treatment. Additional water testing for NPDES DGP requirements and approval from NHDES, and treatment for, at a minimum, total suspended solids (TSS) would be necessary to discharge to Knight's Brook. If, based on NHDES requirements or NPDES DGP testing results, a NPDES DGP is not appropriate, a NPDES Remediation General Permit (RGP) would likely be required to discharge to Knight's Brook. Additional water treatment requirements would also likely apply.
- **Off-site Treatment and Recharge at Pease:** Dewatering effluent may be collected in a tanker truck or other appropriate containers, and transported off-site for treatment and recharge at Pease. Pease currently operates a groundwater treatment system at Site 8 that treats and recharges PFOA and PFOS contaminated groundwater. If Pease is selected for off-site treatment, the Contractor shall coordinate with Pease for accepting and treating the groundwater collected from the Project Area including obtaining any required permits.
- **Off-Site Disposal:** If on-site recharge or treatment or offsite water treatment at Pease is not feasible, the contractor shall identify an appropriate off-site groundwater disposal method and facility. Dewatering effluent may be pumped into a tanker truck or other appropriate containers, and transported off-site to the selected facility. All receiving facilities must be pre-approved by Eversource. No excess effluent may be recharged or disposed of at an uncontrolled location.

Groundwater Management Stations 498+00 to 500+00

Based on the surface water laboratory analytical results, groundwater encountered during excavation of the trench may contain groundwater with concentrations of PFCs that exceed the NH AGQS of 0.07 µg/L. As discussed below, surface water will be diverted during construction. Once below the sediment surface, dewatering effluent will be managed using one or both of the following options:

- **Off-site Treatment and Recharge at Pease:** Dewatering effluent will be collected in a tanker truck or other appropriate containers, and transported off-site for treatment and recharge at Pease. Pease currently operates a groundwater treatment system at Site 8 that treats and recharges PFOA and PFOS contaminated groundwater. If Pease is selected for off-site treatment, the Contractor shall coordinate with Pease for accepting and treating the groundwater collected from the Project Area including obtaining any required permits.
- **On-Site Surface Water Discharge:** On-site surface water discharge would require use of a water treatment system, including equipment such as fractionation (frac) tanks and carbon units, to adequately treat the groundwater for contaminants before discharging into Knight's

Brook. Discharge of dewatering effluent into Knight's Brook would be performed under either a NPDES DGP or RGP based on the results of additional groundwater testing as follows:

- If the results of groundwater testing indicate that it is possible to discharge dewatering effluent into Knight's Brook under a NPDES DGP, Eversource will obtain approval from NHDES to treat dewatering effluent for, at a minimum, total suspended solids (TSS) prior to discharge to Knight's Brook.
- If, based on NHDES requirements or the groundwater testing results, a NPDES DGP is not appropriate, a NPDES RGP would likely be required to discharge to Knight's Brook and additional water treatment requirements would also likely apply.

Alternative Groundwater Management Options Stations 498+00 to 500+00

If the quantity of groundwater to be managed exceeds the capacity of onsite recharge, other potential groundwater management options may be used with approval by Eversource. These options include:

- **Off-Site Disposal:** If on-site recharge or treatment or offsite water treatment at Pease is not feasible, the contractor shall identify an appropriate off-site groundwater disposal method and facility. Dewatering effluent may be pumped into a tanker truck or other appropriate containers, and transported off-site to the selected facility. All receiving facilities must be pre-approved by Eversource. No excess effluent may be recharged or disposed of at an uncontrolled location.
- **Surface Water Pre-characterization and Classification:** Surface water testing from September 2016 indicated that PFOA and PFOS were detected in sample SW1 from Knight's Brook tributary at 0.842 µg/L and 2.91 µg/L, respectively. The total PFOA/PFOS concentration was 3.752 µg/L. Both the individual and total concentrations exceed the NH AGQS of 0.07 µg/L.

We understand that Knight's Brook tributary will be diverted during construction in a manner that does not produce excess water or require additional water management, treatment, or offsite disposal. However, if excess water is generated, the contractor shall propose methods of treatment or disposal of the surface water for approval by Eversource.

Attachments:

Fig. 1 – Site Location Map


Fig. 2 – Project Area Plan

Attachment A-1 – Gove Environmental Services Soil Management Plan

CRC/MWS/JRA:jam

B:\Working\EVERSOURCE\1607530 - EVS-SRP NH\01_ADMIN\Soil and GW Mgmt Plan 06-29-2017\App A Frink Soil and GW\A Soil and GW Management Plan\A - Soil and GW Management Plan rev 06_29_2017.docx

Figures



This Image from U.S.G.S. Topographic 7.5 Minute Series
 Portsmouth, NH - ME Quadrangle, 1981.
 Datum is National Geodetic Vertical Datum of 1929 (NGVD29).
 Contour Interval is 20 Feet.



Soil and Water Management Plan
 Darius Frink Farm
 Newington, New Hampshire
 Eversource Energy
 Manchester, New Hampshire



SITE LOCATION MAP


Project 1607530

June 2017

Fig. 1

Attachment A-1

Gove Environmental Services Soil Management Plan



August 30, 2016

SOIL MANAGEMENT PLAN FOR EASEMENT
FRINK FARM, NIMBLE HILL ROAD, NEWINGTON, NH

- 1- Meeting with contractor, prior to construction, to discuss handling of soil.
- 2- Concept is to segregate the topsoil (A horizon) from the subsoil (B horizon) from the substratum (C horizon). The natural soil profile is a topsoil over a subsoil over a substratum. The intent is to replicate the natural soil profile when the excavation in the field is to be restored.
- 3- A qualified person will be on site during the excavation of the line to identify the soil horizons for the contractor.
- 4- The contractor, during the course of the excavation, shall segregate the topsoil, segregate the subsoil and segregate the substratum such that they are individually stock piled and not intermixed.
- 5- At 25-foot intervals along the trench in the field, the depth of the topsoil, subsoil and substratum shall be recorded as a basis for replicating the soil profile during restoration.
- 6- After the utility line is placed, with appropriate stone material around it, the substratum shall be placed and slightly compacted up the depth of the bottom of the subsoil layer.
- 7- The subsoil shall be placed into the trench, over the substratum layer, up to the depth of the bottom of the topsoil layer. Care will be taken to remove any open voids, but shall not compact the subsoil layer.
- 8- The topsoil shall be placed over the subsoil, mounded 2 inches above the natural grade on either side of the trench to allow for natural settling. Care will be taken to remove any open voids, but shall not compact the topsoil layer.
- 9- The topsoil shall be seeded with a seed mix recommended by the Rockingham County Conservation District and mulched with straw.
- 10- Areas that were used as stockpile areas will have the stockpiled material removed to expose the topsoil layer, scarified to remove compaction, and shall be seeded and mulched as specified in 9.
- 11- Excess substratum/subsoil soil material shall be removed from the field. Excess topsoil shall be spread evenly in the easement area in the stock pile areas and seeded and mulched as noted in 9.
- 12 – Monitor success of seeding and reseed as necessary.

Compiled by Jim Gove, President of Gove Environmental Services, Inc.
GES Project Number 2015138

Appendix B

Boring Logs


BORING INFORMATION		BORING B101 PAGE 1 of 1
LOCATION: West end of field at Frink Farm		
GROUND SURFACE EL. (ft): NM	DATE START/END: 8/26/2016 - 8/26/2016	
VERTICAL DATUM: NA	DRILLING COMPANY: Drilex Environmental	
TOTAL DEPTH (ft): 8.0	DRILLER NAME: J Jalutkewicz	
LOGGED BY: C Conti	RIG TYPE: CME 45	

DRILLING INFORMATION		
HAMMER TYPE: Automatic	CASING I.D./O.D.: 4.25 inch/ 8 inch	CORE BARREL TYPE: NA
AUGER I.D./O.D.: NA / NA	DRILL ROD O.D.: _____	CORE BARREL I.D./O.D.: NA / NA
DRILLING METHOD: Hollow Stem Auger		
WATER LEVEL DEPTHS (ft): Not Encountered		

ABBREVIATIONS:

Pen = Penetration Length	S = Split Spoon Sample	Qp = Pocket Penetrometer Strength	NA = Not Applicable Not Measured
Rec = Recovery Length	C = Core Sample	Sv = Pocket orvane Shear Strength	Blows per 6 in 140-lb hammer falling
RQD = Rock Quality Designation	U = Undisturbed Sample	LL = Liquid Limit	30 inches to drive a 2-inch-O D
= Length of Sound Cores > 4 in / Pen %	SC = Sonic Core	P = Plasticity Index	split spoon sampler
WOR = Weight of Rods	DP = Direct Push Sample	P D = Photoionization Detector	
WOH = Weight of Hammer	HSA = Hollow-Stem Auger	D / O D = Inside Diameter/Outside Diameter	

Elev. (ft)	Depth (ft)	Sample Information				Drilling Remarks/ Field Test Data	Layer Name	Soil and Rock Description
		Sample No.	Depth (ft)	Pen./Rec. (n)	Blows per 6 in. or RQD			
		S1	0 to 2	24/18	3 4 4 6	S1= 32.5 ppm	SLT	S1: SILT WITH SAND (ML); ~90% nonplastic fines, ~10% fine sand, gray, dry, roots.
		S2	2 to 4	24/20	6 6 5 5	S2= 7.0 ppm		S2: LEAN CLAY WITH SAND (CL); ~90% low plasticity fines, ~10% mostly fine sand, gray. Moist in bottom 6 inches.
	5	S3	4 to 6	24/21	1 2 2 2	S3= 5.6 ppm	CLAY	S3: Similar to S2. Wet starting at ~4.5 to 5 feet. Some reddish orange mottling.
		S4	6 to 8	24/17	3 3 2 1	S4= 4.6 ppm		S4: Similar to S2. Gray light brown, wet, some mottling with reddish orange.
	10							Bottom of boring at ~8 feet. Installed monitoring well.
	15							
	20							

NOTES: Samples collected B101(S1-S2) composite and B101(S3-S4) composite	PROJECT NAME: Eversource New Hampshire Seacoast Reliability Project CITY/STATE: Newington NH GEI PROJECT NUMBER: 1607530	
--	---	---

GEI WOBURN STD 1-LOCATION-LAYER NAME EYS NH_SRP.GPJ_GEI DATA TEMPLATE 2011.GDT 8/29/16


BORING INFORMATION		BORING B102 PAGE 1 of 1
LOCATION: Middle of field at Frink Farm	DATE START/END: 8/26/2016 - 8/26/2016	
GROUND SURFACE EL. (ft): NM	DRILLING COMPANY: Drilrex Environmental	
VERTICAL DATUM: NA	DRILLER NAME: J Jalutkewicz	
TOTAL DEPTH (ft): 7.5	RIG TYPE: CME 45	
LOGGED BY: C Conti		

DRILLING INFORMATION		
HAMMER TYPE: Automatic	CASING I.D./O.D.: 4.25 inch/ 8 inch	CORE BARREL TYPE: NA
AUGER I.D./O.D.: NA / NA	DRILL ROD O.D.:	CORE BARREL I.D./O.D. NA / NA
DRILLING METHOD: Hollow Stem Auger		
WATER LEVEL DEPTHS (ft): Not Encountered		

ABBREVIATIONS:

Pen = Penetration Length	S = Split Spoon Sample	Qp = Pocket Penetrometer Strength	NA NM = Not Applicable Not Measured
Rec = Recovery Length	C = Core Sample	Sv = Pocket orvane Shear Strength	Blows per 6 in 140-lb hammer falling
RQD = Rock Quality Designation	U = Undisturbed Sample	LL = Liquid Limit	30 inches to drive a 2-inch-O D
= Length o Sound Cores > 4 in / Pen %	SC = Sonic Core	P = Plasticity Index	split spoon sampler
WOR = Weight o Rods	DP = Direct Push Sample	P D = Photoionization Detector	
WOH = Weight o Hammer	HSA = Hollow-Stem Auger	D / O D = Inside Diameter/Outside Diameter	

Elev. (ft)	Depth (ft)	Sample Information				Drilling Remarks/ Field Test Data	Layer Name	Soil and Rock Description
		Sample No.	Depth (ft)	Pen./Rec. (n)	Blows per 6 in. or RQD			
		S1	0 to 2	24/14	3 3 5 5	S1= 5.6 ppm	SILT	S1: SILT WITH SAND (ML); ~85% nonplastic fines, ~15% mostly fine sand, light brown to gray, roots.
		S2	2 to 4	24/20	8 9 10 10	S2= 5.1 ppm		S2: SILT (ML); ~95% low plasticity fines, ~5% fine sand, gray.
	5	S3	4 to 6	24/19	2 2 2 2	S3= 5.4 ppm	CLAY	S3: LEAN CLAY WITH SAND (CL); ~85% low plasticity fines, ~15% mostly fine sand, brown gray. Wet at 5 feet with 2" seam of fine sand at ~ 5 feet. Increasing fine sand with depth.
		S4	6 to 6.8	9/9	18 55/3"	S4= 5.1 ppm Weathered rock ntp. Auger refusal at 7.5 feet.		S4: SANDY LEAN CLAY (CL); ~75% low plasticity fines, ~25% mostly fine sand, light brown gray, wet, rock ntp.
	10							Bottom of boring @ 7.5 feet. Installed monitoring well. Rock shaled, bottom of screen at 7 feet.
	15							
	20							

NOTES: Samples collected B102(S1-S2) composite and B102 (S3-S4) composite	PROJECT NAME: Eversource New Hampshire Seacoast Reliability Project CITY/STATE: Newington NH GEI PROJECT NUMBER: 1607530	
---	---	---

GEI WOBURN STD 1-LOCATION-LAYER NAME EYS NH_SRP.GPJ_GEI DATA TEMPLATE 2011.GDT 8/29/16

BORING INFORMATION		BORING B103 PAGE 1 of 1
LOCATION: East end of field Frink Farm		
GROUND SURFACE EL. (ft): <u>NM</u>	DATE START/END: <u>8/26/2016 - 8/26/2016</u>	
VERTICAL DATUM: <u>NA</u>	DRILLING COMPANY: <u>Drilrex Environmental</u>	
TOTAL DEPTH (ft): <u>8 0</u>	DRILLER NAME: <u>J Jalutkewicz</u>	
LOGGED BY: <u>C Conti</u>	RIG TYPE: <u>CME 45</u>	

DRILLING INFORMATION		
HAMMER TYPE: <u>Automatic</u>	CASING I.D./O.D.: <u>4 25 inch/ 8 inch</u>	CORE BARREL TYPE: <u>NA</u>
AUGER I.D./O.D.: <u>NA / NA</u>	DRILL ROD O.D.: _____	CORE BARREL I.D./O.D. <u>NA / NA</u>
DRILLING METHOD: <u>Hollow Stem Auger</u>		
WATER LEVEL DEPTHS (ft): <u>Not Encountered</u>		

ABBREVIATIONS:

Pen = Penetration Length	S = Split Spoon Sample	Qp = Pocket Penetrometer Strength	NA NM = Not Applicable Not Measured
Rec = Recovery Length	C = Core Sample	Sv = Pocket orvane Shear Strength	Blows per 6 in 140-lb hammer falling
RQD = Rock Quality Designation	U = Undisturbed Sample	LL = Liquid Limit	30 inches to drive a 2-inch-O D
= Length o Sound Cores > 4 in / Pen %	SC = Sonic Core	P = Plasticity Index	split spoon sampler
WOR = Weight o Rods	DP = Direct Push Sample	P D = Photoionization Detector	
WOH = Weight o Hammer	HSA = Hollow-Stem Auger	D / O D = Inside Diameter/Outside Diameter	

Elev. (ft)	Depth (ft)	Sample Information				Drilling Remarks/ Field Test Data	Layer Name	Soil and Rock Description
		Sample No.	Depth (ft)	Pen./Rec. (n)	Blows per 6 in. or RQD			
		S1	0 to 2	24/13	3 5 8 8	S1= 0.3 ppm	SILT	S1: SILT WITH SAND (ML); ~70% nonplastic fines, ~25% mosty fine sand, ~5% gravel to 3/4", light brown, dry, some roots n top 3".
		S2	2 to 2.9	11/11	18 65/5"	S2= 0.5 ppm		S2: Similar to S1, no roots.
	5	S3	4 to 6	24/13	18 19 25 32	Cobble from 3 4 feet. S3= 0.6 ppm	GRAVEL	S3: WIDELY GRADED GRAVEL WITH SILT AND SAND (GW GM); ~75% fine to coarse gravel, ~15% mosty fine sand, ~10% nonplastic fines, brown.
		S4			55 30 80/7"	S4= 0.8 ppm		S4: WIDELY GRADED GRAVEL WITH SILT AND SAND (GW GM); ~60% fine to coarse gravel, ~30% fine to coarse sand, ~10% nonplastic fines, brown to reddish brown.
	10					Refusal on cobble/ weathered rock. Augered to 8 feet.		Bottom of boring at 8 feet. Installed monitoring well.
	15							
	20							

NOTES: Samples collected B103(S1-S2) composite and B103 (S3-S4) composite	PROJECT NAME: Eversource New Hampshire Seacoast Reliability Project CITY/STATE: Newington NH GEI PROJECT NUMBER: 1607530
---	---



GEI WOBURN STD 1-LOCATION-LAYER NAME EYS NH_SRP.GPJ_GEI DATA TEMPLATE 2011.GDT 8/29/16

BORING

HA1

PAGE 1 of 1

BORING INFORMATION

LOCATION: East side of tributary
 GROUND SURFACE EL. (ft): NM DATE START/END: 4/7/2017 - 4/7/2017
 VERTICAL DATUM: NM DRILLING COMPANY: GE Consultants
 TOTAL DEPTH (ft): 6.5 DRILLER NAME: M Greer J Wolpert
 LOGGED BY: M Greer RIG TYPE: Hand Auger

DRILLING INFORMATION

HAMMER TYPE: NA CASING I.D./O.D.: NA / NA CORE BARREL TYPE: NA
 AUGER I.D./O.D.: 2.5 inch / 2.6 inch DRILL ROD O.D.: NM CORE BARREL I.D./O.D.: NA / NA
 DRILLING METHOD: Auger
 WATER LEVEL DEPTHS (ft): Not measured

ABBREVIATIONS: Pen = Penetration Length S = Split Spoon Sample Qp = Pocket Penetrometer Strength NA NM = Not Applicable Not Measured
 Rec = Recovery Length C = Core Sample Sv = Pocket or vane Shear Strength Blows per 6 in 140-lb hammer falling
 RQD = Rock Quality Designation U = Undisturbed Sample LL = Liquid Limit 30 inches to drive a 2-inch-O D
 = Length of Sound Cores > 4 in / Pen % SC = Sonic Core P = Plasticity Index split spoon sampler
 WOR = Weight of Rods DP = Direct Push Sample P D = Photoionization Detector
 WOH = Weight of Hammer HSA = Hollow-Stem Auger D / O D = Inside Diameter/Outside Diameter

Elev. (ft)	Depth (ft)	Sample Information				Drilling Remarks / Field Test Data	Layer Name	Soil and Rock Description
		Sample No.	Depth (ft)	Pen./Rec. (n)	Blows per 6 in. or RQD			
		S1	1 to 2	12/12		OL	S1 (0 1'): ORGANIC SOIL (OL); ~85% low plasticity fines, ~15% fine sand, dark brown, roots in top 6 inches, wet.	
		S2	2 to 3	12/12		ML	S2 (1 1.5'): Same as S1(0 1'), no roots.	
		S3	3 to 4	12/12			S2(1.5 2'): SANDY SILT (ML); ~70% low plasticity fines, ~30% fine sand, gray, wet.	
		S4	4 to 5	12/12		CLAY	S3: Same as above.	
		S5	5 to 6	12/12			S4: LEAN CLAY (CL); ~95% medium plasticity fines, ~5% fine sand, gray, wet.	
		S6	6 to 6.5	12/12			S5: Same as S4, mottled orange, some roots.	
		S7	6.5 to 7	6/6			S6: Same as S4, mottled orange, some roots.	
							S7: Same as S4, mottled orange, some roots.	
							Bottom of boring at about 6.5 feet. Backfilled with cuttings.	

NOTES:

PROJECT NAME: Eversource New Hampshire Seacoast Reliability Project
 CITY/STATE: Newington NH
 GEI PROJECT NUMBER: 1607530



GEI WOBURN, S.D. 14-LOCA ON-LAYER NAME: EVS NH SRP GPJ 6/21/17

BORING

HA2

PAGE 1 of 1

BORING INFORMATION

LOCATION: West side of tributary
 GROUND SURFACE EL. (ft): NM DATE START/END: 4/7/2017 - 4/7/2017
 VERTICAL DATUM: NM DRILLING COMPANY: GE Consultants
 TOTAL DEPTH (ft): 6.0 DRILLER NAME: M Greer J Wolpert
 LOGGED BY: M Greer RIG TYPE: Hand Auger

DRILLING INFORMATION

HAMMER TYPE: NA CASING I.D./O.D.: NA / NA CORE BARREL TYPE: NA
 AUGER I.D./O.D.: 2.5 inch / 2.6 inch DRILL ROD O.D.: NM CORE BARREL I.D./O.D.: NA / NA
 DRILLING METHOD: Auger
 WATER LEVEL DEPTHS (ft): Not measured

ABBREVIATIONS: Pen = Penetration Length S = Split Spoon Sample Qp = Pocket Penetrometer Strength NA NM = Not Applicable Not Measured
 Rec = Recovery Length C = Core Sample Sv = Pocket or vane Shear Strength Blows per 6 in 140-lb hammer falling
 RQD = Rock Quality Designation U = Undisturbed Sample LL = Liquid Limit 30 inches to drive a 2-inch-O D
 = Length of Sound Cores > 4 in / Pen % SC = Sonic Core P = Plasticity Index split spoon sampler
 WOR = Weight of Rods DP = Direct Push Sample P D = Photoionization Detector
 WOH = Weight of Hammer HSA = Hollow-Stem Auger D / O D = Inside Diameter/Outside Diameter

Elev. (ft)	Depth (ft)	Sample Information				Drilling Remarks / Field Test Data	Layer Name	Soil and Rock Description
		Sample No.	Depth (ft)	Pen./Rec. (n)	Blows per 6 in. or RQD			
						OL	S1(0.05'): ORGANIC SOIL (OL); ~85% organic fines, ~15% fine sand, dark brown, roots, wet.	
		S1	1 to 2	12/12		SANDY SILT	S1(0.5 1'): SANDY SILT (ML); ~80% organic fines, ~20% fine sand, no roots, organic mottling, blue, wet.	
		S2	2 to 3	12/12			S2: same as S1(0.5 1'). S3: same as S1(0.5 1').	
		S3	3 to 4	12/12				
		S4	4 to 5	12/12		SAND	S4(3.35'): same as S1(0.5 1'). S4(3.5 4'): NARROWLY GRADED SAND WITH SILT (SP SM); ~80% mostly fine sand, ~20% organic fines, gray, wet.	
		S5	5 to 6	12/12			S5: same as S4(3.5 4').	
		S6	6 to 7	12/12		CLAY	S6: LEAN CLAY (CL); ~95% medium plastic fines, ~5% fine sand, gray, mottled, wet.	
							Bottom of boring at about 6 feet. Backfilled with cuttings.	

NOTES:

PROJECT NAME: Eversource New Hampshire Seacoast Reliability Project
 CITY/STATE: Newington NH
 GEI PROJECT NUMBER: 1607530



GEI WOBURN, S. D. 14-LOCA ON-LAYER NAME: EVS NH SRP GPJ 6/21/17

BORING LOG NO. F107-109

PROJECT: Seacoast Reliability Project

CLIENT: Eversource Energy

SITE: Portsmouth, Newington,
Durham, and Madbury, New Hampshire

GRAPHIC LOG	LOCATION See Exhibit A-2 Latitude 43 10076522° Longitude -70 83778978° Surface Elev 43 284 (Ft) ELEVATION (Ft)	DEPTH (Ft)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	RECOVERY (n)	FIELD TEST RESULTS	ROD (%)	Core Rate (min/ft)
	3 inches of forest oam, roots 6 inches of subso	41.5			12	4 7 11 12 N=18		
2.0	SILTY SAND (SM) , ght brown to wh te, des ccated, med um dense	40			16	7 9 8 8 N=17		
3.5	SILT WITH SAND (ML) , o ve brown, des ccated				24	6 5 7 8 N=12		
9.0	LEAN CLAY (CL) , gray, very soft	34.5			24	woh 1 1 woh N=2		
24.0		19.5			24	wor/12" woh/12"		
25.0	SILTY SAND (SM) , w th fractured grave , brown, very dense, (GLACIAL TILL) Ro er b t to 29 feet	18.5			18	18 18 32 21 N=50		
29.0	Run 1 Hard, s ght y weathered, gray, aphan t c PHYLLITE, moderate y d pp ng, c ose jo nts EXETER DIORITE FORMATION	14.5			49		25	
	Run 2 Sm ar Note: Numerous mechan ca breaks due to jamm ng ns de the barre				41		13	

Stratification lines are approximate n-situ the transition may be gradual

Hammer Type Automatic

Advancement Method 3-inch casing	See Exhibit A-3 for description of field procedures See Appendix B for description of laboratory procedures and additional data (if any) See Appendix C for explanation of symbols and abbreviations	Notes
Abandonment Method Boring backfilled with soil cuttings upon completion		
WATER LEVEL OBSERVATIONS No free water observed	77 Sundial Ave Ste 401W Manchester NH	Boring Started 8/26/2016 Boring Completed 8/26/2016 Drill Rig Diedrich D-50 turbo Driller Drilex Project No J1165081 Exhibit A-31

H.S.BORING LOG S NO VAL D F SEPARA ED FROM OR GINAL REPOR GEO SMAR LOG-NO WELL J1165081 GPJ

BORING LOG NO. F107-109

PROJECT: Seacoast Reliability Project

CLIENT: Eversource Energy

SITE: Portsmouth, Newington,
Durham, and Madbury, New Hampshire

GRAPHIC LOG	LOCATION See Exhibit A-2 Latitude 43 10076522° Longitude -70 83778978° Surface Elev 43 284 (Ft) ELEVATION (Ft)	DEPTH (Ft)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	RECOVERY (n)	FIELD TEST RESULTS	ROD (%)	Core Rate (min/ft)
39.0	4.5	41						
Boring Terminated at 39 Feet								
Stratification lines are approximate n-situ the transition may be gradual Hammer Type Automatic								

Advancement Method 3-inch casing	See Exhibit A-3 for description of field procedures See Appendix B for description of laboratory procedures and additional data (if any)	Notes
Abandonment Method Boring backfilled with soil cuttings upon completion	See Appendix C for explanation of symbols and abbreviations	
WATER LEVEL OBSERVATIONS No free water observed		Boring Started 8/26/2016 Boring Completed 8/26/2016
		Drill Rig Diedrich D-50 turbo Driller Drilex
		Project No J1165081 Exhibit A-31



H.S.BORING LOG S.NO. VAL.D.F.SEPARATED FROM ORIGINAL REPORT GEO SMAR LOG-NO WELL J1165081 GPJ

Groundwater Well Installation Log

B101(MW)

Project Eversource New Hampshire Seacoast Reliability Project
City / Town Newington, NH
Client Eversource
Contractor Drilx Environmental
Driller J. Jalutkewicz **GEI Rep.** C. Conti

GEI Proj. No. 1607530
Location East end of field at Frink Farm
Install Date 8/26/2016

Survey


Datum: _____

Ground Elevation:

Date	Time	Distance to ▼ below top of riser pipe

Silt

Clay



- Length of Surface Casing above Ground 3.3'
- Dist. Top of Surf. Casing to Top of Riser Pipe 0.18'
- Type and Thickness of Seal around Surface Casing NA
- ID of Surface Casing 4"
- Type of Surface Casing _____
- Depth Bottom of Surface Casing 1.7
- ID and OD of Riser Pipe 2.0"/2.5"
- Type of Riser Pipe Sch. 40 PVC
- Type of Backfill around Riser Pipe NA
- Diameter of Borehole 8"
- Depth Top of Seal NA
- Type of Seal Med. Bentonite Chips
- Depth Bottom of Seal 1.5'
- Depth Top of Screened Section 2'
- Type of Screen Sch. 40 PVC
- Description of Screen Openings 0.010 Slotted
- ID and OD of Screened Section 2.0"/2.5"
- Type of Filter Material Sand Type 0
- Depth Bottom of Screened Section 7.7'
- Depth Bottom of Silt Trap 8'
- Depth Bottom of Filter Material NA
- Depth Top of Seal NA
- Type of Seal NA
- Depth Bottom of Seal NA
- Type of Backfill below Filter Material NA
- Bottom of Borehole 8'

Notes:



Groundwater Well Installation Log

B102(MW)

Project Eversource New Hampshire Seacoast Reliability Project
City / Town Newington, NH
Client Eversource
Contractor Drilx Environmental
Driller J. Jalutkewicz **GEI Rep.** C. Conti


GEI Proj. No. 1607530
Location Middle of field at Frink Farm
Install Date 8/26/2016

Survey

Datum: _____

Ground Elevation:

Date	Time	Distance to ▼ below top of riser pipe



Length of Surface Casing above Ground	3.1'
Dist. Top of Surf. Casing to Top of Riser Pipe	0.2'
Type and Thickness of Seal around Surface Casing	NA
ID of Surface Casing	4.25"
Type of Surface Casing	Steel guard pipe
Depth Bottom of Surface Casing	1.9
ID and OD of Riser Pipe	2.0"/2.5"
Type of Riser Pipe	Sch. 40 PVC
Type of Backfill around Riser Pipe	NA
Diameter of Borehole	8"
Depth Top of Seal	NA
Type of Seal	Med. Bentonite Chips
Depth Bottom of Seal	1.5'
Depth Top of Screened Section	2'
Type of Screen	Sch. 40 PVC
Description of Screen Openings	0.010 Slotted
ID and OD of Screened Section	2.0"/2.5"
Type of Filter Material	Sand Type 0
Depth Bottom of Screened Section	6.7'
Depth Bottom of Silt Trap	7'
Depth Bottom of Filter Material	NA
Depth Top of Seal	NA
Type of Seal	NA
Depth Bottom of Seal	NA
Type of Backfill below Filter Material	NA
Bottom of Borehole	7'

Notes:



Groundwater Well Installation Log

B103(MW)

Project Eversource New Hampshire Seacoast Reliability Project
City / Town Newington, NH
Client Eversource
Contractor Drilx Environmental
Driller J. Jalutkewicz **GEI Rep.** C. Conti

GEI Proj. No. 1607530
Location West end of field at Frink Farm
Install Date 8/26/2016

Survey Datum: _____

Ground Elevation:

Date	Time	Distance to ▼ below top of riser pipe

Silt

Gravel

Length of Surface Casing above Ground	Flushmount
Dist. Top of Surf. Casing to Top of Riser Pipe	NA
Type and Thickness of Seal around Surface Casing	NA
ID of Surface Casing	4.25"
Type of Surface Casing	Flushmount
Depth Bottom of Surface Casing	10"
ID and OD of Riser Pipe	2.0"/2.5"
Type of Riser Pipe	Sch. 40 PVC
Type of Backfill around Riser Pipe	NA
Diameter of Borehole	8"
Depth Top of Seal	NA
Type of Seal	Med. Bentonite Chips
Depth Bottom of Seal	1.5'
Depth Top of Screened Section	2'
Type of Screen	Sch. 40 PVC
Description of Screen Openings	0.010 Slotted
ID and OD of Screened Section	2.0"/2.5"
Type of Filter Material	Sand Type 0
Depth Bottom of Screened Section	7.7'
Depth Bottom of Silt Trap	8'
Depth Bottom of Filter Material	NA
Depth Top of Seal	NA
Type of Seal	NA
Depth Bottom of Seal	NA
Type of Backfill below Filter Material	NA
Bottom of Borehole	8'

Notes:



Appendix C

Laboratory Data Reports



ANALYTICAL REPORT

Lab Number:	L1627010
Client:	GEI Consultants 400 Unicorn Park Drive Woburn, MA 01801
ATTN:	Mike Sabulis
Phone:	(781) 721-4114
Project Name:	EVERSOURCE NH SRP
Project Number:	1607530
Report Date:	09/15/16

The original project report/data package is held by Alpha Analytical. This report/data package is paginated and should be reproduced only in its entirety. Alpha Analytical holds no responsibility for results and/or data that are not consistent with the original.

Certifications & Approvals: MA (M-MA086), NY (11148), CT (PH-0574), NH (2003), NJ NELAP (MA935), RI (LAO00065), ME (MA00086), PA (68-03671), VA (460195), MD (348), IL (200077), NC (666), TX (T104704476), DOD (L2217), USDA (Permit #P-330-11-00240).

Eight Walkup Drive, Westborough, MA 01581-1019
508-898-9220 (Fax) 508-898-9193 800-624-9220 - www.alphalab.com



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Alpha Sample ID	Client ID	Matrix	Sample Location	Collection Date/Time	Receive Date
L1627010-01	1607530-B103(S1-S2)	SOIL	NEWINGTON, NH	08/26/16 09:25	08/29/16
L1627010-02	1607530-B103(S3-S4)	SOIL	NEWINGTON, NH	08/26/16 09:55	08/29/16
L1627010-03	1607530-B102(S1-S2)	SOIL	NEWINGTON, NH	08/26/16 10:45	08/29/16
L1627010-04	1607530-B102(S3-S4)	SOIL	NEWINGTON, NH	08/26/16 11:00	08/29/16
L1627010-05	1607530-B101(S1-S2)	SOIL	NEWINGTON, NH	08/26/16 11:45	08/29/16
L1627010-06	1607530-B101(S3-S4)	SOIL	NEWINGTON, NH	08/26/16 12:00	08/29/16

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Case Narrative

The samples were received in accordance with the Chain of Custody and no significant deviations were encountered during the preparation or analysis unless otherwise noted. Sample Receipt, Container Information, and the Chain of Custody are located at the back of the report.

Results contained within this report relate only to the samples submitted under this Alpha Lab Number and meet NELAP requirements for all NELAP accredited parameters unless otherwise noted in the following narrative. The data presented in this report is organized by parameter (i.e. VOC, SVOC, etc.). Sample specific Quality Control data (i.e. Surrogate Spike Recovery) is reported at the end of the target analyte list for each individual sample, followed by the Laboratory Batch Quality Control at the end of each parameter. Tentatively Identified Compounds (TICs), if requested, are reported for compounds identified to be present and are not part of the method/program Target Compound List, even if only a subset of the TCL are being reported. If a sample was re-analyzed or re-extracted due to a required quality control corrective action and if both sets of data are reported, the Laboratory ID of the re-analysis or re-extraction is designated with an "R" or "RE", respectively. When multiple Batch Quality Control elements are reported (e.g. more than one LCS), the associated samples for each element are noted in the grey shaded header line of each data table. Any Laboratory Batch, Sample Specific % recovery or RPD value that is outside the listed Acceptance Criteria is bolded in the report. All specific QC information is also incorporated in the Data Usability format of our Data Merger tool where it can be reviewed along with any associated usability implications. Soil/sediments, solids and tissues are reported on a dry weight basis unless otherwise noted. Definitions of all data qualifiers and acronyms used in this report are provided in the Glossary located at the back of the report.

In reference to questions H (CAM) or 4 (RCP) when "NO" is checked, the performance criteria for CAM and RCP methods allow for some quality control failures to occur and still be within method compliance. In these instances the specific failure is not narrated but noted in the associated QC table. The information is also incorporated in the Data Usability format of our Data Merger tool where it can be reviewed along with any associated usability implications.

Please see the associated ADEx data file for a comparison of laboratory reporting limits that were achieved with the regulatory Numerical Standards requested on the Chain of Custody.

HOLD POLICY

For samples submitted on hold, Alpha's policy is to hold samples (with the exception of Air canisters) free of charge for 21 calendar days from the date the project is completed. After 21 calendar days, we will dispose of all samples submitted including those put on hold unless you have contacted your Client Service Representative and made arrangements for Alpha to continue to hold the samples. Air canisters will be disposed after 3 business days from the date the project is completed.

Please contact Client Services at 800-624-9220 with any questions.

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Case Narrative (continued)


Report Submission

This final report replaces the partial report issued September 6, 2016 and includes the results of all requested analyses.

The analyses of PFOA and PFOS by Method 537 were subcontracted. A copy of the laboratory report is included as an addendum. Please note: This data is only available in PDF format and is not available on Data Merger.

I, the undersigned, attest under the pains and penalties of perjury that, to the best of my knowledge and belief and based upon my personal inquiry of those responsible for providing the information contained in this analytical report, such information is accurate and complete. This certificate of analysis is not complete unless this page accompanies any and all pages of this report.

Authorized Signature:

 Kelly Stenstrom

Title: Technical Director/Representative

Date: 09/15/16

ORGANICS

VOLATILES

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-01
 Client ID: 1607530-B103(S1-S2)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8260C
 Analytical Date: 09/05/16 12:20
 Analyst: BN
 Percent Solids: 93%

Date Collected: 08/26/16 09:25
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by EPA 5035 High - Westborough Lab						
Methylene chloride	ND		ug/kg	610	--	1
1,1-Dichloroethane	ND		ug/kg	92	--	1
Chloroform	ND		ug/kg	92	--	1
Carbon tetrachloride	ND		ug/kg	61	--	1
1,2-Dichloropropane	ND		ug/kg	210	--	1
Dibromochloromethane	ND		ug/kg	61	--	1
1,1,2-Trichloroethane	ND		ug/kg	92	--	1
Tetrachloroethene	ND		ug/kg	61	--	1
Chlorobenzene	ND		ug/kg	61	--	1
Trichlorofluoromethane	ND		ug/kg	300	--	1
1,2-Dichloroethane	ND		ug/kg	61	--	1
1,1,1-Trichloroethane	ND		ug/kg	61	--	1
Bromodichloromethane	ND		ug/kg	61	--	1
trans-1,3-Dichloropropene	ND		ug/kg	61	--	1
cis-1,3-Dichloropropene	ND		ug/kg	61	--	1
1,3-Dichloropropene, Total	ND		ug/kg	61	--	1
1,1-Dichloropropene	ND		ug/kg	300	--	1
Bromoform	ND		ug/kg	240	--	1
1,1,2,2-Tetrachloroethane	ND		ug/kg	61	--	1
Benzene	ND		ug/kg	61	--	1
Toluene	ND		ug/kg	92	--	1
Ethylbenzene	ND		ug/kg	61	--	1
Chloromethane	ND		ug/kg	300	--	1
Bromomethane	ND		ug/kg	120	--	1
Vinyl chloride	ND		ug/kg	120	--	1
Chloroethane	ND		ug/kg	120	--	1
1,1-Dichloroethene	ND		ug/kg	61	--	1
trans-1,2-Dichloroethene	ND		ug/kg	92	--	1
Trichloroethene	ND		ug/kg	61	--	1
1,2-Dichlorobenzene	ND		ug/kg	300	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-01
 Client ID: 1607530-B103(S1-S2)
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 09:25
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by EPA 5035 High - Westborough Lab						
1,3-Dichlorobenzene	ND		ug/kg	300	--	1
1,4-Dichlorobenzene	ND		ug/kg	300	--	1
Methyl tert butyl ether	ND		ug/kg	120	--	1
p/m-Xylene	ND		ug/kg	120	--	1
o-Xylene	ND		ug/kg	120	--	1
Xylenes, Total	ND		ug/kg	120	--	1
cis-1,2-Dichloroethene	ND		ug/kg	61	--	1
1,2-Dichloroethene, Total	ND		ug/kg	61	--	1
Dibromomethane	ND		ug/kg	610	--	1
1,4-Dichlorobutane	ND		ug/kg	610	--	1
1,2,3-Trichloropropane	ND		ug/kg	610	--	1
Styrene	ND		ug/kg	120	--	1
Dichlorodifluoromethane	ND		ug/kg	610	--	1
Acetone	ND		ug/kg	2200	--	1
Carbon disulfide	ND		ug/kg	610	--	1
2-Butanone	ND		ug/kg	610	--	1
Vinyl acetate	ND		ug/kg	610	--	1
4-Methyl-2-pentanone	ND		ug/kg	610	--	1
2-Hexanone	ND		ug/kg	610	--	1
Ethyl methacrylate	ND		ug/kg	610	--	1
Acrylonitrile	ND		ug/kg	240	--	1
Bromochloromethane	ND		ug/kg	300	--	1
Tetrahydrofuran	ND		ug/kg	1200	--	1
2,2-Dichloropropane	ND		ug/kg	300	--	1
1,2-Dibromoethane	ND		ug/kg	240	--	1
1,3-Dichloropropane	ND		ug/kg	300	--	1
1,1,1,2-Tetrachloroethane	ND		ug/kg	61	--	1
Bromobenzene	ND		ug/kg	300	--	1
n-Butylbenzene	ND		ug/kg	61	--	1
sec-Butylbenzene	ND		ug/kg	61	--	1
tert-Butylbenzene	ND		ug/kg	300	--	1
o-Chlorotoluene	ND		ug/kg	300	--	1
p-Chlorotoluene	ND		ug/kg	300	--	1
1,2-Dibromo-3-chloropropane	ND		ug/kg	300	--	1
Hexachlorobutadiene	ND		ug/kg	300	--	1
Isopropylbenzene	ND		ug/kg	61	--	1
p-Isopropyltoluene	ND		ug/kg	61	--	1
Naphthalene	ND		ug/kg	300	--	1
n-Propylbenzene	ND		ug/kg	61	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-01
 Client ID: 1607530-B103(S1-S2)
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 09:25
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Volatile Organics by EPA 5035 High - Westborough Lab						
1,2,3-Trichlorobenzene	ND		ug/kg	300	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	300	--	1
1,3,5-Trimethylbenzene	ND		ug/kg	300	--	1
1,2,4-Trimethylbenzene	ND		ug/kg	300	--	1
trans-1,4-Dichloro-2-butene	ND		ug/kg	300	--	1
Ethyl ether	ND		ug/kg	300	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	97		70-130
Toluene-d8	100		70-130
4-Bromofluorobenzene	98		70-130
Dibromofluoromethane	94		70-130

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-02
 Client ID: 1607530-B103(S3-S4)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8260C
 Analytical Date: 09/05/16 12:47
 Analyst: BN
 Percent Solids: 92%

Date Collected: 08/26/16 09:55
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by EPA 5035 High - Westborough Lab						
Methylene chloride	ND		ug/kg	520	--	1
1,1-Dichloroethane	ND		ug/kg	77	--	1
Chloroform	ND		ug/kg	77	--	1
Carbon tetrachloride	ND		ug/kg	52	--	1
1,2-Dichloropropane	ND		ug/kg	180	--	1
Dibromochloromethane	ND		ug/kg	52	--	1
1,1,2-Trichloroethane	ND		ug/kg	77	--	1
Tetrachloroethene	ND		ug/kg	52	--	1
Chlorobenzene	ND		ug/kg	52	--	1
Trichlorofluoromethane	ND		ug/kg	260	--	1
1,2-Dichloroethane	ND		ug/kg	52	--	1
1,1,1-Trichloroethane	ND		ug/kg	52	--	1
Bromodichloromethane	ND		ug/kg	52	--	1
trans-1,3-Dichloropropene	ND		ug/kg	52	--	1
cis-1,3-Dichloropropene	ND		ug/kg	52	--	1
1,3-Dichloropropene, Total	ND		ug/kg	52	--	1
1,1-Dichloropropene	ND		ug/kg	260	--	1
Bromoform	ND		ug/kg	210	--	1
1,1,2,2-Tetrachloroethane	ND		ug/kg	52	--	1
Benzene	ND		ug/kg	52	--	1
Toluene	ND		ug/kg	77	--	1
Ethylbenzene	ND		ug/kg	52	--	1
Chloromethane	ND		ug/kg	260	--	1
Bromomethane	ND		ug/kg	100	--	1
Vinyl chloride	ND		ug/kg	100	--	1
Chloroethane	ND		ug/kg	100	--	1
1,1-Dichloroethene	ND		ug/kg	52	--	1
trans-1,2-Dichloroethene	ND		ug/kg	77	--	1
Trichloroethene	ND		ug/kg	52	--	1
1,2-Dichlorobenzene	ND		ug/kg	260	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-02
Client ID: 1607530-B103(S3-S4)
Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 09:55
Date Received: 08/29/16
Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by EPA 5035 High - Westborough Lab						
1,3-Dichlorobenzene	ND		ug/kg	260	--	1
1,4-Dichlorobenzene	ND		ug/kg	260	--	1
Methyl tert butyl ether	ND		ug/kg	100	--	1
p/m-Xylene	ND		ug/kg	100	--	1
o-Xylene	ND		ug/kg	100	--	1
Xylenes, Total	ND		ug/kg	100	--	1
cis-1,2-Dichloroethene	ND		ug/kg	52	--	1
1,2-Dichloroethene, Total	ND		ug/kg	52	--	1
Dibromomethane	ND		ug/kg	520	--	1
1,4-Dichlorobutane	ND		ug/kg	520	--	1
1,2,3-Trichloropropane	ND		ug/kg	520	--	1
Styrene	ND		ug/kg	100	--	1
Dichlorodifluoromethane	ND		ug/kg	520	--	1
Acetone	ND		ug/kg	1800	--	1
Carbon disulfide	ND		ug/kg	520	--	1
2-Butanone	ND		ug/kg	520	--	1
Vinyl acetate	ND		ug/kg	520	--	1
4-Methyl-2-pentanone	ND		ug/kg	520	--	1
2-Hexanone	ND		ug/kg	520	--	1
Ethyl methacrylate	ND		ug/kg	520	--	1
Acrylonitrile	ND		ug/kg	210	--	1
Bromochloromethane	ND		ug/kg	260	--	1
Tetrahydrofuran	ND		ug/kg	1000	--	1
2,2-Dichloropropane	ND		ug/kg	260	--	1
1,2-Dibromoethane	ND		ug/kg	210	--	1
1,3-Dichloropropane	ND		ug/kg	260	--	1
1,1,1,2-Tetrachloroethane	ND		ug/kg	52	--	1
Bromobenzene	ND		ug/kg	260	--	1
n-Butylbenzene	ND		ug/kg	52	--	1
sec-Butylbenzene	ND		ug/kg	52	--	1
tert-Butylbenzene	ND		ug/kg	260	--	1
o-Chlorotoluene	ND		ug/kg	260	--	1
p-Chlorotoluene	ND		ug/kg	260	--	1
1,2-Dibromo-3-chloropropane	ND		ug/kg	260	--	1
Hexachlorobutadiene	ND		ug/kg	260	--	1
Isopropylbenzene	ND		ug/kg	52	--	1
p-Isopropyltoluene	ND		ug/kg	52	--	1
Naphthalene	ND		ug/kg	260	--	1
n-Propylbenzene	ND		ug/kg	52	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-02
 Client ID: 1607530-B103(S3-S4)
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 09:55
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Volatile Organics by EPA 5035 High - Westborough Lab						
1,2,3-Trichlorobenzene	ND		ug/kg	260	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	260	--	1
1,3,5-Trimethylbenzene	ND		ug/kg	260	--	1
1,2,4-Trimethylbenzene	ND		ug/kg	260	--	1
trans-1,4-Dichloro-2-butene	ND		ug/kg	260	--	1
Ethyl ether	ND		ug/kg	260	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	99		70-130
Toluene-d8	100		70-130
4-Bromofluorobenzene	98		70-130
Dibromofluoromethane	94		70-130

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-03
 Client ID: 1607530-B102(S1-S2)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8260C
 Analytical Date: 09/05/16 13:13
 Analyst: BN
 Percent Solids: 84%

Date Collected: 08/26/16 10:45
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by EPA 5035 High - Westborough Lab						
Methylene chloride	ND		ug/kg	650	--	1
1,1-Dichloroethane	ND		ug/kg	97	--	1
Chloroform	ND		ug/kg	97	--	1
Carbon tetrachloride	ND		ug/kg	65	--	1
1,2-Dichloropropane	ND		ug/kg	230	--	1
Dibromochloromethane	ND		ug/kg	65	--	1
1,1,2-Trichloroethane	ND		ug/kg	97	--	1
Tetrachloroethene	ND		ug/kg	65	--	1
Chlorobenzene	ND		ug/kg	65	--	1
Trichlorofluoromethane	ND		ug/kg	320	--	1
1,2-Dichloroethane	ND		ug/kg	65	--	1
1,1,1-Trichloroethane	ND		ug/kg	65	--	1
Bromodichloromethane	ND		ug/kg	65	--	1
trans-1,3-Dichloropropene	ND		ug/kg	65	--	1
cis-1,3-Dichloropropene	ND		ug/kg	65	--	1
1,3-Dichloropropene, Total	ND		ug/kg	65	--	1
1,1-Dichloropropene	ND		ug/kg	320	--	1
Bromoform	ND		ug/kg	260	--	1
1,1,2,2-Tetrachloroethane	ND		ug/kg	65	--	1
Benzene	ND		ug/kg	65	--	1
Toluene	ND		ug/kg	97	--	1
Ethylbenzene	ND		ug/kg	65	--	1
Chloromethane	ND		ug/kg	320	--	1
Bromomethane	ND		ug/kg	130	--	1
Vinyl chloride	ND		ug/kg	130	--	1
Chloroethane	ND		ug/kg	130	--	1
1,1-Dichloroethene	ND		ug/kg	65	--	1
trans-1,2-Dichloroethene	ND		ug/kg	97	--	1
Trichloroethene	ND		ug/kg	65	--	1
1,2-Dichlorobenzene	ND		ug/kg	320	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-03
Client ID: 1607530-B102(S1-S2)
Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 10:45
Date Received: 08/29/16
Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by EPA 5035 High - Westborough Lab						
1,3-Dichlorobenzene	ND		ug/kg	320	--	1
1,4-Dichlorobenzene	ND		ug/kg	320	--	1
Methyl tert butyl ether	ND		ug/kg	130	--	1
p/m-Xylene	ND		ug/kg	130	--	1
o-Xylene	ND		ug/kg	130	--	1
Xylenes, Total	ND		ug/kg	130	--	1
cis-1,2-Dichloroethene	ND		ug/kg	65	--	1
1,2-Dichloroethene, Total	ND		ug/kg	65	--	1
Dibromomethane	ND		ug/kg	650	--	1
1,4-Dichlorobutane	ND		ug/kg	650	--	1
1,2,3-Trichloropropane	ND		ug/kg	650	--	1
Styrene	ND		ug/kg	130	--	1
Dichlorodifluoromethane	ND		ug/kg	650	--	1
Acetone	ND		ug/kg	2300	--	1
Carbon disulfide	ND		ug/kg	650	--	1
2-Butanone	ND		ug/kg	650	--	1
Vinyl acetate	ND		ug/kg	650	--	1
4-Methyl-2-pentanone	ND		ug/kg	650	--	1
2-Hexanone	ND		ug/kg	650	--	1
Ethyl methacrylate	ND		ug/kg	650	--	1
Acrylonitrile	ND		ug/kg	260	--	1
Bromochloromethane	ND		ug/kg	320	--	1
Tetrahydrofuran	ND		ug/kg	1300	--	1
2,2-Dichloropropane	ND		ug/kg	320	--	1
1,2-Dibromoethane	ND		ug/kg	260	--	1
1,3-Dichloropropane	ND		ug/kg	320	--	1
1,1,1,2-Tetrachloroethane	ND		ug/kg	65	--	1
Bromobenzene	ND		ug/kg	320	--	1
n-Butylbenzene	ND		ug/kg	65	--	1
sec-Butylbenzene	ND		ug/kg	65	--	1
tert-Butylbenzene	ND		ug/kg	320	--	1
o-Chlorotoluene	ND		ug/kg	320	--	1
p-Chlorotoluene	ND		ug/kg	320	--	1
1,2-Dibromo-3-chloropropane	ND		ug/kg	320	--	1
Hexachlorobutadiene	ND		ug/kg	320	--	1
Isopropylbenzene	ND		ug/kg	65	--	1
p-Isopropyltoluene	ND		ug/kg	65	--	1
Naphthalene	ND		ug/kg	320	--	1
n-Propylbenzene	ND		ug/kg	65	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-03
Client ID: 1607530-B102(S1-S2)
Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 10:45
Date Received: 08/29/16
Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Volatile Organics by EPA 5035 High - Westborough Lab						
1,2,3-Trichlorobenzene	ND		ug/kg	320	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	320	--	1
1,3,5-Trimethylbenzene	ND		ug/kg	320	--	1
1,2,4-Trimethylbenzene	ND		ug/kg	320	--	1
trans-1,4-Dichloro-2-butene	ND		ug/kg	320	--	1
Ethyl ether	ND		ug/kg	320	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	96		70-130
Toluene-d8	101		70-130
4-Bromofluorobenzene	98		70-130
Dibromofluoromethane	94		70-130

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-04
 Client ID: 1607530-B102(S3-S4)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8260C
 Analytical Date: 09/05/16 13:40
 Analyst: BN
 Percent Solids: 79%

Date Collected: 08/26/16 11:00
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by EPA 5035 High - Westborough Lab						
Methylene chloride	ND		ug/kg	480	--	1
1,1-Dichloroethane	ND		ug/kg	73	--	1
Chloroform	ND		ug/kg	73	--	1
Carbon tetrachloride	ND		ug/kg	48	--	1
1,2-Dichloropropane	ND		ug/kg	170	--	1
Dibromochloromethane	ND		ug/kg	48	--	1
1,1,2-Trichloroethane	ND		ug/kg	73	--	1
Tetrachloroethene	ND		ug/kg	48	--	1
Chlorobenzene	ND		ug/kg	48	--	1
Trichlorofluoromethane	ND		ug/kg	240	--	1
1,2-Dichloroethane	ND		ug/kg	48	--	1
1,1,1-Trichloroethane	ND		ug/kg	48	--	1
Bromodichloromethane	ND		ug/kg	48	--	1
trans-1,3-Dichloropropene	ND		ug/kg	48	--	1
cis-1,3-Dichloropropene	ND		ug/kg	48	--	1
1,3-Dichloropropene, Total	ND		ug/kg	48	--	1
1,1-Dichloropropene	ND		ug/kg	240	--	1
Bromoform	ND		ug/kg	190	--	1
1,1,2,2-Tetrachloroethane	ND		ug/kg	48	--	1
Benzene	ND		ug/kg	48	--	1
Toluene	ND		ug/kg	73	--	1
Ethylbenzene	ND		ug/kg	48	--	1
Chloromethane	ND		ug/kg	240	--	1
Bromomethane	ND		ug/kg	97	--	1
Vinyl chloride	ND		ug/kg	97	--	1
Chloroethane	ND		ug/kg	97	--	1
1,1-Dichloroethene	ND		ug/kg	48	--	1
trans-1,2-Dichloroethene	ND		ug/kg	73	--	1
Trichloroethene	ND		ug/kg	48	--	1
1,2-Dichlorobenzene	ND		ug/kg	240	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-04
 Client ID: 1607530-B102(S3-S4)
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 11:00
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by EPA 5035 High - Westborough Lab						
1,3-Dichlorobenzene	ND		ug/kg	240	--	1
1,4-Dichlorobenzene	ND		ug/kg	240	--	1
Methyl tert butyl ether	ND		ug/kg	97	--	1
p/m-Xylene	ND		ug/kg	97	--	1
o-Xylene	ND		ug/kg	97	--	1
Xylenes, Total	ND		ug/kg	97	--	1
cis-1,2-Dichloroethene	ND		ug/kg	48	--	1
1,2-Dichloroethene, Total	ND		ug/kg	48	--	1
Dibromomethane	ND		ug/kg	480	--	1
1,4-Dichlorobutane	ND		ug/kg	480	--	1
1,2,3-Trichloropropane	ND		ug/kg	480	--	1
Styrene	ND		ug/kg	97	--	1
Dichlorodifluoromethane	ND		ug/kg	480	--	1
Acetone	ND		ug/kg	1700	--	1
Carbon disulfide	ND		ug/kg	480	--	1
2-Butanone	ND		ug/kg	480	--	1
Vinyl acetate	ND		ug/kg	480	--	1
4-Methyl-2-pentanone	ND		ug/kg	480	--	1
2-Hexanone	ND		ug/kg	480	--	1
Ethyl methacrylate	ND		ug/kg	480	--	1
Acrylonitrile	ND		ug/kg	190	--	1
Bromochloromethane	ND		ug/kg	240	--	1
Tetrahydrofuran	ND		ug/kg	970	--	1
2,2-Dichloropropane	ND		ug/kg	240	--	1
1,2-Dibromoethane	ND		ug/kg	190	--	1
1,3-Dichloropropane	ND		ug/kg	240	--	1
1,1,1,2-Tetrachloroethane	ND		ug/kg	48	--	1
Bromobenzene	ND		ug/kg	240	--	1
n-Butylbenzene	ND		ug/kg	48	--	1
sec-Butylbenzene	ND		ug/kg	48	--	1
tert-Butylbenzene	ND		ug/kg	240	--	1
o-Chlorotoluene	ND		ug/kg	240	--	1
p-Chlorotoluene	ND		ug/kg	240	--	1
1,2-Dibromo-3-chloropropane	ND		ug/kg	240	--	1
Hexachlorobutadiene	ND		ug/kg	240	--	1
Isopropylbenzene	ND		ug/kg	48	--	1
p-Isopropyltoluene	ND		ug/kg	48	--	1
Naphthalene	ND		ug/kg	240	--	1
n-Propylbenzene	ND		ug/kg	48	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-04
Client ID: 1607530-B102(S3-S4)
Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 11:00
Date Received: 08/29/16
Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Volatile Organics by EPA 5035 High - Westborough Lab						
1,2,3-Trichlorobenzene	ND		ug/kg	240	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	240	--	1
1,3,5-Trimethylbenzene	ND		ug/kg	240	--	1
1,2,4-Trimethylbenzene	ND		ug/kg	240	--	1
trans-1,4-Dichloro-2-butene	ND		ug/kg	240	--	1
Ethyl ether	ND		ug/kg	240	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	97		70-130
Toluene-d8	101		70-130
4-Bromofluorobenzene	98		70-130
Dibromofluoromethane	93		70-130

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-05
 Client ID: 1607530-B101(S1-S2)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8260C
 Analytical Date: 09/05/16 14:06
 Analyst: BN
 Percent Solids: 84%

Date Collected: 08/26/16 11:45
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by EPA 5035 High - Westborough Lab						
Methylene chloride	ND		ug/kg	650	--	1
1,1-Dichloroethane	ND		ug/kg	98	--	1
Chloroform	ND		ug/kg	98	--	1
Carbon tetrachloride	ND		ug/kg	65	--	1
1,2-Dichloropropane	ND		ug/kg	230	--	1
Dibromochloromethane	ND		ug/kg	65	--	1
1,1,2-Trichloroethane	ND		ug/kg	98	--	1
Tetrachloroethene	ND		ug/kg	65	--	1
Chlorobenzene	ND		ug/kg	65	--	1
Trichlorofluoromethane	ND		ug/kg	320	--	1
1,2-Dichloroethane	ND		ug/kg	65	--	1
1,1,1-Trichloroethane	ND		ug/kg	65	--	1
Bromodichloromethane	ND		ug/kg	65	--	1
trans-1,3-Dichloropropene	ND		ug/kg	65	--	1
cis-1,3-Dichloropropene	ND		ug/kg	65	--	1
1,3-Dichloropropene, Total	ND		ug/kg	65	--	1
1,1-Dichloropropene	ND		ug/kg	320	--	1
Bromoform	ND		ug/kg	260	--	1
1,1,2,2-Tetrachloroethane	ND		ug/kg	65	--	1
Benzene	ND		ug/kg	65	--	1
Toluene	ND		ug/kg	98	--	1
Ethylbenzene	ND		ug/kg	65	--	1
Chloromethane	ND		ug/kg	320	--	1
Bromomethane	ND		ug/kg	130	--	1
Vinyl chloride	ND		ug/kg	130	--	1
Chloroethane	ND		ug/kg	130	--	1
1,1-Dichloroethene	ND		ug/kg	65	--	1
trans-1,2-Dichloroethene	ND		ug/kg	98	--	1
Trichloroethene	ND		ug/kg	65	--	1
1,2-Dichlorobenzene	ND		ug/kg	320	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-05
Client ID: 1607530-B101(S1-S2)
Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 11:45
Date Received: 08/29/16
Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by EPA 5035 High - Westborough Lab						
1,3-Dichlorobenzene	ND		ug/kg	320	--	1
1,4-Dichlorobenzene	ND		ug/kg	320	--	1
Methyl tert butyl ether	ND		ug/kg	130	--	1
p/m-Xylene	ND		ug/kg	130	--	1
o-Xylene	ND		ug/kg	130	--	1
Xylenes, Total	ND		ug/kg	130	--	1
cis-1,2-Dichloroethene	ND		ug/kg	65	--	1
1,2-Dichloroethene, Total	ND		ug/kg	65	--	1
Dibromomethane	ND		ug/kg	650	--	1
1,4-Dichlorobutane	ND		ug/kg	650	--	1
1,2,3-Trichloropropane	ND		ug/kg	650	--	1
Styrene	ND		ug/kg	130	--	1
Dichlorodifluoromethane	ND		ug/kg	650	--	1
Acetone	ND		ug/kg	2300	--	1
Carbon disulfide	ND		ug/kg	650	--	1
2-Butanone	ND		ug/kg	650	--	1
Vinyl acetate	ND		ug/kg	650	--	1
4-Methyl-2-pentanone	ND		ug/kg	650	--	1
2-Hexanone	ND		ug/kg	650	--	1
Ethyl methacrylate	ND		ug/kg	650	--	1
Acrylonitrile	ND		ug/kg	260	--	1
Bromochloromethane	ND		ug/kg	320	--	1
Tetrahydrofuran	ND		ug/kg	1300	--	1
2,2-Dichloropropane	ND		ug/kg	320	--	1
1,2-Dibromoethane	ND		ug/kg	260	--	1
1,3-Dichloropropane	ND		ug/kg	320	--	1
1,1,1,2-Tetrachloroethane	ND		ug/kg	65	--	1
Bromobenzene	ND		ug/kg	320	--	1
n-Butylbenzene	ND		ug/kg	65	--	1
sec-Butylbenzene	ND		ug/kg	65	--	1
tert-Butylbenzene	ND		ug/kg	320	--	1
o-Chlorotoluene	ND		ug/kg	320	--	1
p-Chlorotoluene	ND		ug/kg	320	--	1
1,2-Dibromo-3-chloropropane	ND		ug/kg	320	--	1
Hexachlorobutadiene	ND		ug/kg	320	--	1
Isopropylbenzene	ND		ug/kg	65	--	1
p-Isopropyltoluene	ND		ug/kg	65	--	1
Naphthalene	ND		ug/kg	320	--	1
n-Propylbenzene	ND		ug/kg	65	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-05
Client ID: 1607530-B101(S1-S2)
Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 11:45
Date Received: 08/29/16
Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Volatile Organics by EPA 5035 High - Westborough Lab						
1,2,3-Trichlorobenzene	ND		ug/kg	320	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	320	--	1
1,3,5-Trimethylbenzene	ND		ug/kg	320	--	1
1,2,4-Trimethylbenzene	ND		ug/kg	320	--	1
trans-1,4-Dichloro-2-butene	ND		ug/kg	320	--	1
Ethyl ether	ND		ug/kg	320	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	98		70-130
Toluene-d8	101		70-130
4-Bromofluorobenzene	97		70-130
Dibromofluoromethane	94		70-130

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-06
 Client ID: 1607530-B101(S3-S4)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8260C
 Analytical Date: 09/05/16 14:33
 Analyst: BN
 Percent Solids: 81%

Date Collected: 08/26/16 12:00
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by EPA 5035 High - Westborough Lab						
Methylene chloride	ND		ug/kg	480	--	1
1,1-Dichloroethane	ND		ug/kg	71	--	1
Chloroform	ND		ug/kg	71	--	1
Carbon tetrachloride	ND		ug/kg	48	--	1
1,2-Dichloropropane	ND		ug/kg	170	--	1
Dibromochloromethane	ND		ug/kg	48	--	1
1,1,2-Trichloroethane	ND		ug/kg	71	--	1
Tetrachloroethene	ND		ug/kg	48	--	1
Chlorobenzene	ND		ug/kg	48	--	1
Trichlorofluoromethane	ND		ug/kg	240	--	1
1,2-Dichloroethane	ND		ug/kg	48	--	1
1,1,1-Trichloroethane	ND		ug/kg	48	--	1
Bromodichloromethane	ND		ug/kg	48	--	1
trans-1,3-Dichloropropene	ND		ug/kg	48	--	1
cis-1,3-Dichloropropene	ND		ug/kg	48	--	1
1,3-Dichloropropene, Total	ND		ug/kg	48	--	1
1,1-Dichloropropene	ND		ug/kg	240	--	1
Bromoform	ND		ug/kg	190	--	1
1,1,2,2-Tetrachloroethane	ND		ug/kg	48	--	1
Benzene	ND		ug/kg	48	--	1
Toluene	ND		ug/kg	71	--	1
Ethylbenzene	ND		ug/kg	48	--	1
Chloromethane	ND		ug/kg	240	--	1
Bromomethane	ND		ug/kg	95	--	1
Vinyl chloride	ND		ug/kg	95	--	1
Chloroethane	ND		ug/kg	95	--	1
1,1-Dichloroethene	ND		ug/kg	48	--	1
trans-1,2-Dichloroethene	ND		ug/kg	71	--	1
Trichloroethene	ND		ug/kg	48	--	1
1,2-Dichlorobenzene	ND		ug/kg	240	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-06
 Client ID: 1607530-B101(S3-S4)
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 12:00
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Volatile Organics by EPA 5035 High - Westborough Lab						
1,3-Dichlorobenzene	ND		ug/kg	240	--	1
1,4-Dichlorobenzene	ND		ug/kg	240	--	1
Methyl tert butyl ether	ND		ug/kg	95	--	1
p/m-Xylene	ND		ug/kg	95	--	1
o-Xylene	ND		ug/kg	95	--	1
Xylenes, Total	ND		ug/kg	95	--	1
cis-1,2-Dichloroethene	ND		ug/kg	48	--	1
1,2-Dichloroethene, Total	ND		ug/kg	48	--	1
Dibromomethane	ND		ug/kg	480	--	1
1,4-Dichlorobutane	ND		ug/kg	480	--	1
1,2,3-Trichloropropane	ND		ug/kg	480	--	1
Styrene	ND		ug/kg	95	--	1
Dichlorodifluoromethane	ND		ug/kg	480	--	1
Acetone	ND		ug/kg	1700	--	1
Carbon disulfide	ND		ug/kg	480	--	1
2-Butanone	ND		ug/kg	480	--	1
Vinyl acetate	ND		ug/kg	480	--	1
4-Methyl-2-pentanone	ND		ug/kg	480	--	1
2-Hexanone	ND		ug/kg	480	--	1
Ethyl methacrylate	ND		ug/kg	480	--	1
Acrylonitrile	ND		ug/kg	190	--	1
Bromochloromethane	ND		ug/kg	240	--	1
Tetrahydrofuran	ND		ug/kg	950	--	1
2,2-Dichloropropane	ND		ug/kg	240	--	1
1,2-Dibromoethane	ND		ug/kg	190	--	1
1,3-Dichloropropane	ND		ug/kg	240	--	1
1,1,1,2-Tetrachloroethane	ND		ug/kg	48	--	1
Bromobenzene	ND		ug/kg	240	--	1
n-Butylbenzene	ND		ug/kg	48	--	1
sec-Butylbenzene	ND		ug/kg	48	--	1
tert-Butylbenzene	ND		ug/kg	240	--	1
o-Chlorotoluene	ND		ug/kg	240	--	1
p-Chlorotoluene	ND		ug/kg	240	--	1
1,2-Dibromo-3-chloropropane	ND		ug/kg	240	--	1
Hexachlorobutadiene	ND		ug/kg	240	--	1
Isopropylbenzene	ND		ug/kg	48	--	1
p-Isopropyltoluene	ND		ug/kg	48	--	1
Naphthalene	ND		ug/kg	240	--	1
n-Propylbenzene	ND		ug/kg	48	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-06
Client ID: 1607530-B101(S3-S4)
Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 12:00
Date Received: 08/29/16
Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Volatile Organics by EPA 5035 High - Westborough Lab						
1,2,3-Trichlorobenzene	ND		ug/kg	240	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	240	--	1
1,3,5-Trimethylbenzene	ND		ug/kg	240	--	1
1,2,4-Trimethylbenzene	ND		ug/kg	240	--	1
trans-1,4-Dichloro-2-butene	ND		ug/kg	240	--	1
Ethyl ether	ND		ug/kg	240	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	97		70-130
Toluene-d8	101		70-130
4-Bromofluorobenzene	98		70-130
Dibromofluoromethane	93		70-130

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Method Blank Analysis
Batch Quality Control

Analytical Method: 1,8260C
Analytical Date: 09/05/16 08:21
Analyst: BN

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by EPA 5035 High - Westborough Lab for sample(s): 01-06 Batch: WG929175-5					
Methylene chloride	ND		ug/kg	500	--
1,1-Dichloroethane	ND		ug/kg	75	--
Chloroform	ND		ug/kg	75	--
Carbon tetrachloride	ND		ug/kg	50	--
1,2-Dichloropropane	ND		ug/kg	180	--
Dibromochloromethane	ND		ug/kg	50	--
1,1,2-Trichloroethane	ND		ug/kg	75	--
2-Chloroethylvinyl ether	ND		ug/kg	1000	--
Tetrachloroethene	ND		ug/kg	50	--
Chlorobenzene	ND		ug/kg	50	--
Trichlorofluoromethane	ND		ug/kg	250	--
1,2-Dichloroethane	ND		ug/kg	50	--
1,1,1-Trichloroethane	ND		ug/kg	50	--
Bromodichloromethane	ND		ug/kg	50	--
trans-1,3-Dichloropropene	ND		ug/kg	50	--
cis-1,3-Dichloropropene	ND		ug/kg	50	--
1,3-Dichloropropene, Total	ND		ug/kg	50	--
1,1-Dichloropropene	ND		ug/kg	250	--
Bromoform	ND		ug/kg	200	--
1,1,2,2-Tetrachloroethane	ND		ug/kg	50	--
Benzene	ND		ug/kg	50	--
Toluene	ND		ug/kg	75	--
Ethy benzene	ND		ug/kg	50	--
Chloromethane	ND		ug/kg	250	--
Bromomethane	ND		ug/kg	100	--
Vinyl chloride	ND		ug/kg	100	--
Chloroethane	ND		ug/kg	100	--
1,1-Dichloroethene	ND		ug/kg	50	--
trans-1,2-Dichloroethene	ND		ug/kg	75	--

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Method Blank Analysis
Batch Quality Control

Analytical Method: 1,8260C
Analytical Date: 09/05/16 08:21
Analyst: BN

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by EPA 5035 High - Westborough Lab for sample(s): 01-06 Batch: WG929175-5					
Trichloroethene	ND		ug/kg	50	--
1,2-Dichlorobenzene	ND		ug/kg	250	--
1,3-Dichlorobenzene	ND		ug/kg	250	--
1,4-Dichlorobenzene	ND		ug/kg	250	--
Methyl tert butyl ether	ND		ug/kg	100	--
p/m-Xylene	ND		ug/kg	100	--
o-Xylene	ND		ug/kg	100	--
Xylenes, Total	ND		ug/kg	100	--
cis-1,2-Dichloroethene	ND		ug/kg	50	--
1,2-Dichloroethene, Total	ND		ug/kg	50	--
Dibromomethane	ND		ug/kg	500	--
1,4-Dichlorobutane	ND		ug/kg	500	--
1,2,3-Trichloropropane	ND		ug/kg	500	--
Styrene	ND		ug/kg	100	--
Dichlorodifluoromethane	ND		ug/kg	500	--
Acetone	ND		ug/kg	1800	--
Carbon disulfide	ND		ug/kg	500	--
2-Butanone	ND		ug/kg	500	--
Vinyl acetate	ND		ug/kg	500	--
4-Methyl-2-pentanone	ND		ug/kg	500	--
2-Hexanone	ND		ug/kg	500	--
Ethyl methacrylate	ND		ug/kg	500	--
Acrolein	ND		ug/kg	1200	--
Acrylonitrile	ND		ug/kg	200	--
Bromochloromethane	ND		ug/kg	250	--
Tetrahydrofuran	ND		ug/kg	1000	--
2,2-Dichloropropane	ND		ug/kg	250	--
1,2-Dibromoethane	ND		ug/kg	200	--
1,3-Dichloropropane	ND		ug/kg	250	--

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Method Blank Analysis
Batch Quality Control

Analytical Method: 1,8260C
Analytical Date: 09/05/16 08:21
Analyst: BN

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by EPA 5035 High - Westborough Lab for sample(s): 01-06 Batch: WG929175-5					
1,1,1,2-Tetrachloroethane	ND		ug/kg	50	--
Bromobenzene	ND		ug/kg	250	--
n-Buty benzene	ND		ug/kg	50	--
sec-Buty benzene	ND		ug/kg	50	--
tert-Butylbenzene	ND		ug/kg	250	--
1,3,5-Trichlorobenzene	ND		ug/kg	200	--
o-Chlorotoluene	ND		ug/kg	250	--
p-Chlorotoluene	ND		ug/kg	250	--
1,2-Dibromo-3-chloropropane	ND		ug/kg	250	--
Hexachlorobutadiene	ND		ug/kg	250	--
Isopropylbenzene	ND		ug/kg	50	--
p-Isopropyltoluene	ND		ug/kg	50	--
Naphthalene	ND		ug/kg	250	--
n-Propy benzene	ND		ug/kg	50	--
1,2,3-Trichlorobenzene	ND		ug/kg	250	--
1,2,4-Trichlorobenzene	ND		ug/kg	250	--
1,3,5-Trimethylbenzene	ND		ug/kg	250	--
1,2,4-Trimethylbenzene	ND		ug/kg	250	--
trans-1,4-Dichloro-2-butene	ND		ug/kg	250	--
Halothane	ND		ug/kg	2000	--
Ethyl ether	ND		ug/kg	250	--
Methyl Acetate	ND		ug/kg	1000	--
Ethyl Acetate	ND		ug/kg	1000	--
Isopropyl Ether	ND		ug/kg	200	--
Cyclohexane	ND		ug/kg	1000	--
Tert-Butyl Alcohol	ND		ug/kg	5000	--
Ethyl-Tert-Butyl-Ether	ND		ug/kg	200	--
Tertiary-Amyl Methyl Ether	ND		ug/kg	200	--
1,4-Dioxane	ND		ug/kg	5000	--

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Method Blank Analysis
Batch Quality Control

Analytical Method: 1,8260C
Analytical Date: 09/05/16 08:21
Analyst: BN

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by EPA 5035 High - Westborough Lab for sample(s): 01-06 Batch: WG929175-5					
Methyl cyclohexane	ND		ug/kg	200	--
1,1,2-Trichloro-1,2,2-Trifluoroethane	ND		ug/kg	1000	--
p-Diethylbenzene	ND		ug/kg	200	--
4-Ethyltoluene	ND		ug/kg	200	--
1,2,4,5-Tetramethylbenzene	ND		ug/kg	200	--

Surrogate	%Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	98		70-130
Toluene-d8	99		70-130
4-Bromofluorobenzene	98		70-130
D bromofluoromethane	96		70-130

Lab Control Sample Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by EPA 5035 High - Westborough Lab Associated sample(s): 01-06 Batch: WG929175-3 WG929175-4								
Methylene chloride	89		87		70-130	2		30
1,1-Dichloroethane	96		95		70-130	1		30
Chloroform	95		93		70-130	2		30
Carbon tetrachloride	93		91		70-130	2		30
1,2-Dichloropropane	94		92		70-130	2		30
Dibromochloromethane	92		92		70-130	0		30
1,1,2-Trichloroethane	94		93		70-130	1		30
2-Chloroethylvinyl ether	94		93		70-130	1		30
Tetrachloroethene	103		98		70-130	5		30
Chlorobenzene	96		94		70-130	2		30
Trichlorofluoromethane	112		107		70-139	5		30
1,2-Dichloroethane	93		92		70-130	1		30
1,1,1-Trichloroethane	95		93		70-130	2		30
Bromodichloromethane	92		89		70-130	3		30
trans-1,3-Dichloropropene	96		94		70-130	2		30
cis-1,3-Dichloropropene	95		95		70-130	0		30
1,1-Dichloropropene	107		104		70-130	3		30
Bromoform	83		83		70-130	0		30
1,1,2,2-Tetrachloroethane	94		93		70-130	1		30
Benzene	97		94		70-130	3		30
Toluene	97		94		70-130	3		30

Lab Control Sample Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by EPA 5035 High - Westborough Lab Associated sample(s): 01-06 Batch: WG929175-3 WG929175-4								
Ethylbenzene	99		95		70-130	4		30
Chloromethane	115		111		52-130	4		30
Bromomethane	109		103		57-147	6		30
Vinyl chloride	104		99		67-130	5		30
Chloroethane	112		104		50-151	7		30
1,1-Dichloroethene	89		85		65-135	5		30
trans-1,2-Dichloroethene	99		95		70-130	4		30
Trichloroethene	98		94		70-130	4		30
1,2-Dichlorobenzene	99		98		70-130	1		30
1,3-Dichlorobenzene	100		98		70-130	2		30
1,4-Dichlorobenzene	99		97		70-130	2		30
Methyl tert butyl ether	92		91		66-130	1		30
p/m-Xylene	101		97		70-130	4		30
o-Xylene	101		98		70-130	3		30
cis-1,2-Dichloroethene	97		94		70-130	3		30
Dibromomethane	91		90		70-130	1		30
1,4-Dichlorobutane	94		92		70-130	2		30
1,2,3-Trichloropropane	94		94		68-130	0		30
Styrene	100		97		70-130	3		30
Dichlorodifluoromethane	118		112		30-146	5		30
Acetone	86		86		54-140	0		30

Lab Control Sample Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by EPA 5035 High - Westborough Lab Associated sample(s): 01-06 Batch: WG929175-3 WG929175-4								
Carbon disulfide	73		72		59-130	1		30
2-Butanone	77		78		70-130	1		30
Vinyl acetate	95		96		70-130	1		30
4-Methyl-2-pentanone	89		88		70-130	1		30
2-Hexanone	86		86		70-130	0		30
Ethyl methacrylate	84		83		70-130	1		30
Acrolein	44	Q	47	Q	70-130	7		30
Acrylonitrile	84		83		70-130	1		30
Bromochloromethane	97		95		70-130	2		30
Tetrahydrofuran	84		85		66-130	1		30
2,2-Dichloropropane	97		94		70-130	3		30
1,2-Dibromoethane	94		92		70-130	2		30
1,3-Dichloropropane	96		94		69-130	2		30
1,1,1,2-Tetrachloroethane	95		93		70-130	2		30
Bromobenzene	100		97		70-130	3		30
n-Butylbenzene	109		106		70-130	3		30
sec-Butylbenzene	104		101		70-130	3		30
tert-Butylbenzene	103		100		70-130	3		30
1,3,5-Trichlorobenzene	104		102		70-139	2		30
o-Chlorotoluene	98		95		70-130	3		30
p-Chlorotoluene	98		97		70-130	1		30

Lab Control Sample Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by EPA 5035 High - Westborough Lab Associated sample(s): 01-06 Batch: WG929175-3 WG929175-4								
1,2-Dibromo-3-chloropropane	84		87		68-130	4		30
Hexachlorobutadiene	107		104		67-130	3		30
Isopropylbenzene	102		98		70-130	4		30
p-Isopropyltoluene	106		103		70-130	3		30
Naphthalene	96		95		70-130	1		30
n-Propylbenzene	104		101		70-130	3		30
1,2,3-Trichlorobenzene	101		100		70-130	1		30
1,2,4-Trichlorobenzene	103		102		70-130	1		30
1,3,5-Trimethylbenzene	102		98		70-130	4		30
1,2,4-Trimethylbenzene	103		101		70-130	2		30
trans-1,4-Dichloro-2-butene	90		90		70-130	0		30
Halothane	107		105		70-130	2		20
Ethyl ether	105		102		67-130	3		30
Methyl Acetate	101		100		65-130	1		30
Ethyl Acetate	92		94		70-130	2		30
Isopropyl Ether	93		92		66-130	1		30
Cyclohexane	108		105		70-130	3		30
Tert-Butyl Alcohol	76		76		70-130	0		30
Ethyl-Tert-Butyl-Ether	94		93		70-130	1		30
Tertiary-Amyl Methyl Ether	91		90		70-130	1		30
1,4-Dioxane	78		75		65-136	4		30

Lab Control Sample Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by EPA 5035 High - Westborough Lab Associated sample(s): 01-06 Batch: WG929175-3 WG929175-4								
Methyl cyclohexane	114		109		70-130	4		30
1,1,2-Trichloro-1,2,2-Trifluoroethane	101		96		70-130	5		30
p-Diethylbenzene	107		104		70-130	3		30
4-Ethyltoluene	109		105		70-130	4		30
1,2,4,5-Tetramethylbenzene	105		103		70-130	2		30

Surrogate	LCS %Recovery	Qual	LCSD %Recovery	Qual	Acceptance Criteria
1,2-Dichloroethane-d4	95		97		70-130
Toluene-d8	101		100		70-130
4-Bromofluorobenzene	101		100		70-130
Dibromofluoromethane	100		100		70-130

SEMIVOLATILES

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-01
 Client ID: 1607530-B103(S1-S2)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8270D
 Analytical Date: 09/02/16 04:52
 Analyst: KV
 Percent Solids: 93%

Date Collected: 08/26/16 09:25
 Date Received: 08/29/16
 Field Prep: Not Specified
 Extraction Method: EPA 3546
 Extraction Date: 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Acenaphthene	ND		ug/kg	140	--	1
Benzidine	ND		ug/kg	580	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	180	--	1
Hexachlorobenzene	ND		ug/kg	110	--	1
Bis(2-chloroethyl)ether	ND		ug/kg	160	--	1
2-Chloronaphthalene	ND		ug/kg	180	--	1
1,2-Dichlorobenzene	ND		ug/kg	180	--	1
1,3-Dichlorobenzene	ND		ug/kg	180	--	1
1,4-Dichlorobenzene	ND		ug/kg	180	--	1
3,3'-Dichlorobenzidine	ND		ug/kg	180	--	1
2,4-Dinitrotoluene	ND		ug/kg	180	--	1
2,6-Dinitrotoluene	ND		ug/kg	180	--	1
Azobenzene	ND		ug/kg	180	--	1
Fluoranthene	ND		ug/kg	110	--	1
4-Chlorophenyl phenyl ether	ND		ug/kg	180	--	1
4-Bromophenyl phenyl ether	ND		ug/kg	180	--	1
Bis(2-chloroisopropyl)ether	ND		ug/kg	210	--	1
Bis(2-chloroethoxy)methane	ND		ug/kg	190	--	1
Hexachlorobutadiene	ND		ug/kg	180	--	1
Hexachlorocyclopentadiene	ND		ug/kg	500	--	1
Hexachloroethane	ND		ug/kg	140	--	1
Isophorone	ND		ug/kg	160	--	1
Naphthalene	ND		ug/kg	180	--	1
Nitrobenzene	ND		ug/kg	160	--	1
NDPA/DPA	ND		ug/kg	140	--	1
n-Nitrosodi-n-propylamine	ND		ug/kg	180	--	1
Bis(2-ethylhexyl)phthalate	ND		ug/kg	180	--	1
Butyl benzyl phthalate	ND		ug/kg	180	--	1
Di-n-butylphthalate	ND		ug/kg	180	--	1
Di-n-octylphthalate	ND		ug/kg	180	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-01
 Client ID: 1607530-B103(S1-S2)
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 09:25
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Diethyl phthalate	ND		ug/kg	180	--	1
Dimethyl phthalate	ND		ug/kg	180	--	1
Benzo(a)anthracene	ND		ug/kg	110	--	1
Benzo(a)pyrene	ND		ug/kg	140	--	1
Benzo(b)fluoranthene	ND		ug/kg	110	--	1
Benzo(k)fluoranthene	ND		ug/kg	110	--	1
Chrysene	ND		ug/kg	110	--	1
Acenaphthylene	ND		ug/kg	140	--	1
Anthracene	ND		ug/kg	110	--	1
Benzo(ghi)perylene	ND		ug/kg	140	--	1
Fluorene	ND		ug/kg	180	--	1
Phenanthrene	ND		ug/kg	110	--	1
Dibenzo(a,h)anthracene	ND		ug/kg	110	--	1
Indeno(1,2,3-cd)pyrene	ND		ug/kg	140	--	1
Pyrene	ND		ug/kg	110	--	1
Biphenyl	ND		ug/kg	400	--	1
Aniline	ND		ug/kg	210	--	1
4-Chloroaniline	ND		ug/kg	180	--	1
1-Methylnaphthalene	ND		ug/kg	180	--	1
2-Nitroaniline	ND		ug/kg	180	--	1
3-Nitroaniline	ND		ug/kg	180	--	1
4-Nitroaniline	ND		ug/kg	180	--	1
Dibenzofuran	ND		ug/kg	180	--	1
2-Methylnaphthalene	ND		ug/kg	210	--	1
n-Nitrosodimethylamine	ND		ug/kg	350	--	1
2,4,6-Trichlorophenol	ND		ug/kg	110	--	1
p-Chloro-m-cresol	ND		ug/kg	180	--	1
2-Chlorophenol	ND		ug/kg	180	--	1
2,4-Dichlorophenol	ND		ug/kg	160	--	1
2,4-Dimethylphenol	ND		ug/kg	180	--	1
2-Nitrophenol	ND		ug/kg	380	--	1
4-Nitrophenol	ND		ug/kg	250	--	1
2,4-Dinitrophenol	ND		ug/kg	850	--	1
4,6-Dinitro-o-cresol	ND		ug/kg	460	--	1
Pentachlorophenol	ND		ug/kg	140	--	1
Phenol	ND		ug/kg	180	--	1
2-Methylphenol	ND		ug/kg	180	--	1
3-Methylphenol/4-Methylphenol	ND		ug/kg	250	--	1
2,4,5-Trichlorophenol	ND		ug/kg	180	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-01
 Client ID: 1607530-B103(S1-S2)
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 09:25
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Semivolatile Organics by GC/MS - Westborough Lab

Benzoic Acid	ND		ug/kg	570	--	1
Benzyl Alcohol	ND		ug/kg	180	--	1
Carbazole	ND		ug/kg	180	--	1
Pyridine	ND		ug/kg	710	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	98		25-120
Phenol-d6	101		10-120
Nitrobenzene-d5	103		23-120
2-Fluorobiphenyl	83		30-120
2,4,6-Tribromophenol	89		10-136
4-Terphenyl-d14	84		18-120

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-02
 Client ID: 1607530-B103(S3-S4)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8270D
 Analytical Date: 09/02/16 05:18
 Analyst: KV
 Percent Solids: 92%

Date Collected: 08/26/16 09:55
 Date Received: 08/29/16
 Field Prep: Not Specified
 Extraction Method: EPA 3546
 Extraction Date: 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Acenaphthene	ND		ug/kg	140	--	1
Benzidine	ND		ug/kg	580	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	180	--	1
Hexachlorobenzene	ND		ug/kg	100	--	1
Bis(2-chloroethyl)ether	ND		ug/kg	160	--	1
2-Chloronaphthalene	ND		ug/kg	180	--	1
1,2-Dichlorobenzene	ND		ug/kg	180	--	1
1,3-Dichlorobenzene	ND		ug/kg	180	--	1
1,4-Dichlorobenzene	ND		ug/kg	180	--	1
3,3'-Dichlorobenzidine	ND		ug/kg	180	--	1
2,4-Dinitrotoluene	ND		ug/kg	180	--	1
2,6-Dinitrotoluene	ND		ug/kg	180	--	1
Azobenzene	ND		ug/kg	180	--	1
Fluoranthene	ND		ug/kg	100	--	1
4-Chlorophenyl phenyl ether	ND		ug/kg	180	--	1
4-Bromophenyl phenyl ether	ND		ug/kg	180	--	1
Bis(2-chloroisopropyl)ether	ND		ug/kg	210	--	1
Bis(2-chloroethoxy)methane	ND		ug/kg	190	--	1
Hexachlorobutadiene	ND		ug/kg	180	--	1
Hexachlorocyclopentadiene	ND		ug/kg	500	--	1
Hexachloroethane	ND		ug/kg	140	--	1
Isophorone	ND		ug/kg	160	--	1
Naphthalene	ND		ug/kg	180	--	1
Nitrobenzene	ND		ug/kg	160	--	1
NDPA/DPA	ND		ug/kg	140	--	1
n-Nitrosodi-n-propylamine	ND		ug/kg	180	--	1
Bis(2-ethylhexyl)phthalate	ND		ug/kg	180	--	1
Butyl benzyl phthalate	ND		ug/kg	180	--	1
Di-n-butylphthalate	ND		ug/kg	180	--	1
Di-n-octylphthalate	ND		ug/kg	180	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-02
 Client ID: 1607530-B103(S3-S4)
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 09:55
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Diethyl phthalate	ND		ug/kg	180	--	1
Dimethyl phthalate	ND		ug/kg	180	--	1
Benzo(a)anthracene	ND		ug/kg	100	--	1
Benzo(a)pyrene	ND		ug/kg	140	--	1
Benzo(b)fluoranthene	ND		ug/kg	100	--	1
Benzo(k)fluoranthene	ND		ug/kg	100	--	1
Chrysene	ND		ug/kg	100	--	1
Acenaphthylene	ND		ug/kg	140	--	1
Anthracene	ND		ug/kg	100	--	1
Benzo(ghi)perylene	ND		ug/kg	140	--	1
Fluorene	ND		ug/kg	180	--	1
Phenanthrene	ND		ug/kg	100	--	1
Dibenzo(a,h)anthracene	ND		ug/kg	100	--	1
Indeno(1,2,3-cd)pyrene	ND		ug/kg	140	--	1
Pyrene	ND		ug/kg	100	--	1
Biphenyl	ND		ug/kg	400	--	1
Aniline	ND		ug/kg	210	--	1
4-Chloroaniline	ND		ug/kg	180	--	1
1-Methylnaphthalene	ND		ug/kg	180	--	1
2-Nitroaniline	ND		ug/kg	180	--	1
3-Nitroaniline	ND		ug/kg	180	--	1
4-Nitroaniline	ND		ug/kg	180	--	1
Dibenzofuran	ND		ug/kg	180	--	1
2-Methylnaphthalene	ND		ug/kg	210	--	1
n-Nitrosodimethylamine	ND		ug/kg	350	--	1
2,4,6-Trichlorophenol	ND		ug/kg	100	--	1
p-Chloro-m-cresol	ND		ug/kg	180	--	1
2-Chlorophenol	ND		ug/kg	180	--	1
2,4-Dichlorophenol	ND		ug/kg	160	--	1
2,4-Dimethylphenol	ND		ug/kg	180	--	1
2-Nitrophenol	ND		ug/kg	380	--	1
4-Nitrophenol	ND		ug/kg	250	--	1
2,4-Dinitrophenol	ND		ug/kg	840	--	1
4,6-Dinitro-o-cresol	ND		ug/kg	460	--	1
Pentachlorophenol	ND		ug/kg	140	--	1
Phenol	ND		ug/kg	180	--	1
2-Methylphenol	ND		ug/kg	180	--	1
3-Methylphenol/4-Methylphenol	ND		ug/kg	250	--	1
2,4,5-Trichlorophenol	ND		ug/kg	180	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-02
 Client ID: 1607530-B103(S3-S4)
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 09:55
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Semivolatile Organics by GC/MS - Westborough Lab

Benzoic Acid	ND		ug/kg	570	--	1
Benzyl Alcohol	ND		ug/kg	180	--	1
Carbazole	ND		ug/kg	180	--	1
Pyridine	ND		ug/kg	700	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	93		25-120
Phenol-d6	98		10-120
Nitrobenzene-d5	98		23-120
2-Fluorobiphenyl	85		30-120
2,4,6-Tribromophenol	92		10-136
4-Terphenyl-d14	93		18-120

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-03
 Client ID: 1607530-B102(S1-S2)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8270D
 Analytical Date: 09/02/16 05:43
 Analyst: KV
 Percent Solids: 84%

Date Collected: 08/26/16 10:45
 Date Received: 08/29/16
 Field Prep: Not Specified
 Extraction Method: EPA 3546
 Extraction Date: 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Acenaphthene	ND		ug/kg	150	--	1
Benzidine	ND		ug/kg	640	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	190	--	1
Hexachlorobenzene	ND		ug/kg	120	--	1
Bis(2-chloroethyl)ether	ND		ug/kg	170	--	1
2-Chloronaphthalene	ND		ug/kg	190	--	1
1,2-Dichlorobenzene	ND		ug/kg	190	--	1
1,3-Dichlorobenzene	ND		ug/kg	190	--	1
1,4-Dichlorobenzene	ND		ug/kg	190	--	1
3,3'-Dichlorobenzidine	ND		ug/kg	190	--	1
2,4-Dinitrotoluene	ND		ug/kg	190	--	1
2,6-Dinitrotoluene	ND		ug/kg	190	--	1
Azobenzene	ND		ug/kg	190	--	1
Fluoranthene	ND		ug/kg	120	--	1
4-Chlorophenyl phenyl ether	ND		ug/kg	190	--	1
4-Bromophenyl phenyl ether	ND		ug/kg	190	--	1
Bis(2-chloroisopropyl)ether	ND		ug/kg	230	--	1
Bis(2-chloroethoxy)methane	ND		ug/kg	210	--	1
Hexachlorobutadiene	ND		ug/kg	190	--	1
Hexachlorocyclopentadiene	ND		ug/kg	550	--	1
Hexachloroethane	ND		ug/kg	150	--	1
Isophorone	ND		ug/kg	170	--	1
Naphthalene	ND		ug/kg	190	--	1
Nitrobenzene	ND		ug/kg	170	--	1
NDPA/DPA	ND		ug/kg	150	--	1
n-Nitrosodi-n-propylamine	ND		ug/kg	190	--	1
Bis(2-ethylhexyl)phthalate	ND		ug/kg	190	--	1
Butyl benzyl phthalate	ND		ug/kg	190	--	1
Di-n-butylphthalate	ND		ug/kg	190	--	1
Di-n-octylphthalate	ND		ug/kg	190	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-03
 Client ID: 1607530-B102(S1-S2)
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 10:45
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Diethyl phthalate	ND		ug/kg	190	--	1
Dimethyl phthalate	ND		ug/kg	190	--	1
Benzo(a)anthracene	ND		ug/kg	120	--	1
Benzo(a)pyrene	ND		ug/kg	150	--	1
Benzo(b)fluoranthene	ND		ug/kg	120	--	1
Benzo(k)fluoranthene	ND		ug/kg	120	--	1
Chrysene	ND		ug/kg	120	--	1
Acenaphthylene	ND		ug/kg	150	--	1
Anthracene	ND		ug/kg	120	--	1
Benzo(ghi)perylene	ND		ug/kg	150	--	1
Fluorene	ND		ug/kg	190	--	1
Phenanthrene	ND		ug/kg	120	--	1
Dibenzo(a,h)anthracene	ND		ug/kg	120	--	1
Indeno(1,2,3-cd)pyrene	ND		ug/kg	150	--	1
Pyrene	ND		ug/kg	120	--	1
Biphenyl	ND		ug/kg	440	--	1
Aniline	ND		ug/kg	230	--	1
4-Chloroaniline	ND		ug/kg	190	--	1
1-Methylnaphthalene	ND		ug/kg	190	--	1
2-Nitroaniline	ND		ug/kg	190	--	1
3-Nitroaniline	ND		ug/kg	190	--	1
4-Nitroaniline	ND		ug/kg	190	--	1
Dibenzofuran	ND		ug/kg	190	--	1
2-Methylnaphthalene	ND		ug/kg	230	--	1
n-Nitrosodimethylamine	ND		ug/kg	390	--	1
2,4,6-Trichlorophenol	ND		ug/kg	120	--	1
p-Chloro-m-cresol	ND		ug/kg	190	--	1
2-Chlorophenol	ND		ug/kg	190	--	1
2,4-Dichlorophenol	ND		ug/kg	170	--	1
2,4-Dimethylphenol	ND		ug/kg	190	--	1
2-Nitrophenol	ND		ug/kg	420	--	1
4-Nitrophenol	ND		ug/kg	270	--	1
2,4-Dinitrophenol	ND		ug/kg	930	--	1
4,6-Dinitro-o-cresol	ND		ug/kg	500	--	1
Pentachlorophenol	ND		ug/kg	150	--	1
Phenol	ND		ug/kg	190	--	1
2-Methylphenol	ND		ug/kg	190	--	1
3-Methylphenol/4-Methylphenol	ND		ug/kg	280	--	1
2,4,5-Trichlorophenol	ND		ug/kg	190	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-03
 Client ID: 1607530-B102(S1-S2)
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 10:45
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Semivolatile Organics by GC/MS - Westborough Lab

Benzoic Acid	ND		ug/kg	630	--	1
Benzyl Alcohol	ND		ug/kg	190	--	1
Carbazole	ND		ug/kg	190	--	1
Pyridine	ND		ug/kg	770	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	89		25-120
Phenol-d6	93		10-120
Nitrobenzene-d5	96		23-120
2-Fluorobiphenyl	82		30-120
2,4,6-Tribromophenol	90		10-136
4-Terphenyl-d14	86		18-120

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-04
 Client ID: 1607530-B102(S3-S4)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8270D
 Analytical Date: 09/02/16 06:08
 Analyst: KV
 Percent Solids: 79%

Date Collected: 08/26/16 11:00
 Date Received: 08/29/16
 Field Prep: Not Specified
 Extraction Method: EPA 3546
 Extraction Date: 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Acenaphthene	ND		ug/kg	170	--	1
Benzidine	ND		ug/kg	690	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	210	--	1
Hexachlorobenzene	ND		ug/kg	120	--	1
Bis(2-chloroethyl)ether	ND		ug/kg	190	--	1
2-Chloronaphthalene	ND		ug/kg	210	--	1
1,2-Dichlorobenzene	ND		ug/kg	210	--	1
1,3-Dichlorobenzene	ND		ug/kg	210	--	1
1,4-Dichlorobenzene	ND		ug/kg	210	--	1
3,3'-Dichlorobenzidine	ND		ug/kg	210	--	1
2,4-Dinitrotoluene	ND		ug/kg	210	--	1
2,6-Dinitrotoluene	ND		ug/kg	210	--	1
Azobenzene	ND		ug/kg	210	--	1
Fluoranthene	ND		ug/kg	120	--	1
4-Chlorophenyl phenyl ether	ND		ug/kg	210	--	1
4-Bromophenyl phenyl ether	ND		ug/kg	210	--	1
Bis(2-chloroisopropyl)ether	ND		ug/kg	250	--	1
Bis(2-chloroethoxy)methane	ND		ug/kg	220	--	1
Hexachlorobutadiene	ND		ug/kg	210	--	1
Hexachlorocyclopentadiene	ND		ug/kg	600	--	1
Hexachloroethane	ND		ug/kg	170	--	1
Isophorone	ND		ug/kg	190	--	1
Naphthalene	ND		ug/kg	210	--	1
Nitrobenzene	ND		ug/kg	190	--	1
NDPA/DPA	ND		ug/kg	170	--	1
n-Nitrosodi-n-propylamine	ND		ug/kg	210	--	1
Bis(2-ethylhexyl)phthalate	ND		ug/kg	210	--	1
Butyl benzyl phthalate	ND		ug/kg	210	--	1
Di-n-butylphthalate	ND		ug/kg	210	--	1
Di-n-octylphthalate	ND		ug/kg	210	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-04
 Client ID: 1607530-B102(S3-S4)
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 11:00
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Diethyl phthalate	ND		ug/kg	210	--	1
Dimethyl phthalate	ND		ug/kg	210	--	1
Benzo(a)anthracene	ND		ug/kg	120	--	1
Benzo(a)pyrene	ND		ug/kg	170	--	1
Benzo(b)fluoranthene	ND		ug/kg	120	--	1
Benzo(k)fluoranthene	ND		ug/kg	120	--	1
Chrysene	ND		ug/kg	120	--	1
Acenaphthylene	ND		ug/kg	170	--	1
Anthracene	ND		ug/kg	120	--	1
Benzo(ghi)perylene	ND		ug/kg	170	--	1
Fluorene	ND		ug/kg	210	--	1
Phenanthrene	ND		ug/kg	120	--	1
Dibenzo(a,h)anthracene	ND		ug/kg	120	--	1
Indeno(1,2,3-cd)pyrene	ND		ug/kg	170	--	1
Pyrene	ND		ug/kg	120	--	1
Biphenyl	ND		ug/kg	480	--	1
Aniline	ND		ug/kg	250	--	1
4-Chloroaniline	ND		ug/kg	210	--	1
1-Methylnaphthalene	ND		ug/kg	210	--	1
2-Nitroaniline	ND		ug/kg	210	--	1
3-Nitroaniline	ND		ug/kg	210	--	1
4-Nitroaniline	ND		ug/kg	210	--	1
Dibenzofuran	ND		ug/kg	210	--	1
2-Methylnaphthalene	ND		ug/kg	250	--	1
n-Nitrosodimethylamine	ND		ug/kg	420	--	1
2,4,6-Trichlorophenol	ND		ug/kg	120	--	1
p-Chloro-m-cresol	ND		ug/kg	210	--	1
2-Chlorophenol	ND		ug/kg	210	--	1
2,4-Dichlorophenol	ND		ug/kg	190	--	1
2,4-Dimethylphenol	ND		ug/kg	210	--	1
2-Nitrophenol	ND		ug/kg	450	--	1
4-Nitrophenol	ND		ug/kg	290	--	1
2,4-Dinitrophenol	ND		ug/kg	1000	--	1
4,6-Dinitro-o-cresol	ND		ug/kg	540	--	1
Pentachlorophenol	ND		ug/kg	170	--	1
Phenol	ND		ug/kg	210	--	1
2-Methylphenol	ND		ug/kg	210	--	1
3-Methylphenol/4-Methylphenol	ND		ug/kg	300	--	1
2,4,5-Trichlorophenol	ND		ug/kg	210	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-04
 Client ID: 1607530-B102(S3-S4)
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 11:00
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Semivolatile Organics by GC/MS - Westborough Lab

Benzoic Acid	ND		ug/kg	680	--	1
Benzyl Alcohol	ND		ug/kg	210	--	1
Carbazole	ND		ug/kg	210	--	1
Pyridine	ND		ug/kg	830	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	91		25-120
Phenol-d6	94		10-120
Nitrobenzene-d5	97		23-120
2-Fluorobiphenyl	79		30-120
2,4,6-Tribromophenol	84		10-136
4-Terphenyl-d14	82		18-120

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-05
 Client ID: 1607530-B101(S1-S2)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8270D
 Analytical Date: 09/02/16 06:34
 Analyst: KV
 Percent Solids: 84%

Date Collected: 08/26/16 11:45
 Date Received: 08/29/16
 Field Prep: Not Specified
 Extraction Method: EPA 3546
 Extraction Date: 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Acenaphthene	ND		ug/kg	160	--	1
Benzidine	ND		ug/kg	640	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	200	--	1
Hexachlorobenzene	ND		ug/kg	120	--	1
Bis(2-chloroethyl)ether	ND		ug/kg	180	--	1
2-Chloronaphthalene	ND		ug/kg	200	--	1
1,2-Dichlorobenzene	ND		ug/kg	200	--	1
1,3-Dichlorobenzene	ND		ug/kg	200	--	1
1,4-Dichlorobenzene	ND		ug/kg	200	--	1
3,3'-Dichlorobenzidine	ND		ug/kg	200	--	1
2,4-Dinitrotoluene	ND		ug/kg	200	--	1
2,6-Dinitrotoluene	ND		ug/kg	200	--	1
Azobenzene	ND		ug/kg	200	--	1
Fluoranthene	ND		ug/kg	120	--	1
4-Chlorophenyl phenyl ether	ND		ug/kg	200	--	1
4-Bromophenyl phenyl ether	ND		ug/kg	200	--	1
Bis(2-chloroisopropyl)ether	ND		ug/kg	230	--	1
Bis(2-chloroethoxy)methane	ND		ug/kg	210	--	1
Hexachlorobutadiene	ND		ug/kg	200	--	1
Hexachlorocyclopentadiene	ND		ug/kg	560	--	1
Hexachloroethane	ND		ug/kg	160	--	1
Isophorone	ND		ug/kg	180	--	1
Naphthalene	ND		ug/kg	200	--	1
Nitrobenzene	ND		ug/kg	180	--	1
NDPA/DPA	ND		ug/kg	160	--	1
n-Nitrosodi-n-propylamine	ND		ug/kg	200	--	1
Bis(2-ethylhexyl)phthalate	ND		ug/kg	200	--	1
Butyl benzyl phthalate	ND		ug/kg	200	--	1
Di-n-butylphthalate	ND		ug/kg	200	--	1
Di-n-octylphthalate	ND		ug/kg	200	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-05
 Client ID: 1607530-B101(S1-S2)
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 11:45
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Diethyl phthalate	ND		ug/kg	200	--	1
Dimethyl phthalate	ND		ug/kg	200	--	1
Benzo(a)anthracene	ND		ug/kg	120	--	1
Benzo(a)pyrene	ND		ug/kg	160	--	1
Benzo(b)fluoranthene	ND		ug/kg	120	--	1
Benzo(k)fluoranthene	ND		ug/kg	120	--	1
Chrysene	ND		ug/kg	120	--	1
Acenaphthylene	ND		ug/kg	160	--	1
Anthracene	ND		ug/kg	120	--	1
Benzo(ghi)perylene	ND		ug/kg	160	--	1
Fluorene	ND		ug/kg	200	--	1
Phenanthrene	ND		ug/kg	120	--	1
Dibenzo(a,h)anthracene	ND		ug/kg	120	--	1
Indeno(1,2,3-cd)pyrene	ND		ug/kg	160	--	1
Pyrene	ND		ug/kg	120	--	1
Biphenyl	ND		ug/kg	440	--	1
Aniline	ND		ug/kg	230	--	1
4-Chloroaniline	ND		ug/kg	200	--	1
1-Methylnaphthalene	ND		ug/kg	200	--	1
2-Nitroaniline	ND		ug/kg	200	--	1
3-Nitroaniline	ND		ug/kg	200	--	1
4-Nitroaniline	ND		ug/kg	200	--	1
Dibenzofuran	ND		ug/kg	200	--	1
2-Methylnaphthalene	ND		ug/kg	230	--	1
n-Nitrosodimethylamine	ND		ug/kg	390	--	1
2,4,6-Trichlorophenol	ND		ug/kg	120	--	1
p-Chloro-m-cresol	ND		ug/kg	200	--	1
2-Chlorophenol	ND		ug/kg	200	--	1
2,4-Dichlorophenol	ND		ug/kg	180	--	1
2,4-Dimethylphenol	ND		ug/kg	200	--	1
2-Nitrophenol	ND		ug/kg	420	--	1
4-Nitrophenol	ND		ug/kg	270	--	1
2,4-Dinitrophenol	ND		ug/kg	940	--	1
4,6-Dinitro-o-cresol	ND		ug/kg	510	--	1
Pentachlorophenol	ND		ug/kg	160	--	1
Phenol	ND		ug/kg	200	--	1
2-Methylphenol	ND		ug/kg	200	--	1
3-Methylphenol/4-Methylphenol	ND		ug/kg	280	--	1
2,4,5-Trichlorophenol	ND		ug/kg	200	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-05
Client ID: 1607530-B101(S1-S2)
Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 11:45
Date Received: 08/29/16
Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Semivolatile Organics by GC/MS - Westborough Lab

Benzoic Acid	ND		ug/kg	630	--	1
Benzyl Alcohol	ND		ug/kg	200	--	1
Carbazole	ND		ug/kg	200	--	1
Pyridine	ND		ug/kg	780	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	86		25-120
Phenol-d6	89		10-120
Nitrobenzene-d5	95		23-120
2-Fluorobiphenyl	78		30-120
2,4,6-Tribromophenol	90		10-136
4-Terphenyl-d14	87		18-120

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-06
 Client ID: 1607530-B101(S3-S4)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8270D
 Analytical Date: 09/02/16 07:00
 Analyst: KV
 Percent Solids: 81%

Date Collected: 08/26/16 12:00
 Date Received: 08/29/16
 Field Prep: Not Specified
 Extraction Method: EPA 3546
 Extraction Date: 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Acenaphthene	ND		ug/kg	160	--	1
Benzidine	ND		ug/kg	660	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	200	--	1
Hexachlorobenzene	ND		ug/kg	120	--	1
Bis(2-chloroethyl)ether	ND		ug/kg	180	--	1
2-Chloronaphthalene	ND		ug/kg	200	--	1
1,2-Dichlorobenzene	ND		ug/kg	200	--	1
1,3-Dichlorobenzene	ND		ug/kg	200	--	1
1,4-Dichlorobenzene	ND		ug/kg	200	--	1
3,3'-Dichlorobenzidine	ND		ug/kg	200	--	1
2,4-Dinitrotoluene	ND		ug/kg	200	--	1
2,6-Dinitrotoluene	ND		ug/kg	200	--	1
Azobenzene	ND		ug/kg	200	--	1
Fluoranthene	ND		ug/kg	120	--	1
4-Chlorophenyl phenyl ether	ND		ug/kg	200	--	1
4-Bromophenyl phenyl ether	ND		ug/kg	200	--	1
Bis(2-chloroisopropyl)ether	ND		ug/kg	240	--	1
Bis(2-chloroethoxy)methane	ND		ug/kg	220	--	1
Hexachlorobutadiene	ND		ug/kg	200	--	1
Hexachlorocyclopentadiene	ND		ug/kg	580	--	1
Hexachloroethane	ND		ug/kg	160	--	1
Isophorone	ND		ug/kg	180	--	1
Naphthalene	ND		ug/kg	200	--	1
Nitrobenzene	ND		ug/kg	180	--	1
NDPA/DPA	ND		ug/kg	160	--	1
n-Nitrosodi-n-propylamine	ND		ug/kg	200	--	1
Bis(2-ethylhexyl)phthalate	ND		ug/kg	200	--	1
Butyl benzyl phthalate	ND		ug/kg	200	--	1
Di-n-butylphthalate	ND		ug/kg	200	--	1
Di-n-octylphthalate	ND		ug/kg	200	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-06
 Client ID: 1607530-B101(S3-S4)
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 12:00
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Semivolatile Organics by GC/MS - Westborough Lab						
Diethyl phthalate	ND		ug/kg	200	--	1
Dimethyl phthalate	ND		ug/kg	200	--	1
Benzo(a)anthracene	ND		ug/kg	120	--	1
Benzo(a)pyrene	ND		ug/kg	160	--	1
Benzo(b)fluoranthene	ND		ug/kg	120	--	1
Benzo(k)fluoranthene	ND		ug/kg	120	--	1
Chrysene	ND		ug/kg	120	--	1
Acenaphthylene	ND		ug/kg	160	--	1
Anthracene	ND		ug/kg	120	--	1
Benzo(ghi)perylene	ND		ug/kg	160	--	1
Fluorene	ND		ug/kg	200	--	1
Phenanthrene	ND		ug/kg	120	--	1
Dibenzo(a,h)anthracene	ND		ug/kg	120	--	1
Indeno(1,2,3-cd)pyrene	ND		ug/kg	160	--	1
Pyrene	ND		ug/kg	120	--	1
Biphenyl	ND		ug/kg	460	--	1
Aniline	ND		ug/kg	240	--	1
4-Chloroaniline	ND		ug/kg	200	--	1
1-Methylnaphthalene	ND		ug/kg	200	--	1
2-Nitroaniline	ND		ug/kg	200	--	1
3-Nitroaniline	ND		ug/kg	200	--	1
4-Nitroaniline	ND		ug/kg	200	--	1
Dibenzofuran	ND		ug/kg	200	--	1
2-Methylnaphthalene	ND		ug/kg	240	--	1
n-Nitrosodimethylamine	ND		ug/kg	400	--	1
2,4,6-Trichlorophenol	ND		ug/kg	120	--	1
p-Chloro-m-cresol	ND		ug/kg	200	--	1
2-Chlorophenol	ND		ug/kg	200	--	1
2,4-Dichlorophenol	ND		ug/kg	180	--	1
2,4-Dimethylphenol	ND		ug/kg	200	--	1
2-Nitrophenol	ND		ug/kg	440	--	1
4-Nitrophenol	ND		ug/kg	280	--	1
2,4-Dinitrophenol	ND		ug/kg	970	--	1
4,6-Dinitro-o-cresol	ND		ug/kg	520	--	1
Pentachlorophenol	ND		ug/kg	160	--	1
Phenol	ND		ug/kg	200	--	1
2-Methylphenol	ND		ug/kg	200	--	1
3-Methylphenol/4-Methylphenol	ND		ug/kg	290	--	1
2,4,5-Trichlorophenol	ND		ug/kg	200	--	1

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-06
 Client ID: 1607530-B101(S3-S4)
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 12:00
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Semivolatile Organics by GC/MS - Westborough Lab

Benzoic Acid	ND		ug/kg	650	--	1
Benzyl Alcohol	ND		ug/kg	200	--	1
Carbazole	ND		ug/kg	200	--	1
Pyridine	ND		ug/kg	810	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	111		25-120
Phenol-d6	115		10-120
Nitrobenzene-d5	120		23-120
2-Fluorobiphenyl	92		30-120
2,4,6-Tribromophenol	92		10-136
4-Terphenyl-d14	90		18-120

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Method Blank Analysis
Batch Quality Control

Analytical Method: 1,8270D
Analytical Date: 09/02/16 03:36
Analyst: KV

Extraction Method: EPA 3546
Extraction Date: 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL
Semivolatile Organics by GC/MS - Westborough Lab for sample(s): 01-06 Batch: WG927494-1					
Acenaphthene	ND		ug/kg	130	--
Benzidine	ND		ug/kg	540	--
1,2,4-Trichlorobenzene	ND		ug/kg	160	--
Hexachlorobenzene	ND		ug/kg	98	--
Bis(2-chloroethyl)ether	ND		ug/kg	150	--
2-Chloronaphthalene	ND		ug/kg	160	--
1,2-Dichlorobenzene	ND		ug/kg	160	--
1,3-Dichlorobenzene	ND		ug/kg	160	--
1,4-Dichlorobenzene	ND		ug/kg	160	--
3,3'-Dichlorobenzidine	ND		ug/kg	160	--
2,4-Dinitrotoluene	ND		ug/kg	160	--
2,6-Dinitrotoluene	ND		ug/kg	160	--
Azobenzene	ND		ug/kg	160	--
Fluoranthene	ND		ug/kg	98	--
4-Chlorophenyl phenyl ether	ND		ug/kg	160	--
4-Bromophenyl phenyl ether	ND		ug/kg	160	--
Bis(2-chloroisopropyl)ether	ND		ug/kg	200	--
Bis(2-chloroethoxy)methane	ND		ug/kg	180	--
Hexachlorobutadiene	ND		ug/kg	160	--
Hexachlorocyclopentadiene	ND		ug/kg	470	--
Hexachloroethane	ND		ug/kg	130	--
Isophorone	ND		ug/kg	150	--
Naphthalene	ND		ug/kg	160	--
Nitrobenzene	ND		ug/kg	150	--
NDPA/DPA	ND		ug/kg	130	--
n-Nitrosodi-n-propylamine	ND		ug/kg	160	--
Bis(2-ethylhexyl)phthalate	ND		ug/kg	160	--
Butyl benzyl phthalate	ND		ug/kg	160	--
Di-n-butylphthalate	ND		ug/kg	160	--

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Method Blank Analysis
Batch Quality Control

Analytical Method: 1,8270D
Analytical Date: 09/02/16 03:36
Analyst: KV

Extraction Method: EPA 3546
Extraction Date: 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL
Semivolatile Organics by GC/MS - Westborough Lab for sample(s): 01-06 Batch: WG927494-1					
Di-n-octylphthalate	ND		ug/kg	160	--
Diethyl phthalate	ND		ug/kg	160	--
Dimethyl phthalate	ND		ug/kg	160	--
Benzo(a)anthracene	ND		ug/kg	98	--
Benzo(a)pyrene	ND		ug/kg	130	--
Benzo(b)fluoranthene	ND		ug/kg	98	--
Benzo(k)fluoranthene	ND		ug/kg	98	--
Chrysene	ND		ug/kg	98	--
Acenaphthylene	ND		ug/kg	130	--
Anthracene	ND		ug/kg	98	--
Benzo(ghi)perylene	ND		ug/kg	130	--
Fluorene	ND		ug/kg	160	--
Phenanthrene	ND		ug/kg	98	--
Dibenzo(a,h)anthracene	ND		ug/kg	98	--
Indeno(1,2,3-cd)pyrene	ND		ug/kg	130	--
Pyrene	ND		ug/kg	98	--
Biphenyl	ND		ug/kg	370	--
Aniline	ND		ug/kg	200	--
4-Chloroaniline	ND		ug/kg	160	--
1-Methylnaphthalene	ND		ug/kg	160	--
2-Nitroaniline	ND		ug/kg	160	--
3-Nitroaniline	ND		ug/kg	160	--
4-Nitroaniline	ND		ug/kg	160	--
Dibenzofuran	ND		ug/kg	160	--
2-Methylnaphthalene	ND		ug/kg	200	--
n-Nitrosodimethylamine	ND		ug/kg	330	--
2,4,6-Trichlorophenol	ND		ug/kg	98	--
p-Chloro-m-cresol	ND		ug/kg	160	--
2-Chlorophenol	ND		ug/kg	160	--

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Method Blank Analysis
Batch Quality Control

Analytical Method: 1,8270D
Analytical Date: 09/02/16 03:36
Analyst: KV

Extraction Method: EPA 3546
Extraction Date: 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL
Semivolatile Organics by GC/MS - Westborough Lab for sample(s): 01-06 Batch: WG927494-1					
2,4-Dichlorophenol	ND		ug/kg	150	--
2,4-Dimethylphenol	ND		ug/kg	160	--
2-Nitrophenol	ND		ug/kg	350	--
4-Nitrophenol	ND		ug/kg	230	--
2,4-Dinitrophenol	ND		ug/kg	780	--
4,6-Dinitro-o-cresol	ND		ug/kg	420	--
Pentachlorophenol	ND		ug/kg	130	--
Phenol	ND		ug/kg	160	--
2-Methylphenol	ND		ug/kg	160	--
3-Methylphenol/4-Methylphenol	ND		ug/kg	240	--
2,4,5-Trichlorophenol	ND		ug/kg	160	--
Benzoic Acid	ND		ug/kg	530	--
Benzyl Alcohol	ND		ug/kg	160	--
Carbazole	ND		ug/kg	160	--
Pyridine	ND		ug/kg	650	--

Surrogate	%Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	71		25-120
Phenol-d6	71		10-120
Nitrobenzene-d5	74		23-120
2-Fluorobiphenyl	61		30-120
2,4,6-Tribromophenol	64		10-136
4-Terphenyl-d14	67		18-120

Lab Control Sample Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Semivolatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-06 Batch: WG927494-2 WG927494-3								
Acenaphthene	74		75		31-137	1		50
Benzidine	52		47		10-66	10		50
1,2,4-Trichlorobenzene	73		82		38-107	12		50
Hexachlorobenzene	74		74		40-140	0		50
Bis(2-chloroethyl)ether	75		85		40-140	13		50
2-Chloronaphthalene	74		75		40-140	1		50
1,2-Dichlorobenzene	69		83		40-140	18		50
1,3-Dichlorobenzene	67		80		40-140	18		50
1,4-Dichlorobenzene	68		82		28-104	19		50
3,3'-Dichlorobenzidine	82		76		40-140	8		50
2,4-Dinitrotoluene	96	Q	93	Q	28-89	3		50
2,6-Dinitrotoluene	83		84		40-140	1		50
Azobenzene	76		77		40-140	1		50
Fluoranthene	80		77		40-140	4		50
4-Chlorophenyl phenyl ether	75		75		40-140	0		50
4-Bromophenyl phenyl ether	74		75		40-140	1		50
Bis(2-chloroisopropyl)ether	73		80		40-140	9		50
Bis(2-chloroethoxy)methane	77		84		40-117	9		50
Hexachlorobutadiene	71		77		40-140	8		50
Hexachlorocyclopentadiene	89		93		40-140	4		50
Hexachloroethane	73		88		40-140	19		50

Lab Control Sample Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Semivolatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-06 Batch: WG927494-2 WG927494-3								
Isophorone	82		89		40-140	8		50
Naphthalene	73		79		40-140	8		50
Nitrobenzene	89		100		40-140	12		50
NDPA/DPA	76		77		36-157	1		50
n-Nitrosodi-n-propylamine	86		92		32-121	7		50
Bis(2-ethylhexyl)phthalate	88		84		40-140	5		50
Butyl benzyl phthalate	95		91		40-140	4		50
Di-n-butylphthalate	89		85		40-140	5		50
Di-n-octylphthalate	98		95		40-140	3		50
Diethyl phthalate	82		79		40-140	4		50
Dimethyl phthalate	83		81		40-140	2		50
Benzo(a)anthracene	79		77		40-140	3		50
Benzo(a)pyrene	86		84		40-140	2		50
Benzo(b)fluoranthene	81		80		40-140	1		50
Benzo(k)fluoranthene	81		75		40-140	8		50
Chrysene	76		74		40-140	3		50
Acenaphthylene	80		81		40-140	1		50
Anthracene	81		80		40-140	1		50
Benzo(ghi)perylene	82		80		40-140	2		50
Fluorene	77		77		40-140	0		50
Phenanthrene	72		72		40-140	0		50

Lab Control Sample Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Semivolatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-06 Batch: WG927494-2 WG927494-3								
Dibenzo(a,h)anthracene	84		83		40-140	1		50
Indeno(1,2,3-cd)pyrene	84		83		40-140	1		50
Pyrene	77		74		35-142	4		50
Biphenyl	80		81		54-104	1		50
Aniline	64		69		40-140	8		50
4-Chloroaniline	66		74		40-140	11		50
1-Methylnaphthalene	72		78		26-130	8		50
2-Nitroaniline	91		91		47-134	0		50
3-Nitroaniline	84		79		26-129	6		50
4-Nitroaniline	86		83		41-125	4		50
Dibenzofuran	75		76		40-140	1		50
2-Methylnaphthalene	74		78		40-140	5		50
1,2,4,5-Tetrachlorobenzene	75		80		40-117	6		50
Acetophenone	83		91		14-144	9		50
n-Nitrosodimethylamine	69		83		22-100	18		50
2,4,6-Trichlorophenol	84		83		30-130	1		50
p-Chloro-m-cresol	90		91		26-103	1		50
2-Chlorophenol	87		99		25-102	13		50
2,4-Dichlorophenol	94		97		30-130	3		50
2,4-Dimethylphenol	95		105		30-130	10		50
2-Nitrophenol	113		123		30-130	8		50

Lab Control Sample Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Semivolatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-06 Batch: WG927494-2 WG927494-3								
4-Nitrophenol	85		83		11-114	2		50
2,4-Dinitrophenol	118		109		4-130	8		50
4,6-Dinitro-o-cresol	126		120		10-130	5		50
Pentachlorophenol	76		76		17-109	0		50
Phenol	81		90		26-90	11		50
2-Methylphenol	88		95		30-130	8		50
3-Methylphenol/4-Methylphenol	86		91		30-130	6		50
2,4,5-Trichlorophenol	92		93		30-130	1		50
Benzoic Acid	45		45		10-110	0		50
Benzyl Alcohol	85		94		40-140	10		50
Carbazole	79		76		54-128	4		50
Pyridine	54		72		10-93	29		50
Parathion, ethyl	135		131		40-140	3		50
Atrazine	97		97		40-140	0		50
Benzaldehyde	63		75		40-140	17		50
Caprolactam	90		89		15-130	1		50
2,3,4,6-Tetrachlorophenol	88		86		40-140	2		50

Lab Control Sample Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	<i>LCS</i> %Recovery	<i>Qual</i>	<i>LCSD</i> %Recovery	<i>Qual</i>	<i>%Recovery</i> Limits	<i>RPD</i>	<i>Qual</i>	<i>RPD</i> Limits
-----------	-------------------------	-------------	--------------------------	-------------	----------------------------	------------	-------------	----------------------

Semivolatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-06 Batch: WG927494-2 WG927494-3

<i>Surrogate</i>	<i>LCS</i> %Recovery	<i>Qual</i>	<i>LCSD</i> %Recovery	<i>Qual</i>	<i>Acceptance</i> Criteria
2-Fluorophenol	86		97		25-120
Phenol-d6	87		97		10-120
Nitrobenzene-d5	95		102		23-120
2-Fluorobiphenyl	75		76		30-120
2,4,6-Tribromophenol	80		81		10-136
4-Terphenyl-d14	77		74		18-120

PETROLEUM HYDROCARBONS

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-01
 Client ID: 1607530-B103(S1-S2)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8015C(M)
 Analytical Date: 09/01/16 20:20
 Analyst: DV
 Percent Solids: 93%

Date Collected: 08/26/16 09:25
 Date Received: 08/29/16
 Field Prep: Not Specified
 Extraction Method: EPA 3546
 Extraction Date: 08/31/16 20:59

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Petroleum Hydrocarbon Quantitation - Westborough Lab						
--	--	--	--	--	--	--

TPH	ND		ug/kg	35500	--	1
-----	----	--	-------	-------	----	---

Surrogate	% Recovery	Qualifier	Acceptance Criteria
o-Terphenyl	54		40-140

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-02
 Client ID: 1607530-B103(S3-S4)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8015C(M)
 Analytical Date: 09/01/16 20:53
 Analyst: DV
 Percent Solids: 92%

Date Collected: 08/26/16 09:55
 Date Received: 08/29/16
 Field Prep: Not Specified
 Extraction Method: EPA 3546
 Extraction Date: 08/31/16 20:59

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Petroleum Hydrocarbon Quantitation - Westborough Lab						
--	--	--	--	--	--	--

TPH	ND		ug/kg	34100	--	1
-----	----	--	-------	-------	----	---

Surrogate	% Recovery	Qualifier	Acceptance Criteria
o-Terphenyl	81		40-140

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-03
 Client ID: 1607530-B102(S1-S2)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8015C(M)
 Analytical Date: 09/01/16 21:25
 Analyst: DV
 Percent Solids: 84%

Date Collected: 08/26/16 10:45
 Date Received: 08/29/16
 Field Prep: Not Specified
 Extraction Method: EPA 3546
 Extraction Date: 08/31/16 20:59

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Petroleum Hydrocarbon Quantitation - Westborough Lab						
--	--	--	--	--	--	--

TPH	ND		ug/kg	39500	--	1
-----	----	--	-------	-------	----	---

Surrogate	% Recovery	Qualifier	Acceptance Criteria
o-Terphenyl	83		40-140

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-04
 Client ID: 1607530-B102(S3-S4)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8015C(M)
 Analytical Date: 09/01/16 21:57
 Analyst: DV
 Percent Solids: 79%

Date Collected: 08/26/16 11:00
 Date Received: 08/29/16
 Field Prep: Not Specified
 Extraction Method: EPA 3546
 Extraction Date: 08/31/16 20:59

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Petroleum Hydrocarbon Quantitation - Westborough Lab						
--	--	--	--	--	--	--

TPH	ND		ug/kg	39900	--	1
-----	----	--	-------	-------	----	---

Surrogate	% Recovery	Qualifier	Acceptance Criteria
o-Terphenyl	78		40-140

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-05
 Client ID: 1607530-B101(S1-S2)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8015C(M)
 Analytical Date: 09/01/16 22:29
 Analyst: DV
 Percent Solids: 84%

Date Collected: 08/26/16 11:45
 Date Received: 08/29/16
 Field Prep: Not Specified
 Extraction Method: EPA 3546
 Extraction Date: 08/31/16 20:59

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Petroleum Hydrocarbon Quantitation - Westborough Lab						
--	--	--	--	--	--	--

TPH	39000		ug/kg	37500	--	1
-----	-------	--	-------	-------	----	---

Surrogate	% Recovery	Qualifier	Acceptance Criteria
o-Terphenyl	82		40-140

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-06
 Client ID: 1607530-B101(S3-S4)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8015C(M)
 Analytical Date: 09/01/16 23:01
 Analyst: DV
 Percent Solids: 81%

Date Collected: 08/26/16 12:00
 Date Received: 08/29/16
 Field Prep: Not Specified
 Extraction Method: EPA 3546
 Extraction Date: 08/31/16 20:59

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Petroleum Hydrocarbon Quantitation - Westborough Lab						
--	--	--	--	--	--	--

TPH	ND		ug/kg	39800	--	1
-----	----	--	-------	-------	----	---

Surrogate	% Recovery	Qualifier	Acceptance Criteria
o-Terphenyl	79		40-140

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Method Blank Analysis
Batch Quality Control

Analytical Method: 1,8015C(M)
Analytical Date: 09/01/16 17:08
Analyst: SR

Extraction Method: EPA 3546
Extraction Date: 08/31/16 19:47

Parameter	Result	Qualifier	Units	RL	MDL
Petroleum Hydrocarbon Quantitation - Westborough Lab for sample(s): 01-06 Batch: WG927867-1					
TPH	ND		ug/kg	33000	--

Surrogate	%Recovery	Qualifier	Acceptance Criteria
o-Terphenyl	85		40-140

Lab Control Sample Analysis Batch Quality Control

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Petroleum Hydrocarbon Quantitation - Westborough Lab Associated sample(s): 01-06 Batch: WG927867-2								
TPH	92		-		40-140	-		40

Surrogate	LCS %Recovery	Qual	LCSD %Recovery	Qual	Acceptance Criteria
o-Terphenyl	89				40-140

PCBS

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-01
 Client ID: 1607530-B103(S1-S2)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8082A
 Analytical Date: 09/02/16 22:16
 Analyst: JA
 Percent Solids: 93%

Date Collected: 08/26/16 09:25
 Date Received: 08/29/16
 Field Prep: Not Specified
 Extraction Method: EPA 3546
 Extraction Date: 08/31/16 18:23
 Cleanup Method: EPA 3665A
 Cleanup Date: 09/01/16
 Cleanup Method: EPA 3660B
 Cleanup Date: 09/01/16

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Column
PCB by GC - Westborough Lab							
Aroclor 1016	ND		ug/kg	33.9	--	1	A
Aroclor 1221	ND		ug/kg	33.9	--	1	A
Aroclor 1232	ND		ug/kg	33.9	--	1	A
Aroclor 1242	ND		ug/kg	33.9	--	1	A
Aroclor 1248	ND		ug/kg	33.9	--	1	A
Aroclor 1254	ND		ug/kg	33.9	--	1	A
Aroclor 1260	ND		ug/kg	33.9	--	1	A
Aroclor 1262	ND		ug/kg	33.9	--	1	A
Aroclor 1268	ND		ug/kg	33.9	--	1	A
PCBs, Total	ND		ug/kg	33.9	--	1	A

Surrogate	% Recovery	Qualifier	Acceptance Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	67		30-150	A
Decachlorobiphenyl	67		30-150	A
2,4,5,6-Tetrachloro-m-xylene	72		30-150	B
Decachlorobiphenyl	75		30-150	B

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-02
Client ID: 1607530-B103(S3-S4)
Sample Location: NEWINGTON, NH
Matrix: Soil
Analytical Method: 1,8082A
Analytical Date: 09/02/16 22:31
Analyst: JA
Percent Solids: 92%

Date Collected: 08/26/16 09:55
Date Received: 08/29/16
Field Prep: Not Specified
Extraction Method: EPA 3546
Extraction Date: 08/31/16 18:23
Cleanup Method: EPA 3665A
Cleanup Date: 09/01/16
Cleanup Method: EPA 3660B
Cleanup Date: 09/01/16

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Column
PCB by GC - Westborough Lab							
Aroclor 1016	ND		ug/kg	34.4	--	1	A
Aroclor 1221	ND		ug/kg	34.4	--	1	A
Aroclor 1232	ND		ug/kg	34.4	--	1	A
Aroclor 1242	ND		ug/kg	34.4	--	1	A
Aroclor 1248	ND		ug/kg	34.4	--	1	A
Aroclor 1254	ND		ug/kg	34.4	--	1	A
Aroclor 1260	ND		ug/kg	34.4	--	1	A
Aroclor 1262	ND		ug/kg	34.4	--	1	A
Aroclor 1268	ND		ug/kg	34.4	--	1	A
PCBs, Total	ND		ug/kg	34.4	--	1	A

Surrogate	% Recovery	Qualifier	Acceptance Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	78		30-150	A
Decachlorobiphenyl	82		30-150	A
2,4,5,6-Tetrachloro-m-xylene	82		30-150	B
Decachlorobiphenyl	85		30-150	B

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-03
 Client ID: 1607530-B102(S1-S2)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8082A
 Analytical Date: 09/02/16 22:45
 Analyst: JA
 Percent Solids: 84%

Date Collected: 08/26/16 10:45
 Date Received: 08/29/16
 Field Prep: Not Specified
 Extraction Method: EPA 3546
 Extraction Date: 08/31/16 18:23
 Cleanup Method: EPA 3665A
 Cleanup Date: 09/01/16
 Cleanup Method: EPA 3660B
 Cleanup Date: 09/01/16

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Column
PCB by GC - Westborough Lab							
Aroclor 1016	ND		ug/kg	39.1	--	1	A
Aroclor 1221	ND		ug/kg	39.1	--	1	A
Aroclor 1232	ND		ug/kg	39.1	--	1	A
Aroclor 1242	ND		ug/kg	39.1	--	1	A
Aroclor 1248	ND		ug/kg	39.1	--	1	A
Aroclor 1254	ND		ug/kg	39.1	--	1	A
Aroclor 1260	ND		ug/kg	39.1	--	1	A
Aroclor 1262	ND		ug/kg	39.1	--	1	A
Aroclor 1268	ND		ug/kg	39.1	--	1	A
PCBs, Total	ND		ug/kg	39.1	--	1	A

Surrogate	% Recovery	Qualifier	Acceptance Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	77		30-150	A
Decachlorobiphenyl	84		30-150	A
2,4,5,6-Tetrachloro-m-xylene	78		30-150	B
Decachlorobiphenyl	93		30-150	B

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-04
 Client ID: 1607530-B102(S3-S4)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8082A
 Analytical Date: 09/04/16 16:48
 Analyst: KEG
 Percent Solids: 79%

Date Collected: 08/26/16 11:00
 Date Received: 08/29/16
 Field Prep: Not Specified
 Extraction Method: EPA 3546
 Extraction Date: 09/04/16 06:18
 Cleanup Method: EPA 3665A
 Cleanup Date: 09/04/16
 Cleanup Method: EPA 3660B
 Cleanup Date: 09/04/16

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Column
PCB by GC - Westborough Lab							
Aroclor 1016	ND		ug/kg	41.5	--	1	A
Aroclor 1221	ND		ug/kg	41.5	--	1	A
Aroclor 1232	ND		ug/kg	41.5	--	1	A
Aroclor 1242	ND		ug/kg	41.5	--	1	A
Aroclor 1248	ND		ug/kg	41.5	--	1	A
Aroclor 1254	ND		ug/kg	41.5	--	1	A
Aroclor 1260	ND		ug/kg	41.5	--	1	A
Aroclor 1262	ND		ug/kg	41.5	--	1	A
Aroclor 1268	ND		ug/kg	41.5	--	1	A
PCBs, Total	ND		ug/kg	41.5	--	1	A

Surrogate	% Recovery	Qualifier	Acceptance Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	54		30-150	A
Decachlorobiphenyl	49		30-150	A
2,4,5,6-Tetrachloro-m-xylene	56		30-150	B
Decachlorobiphenyl	62		30-150	B

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-05
 Client ID: 1607530-B101(S1-S2)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8082A
 Analytical Date: 09/02/16 23:14
 Analyst: JA
 Percent Solids: 84%

Date Collected: 08/26/16 11:45
 Date Received: 08/29/16
 Field Prep: Not Specified
 Extraction Method: EPA 3546
 Extraction Date: 08/31/16 18:23
 Cleanup Method: EPA 3665A
 Cleanup Date: 09/01/16
 Cleanup Method: EPA 3660B
 Cleanup Date: 09/01/16

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Column
PCB by GC - Westborough Lab							
Aroclor 1016	ND		ug/kg	39.2	--	1	A
Aroclor 1221	ND		ug/kg	39.2	--	1	A
Aroclor 1232	ND		ug/kg	39.2	--	1	A
Aroclor 1242	ND		ug/kg	39.2	--	1	A
Aroclor 1248	ND		ug/kg	39.2	--	1	A
Aroclor 1254	ND		ug/kg	39.2	--	1	A
Aroclor 1260	ND		ug/kg	39.2	--	1	A
Aroclor 1262	ND		ug/kg	39.2	--	1	A
Aroclor 1268	ND		ug/kg	39.2	--	1	A
PCBs, Total	ND		ug/kg	39.2	--	1	A

Surrogate	% Recovery	Qualifier	Acceptance Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	89		30-150	A
Decachlorobiphenyl	92		30-150	A
2,4,5,6-Tetrachloro-m-xylene	96		30-150	B
Decachlorobiphenyl	113		30-150	B

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-06
 Client ID: 1607530-B101(S3-S4)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Analytical Method: 1,8082A
 Analytical Date: 09/04/16 17:04
 Analyst: KEG
 Percent Solids: 81%

Date Collected: 08/26/16 12:00
 Date Received: 08/29/16
 Field Prep: Not Specified
 Extraction Method: EPA 3546
 Extraction Date: 09/04/16 06:18
 Cleanup Method: EPA 3665A
 Cleanup Date: 09/04/16
 Cleanup Method: EPA 3660B
 Cleanup Date: 09/04/16

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Column
PCB by GC - Westborough Lab							
Aroclor 1016	ND		ug/kg	40.0	--	1	A
Aroclor 1221	ND		ug/kg	40.0	--	1	A
Aroclor 1232	ND		ug/kg	40.0	--	1	A
Aroclor 1242	ND		ug/kg	40.0	--	1	A
Aroclor 1248	ND		ug/kg	40.0	--	1	A
Aroclor 1254	ND		ug/kg	40.0	--	1	A
Aroclor 1260	ND		ug/kg	40.0	--	1	A
Aroclor 1262	ND		ug/kg	40.0	--	1	A
Aroclor 1268	ND		ug/kg	40.0	--	1	A
PCBs, Total	ND		ug/kg	40.0	--	1	A

Surrogate	% Recovery	Qualifier	Acceptance Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	39		30-150	A
Decachlorobiphenyl	32		30-150	A
2,4,5,6-Tetrachloro-m-xylene	38		30-150	B
Decachlorobiphenyl	43		30-150	B

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

**Method Blank Analysis
Batch Quality Control**

Analytical Method: 1,8082A
Analytical Date: 09/02/16 21:33
Analyst: JA

Extraction Method: EPA 3546
Extraction Date: 08/31/16 18:23
Cleanup Method: EPA 3665A
Cleanup Date: 09/01/16
Cleanup Method: EPA 3660B
Cleanup Date: 09/01/16

Parameter	Result	Qualifier	Units	RL	MDL	Column
PCB by GC - Westborough Lab for sample(s): 01-03,05 Batch: WG927841-1						
Aroclor 1016	ND		ug/kg	32.6	--	A
Aroclor 1221	ND		ug/kg	32.6	--	A
Aroclor 1232	ND		ug/kg	32.6	--	A
Aroclor 1242	ND		ug/kg	32.6	--	A
Aroclor 1248	ND		ug/kg	32.6	--	A
Aroclor 1254	ND		ug/kg	32.6	--	A
Aroclor 1260	ND		ug/kg	32.6	--	A
Aroclor 1262	ND		ug/kg	32.6	--	A
Aroclor 1268	ND		ug/kg	32.6	--	A
PCBs, Total	ND		ug/kg	32.6	--	A

Surrogate	%Recovery	Qualifier	Acceptance	
			Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	82		30-150	A
Decachlorobiphenyl	85		30-150	A
2,4,5,6-Tetrachloro-m-xylene	89		30-150	B
Decachlorobiphenyl	93		30-150	B

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Method Blank Analysis
Batch Quality Control

Analytical Method: 1,8082A
 Analytical Date: 09/04/16 19:10
 Analyst: JA

Extraction Method: EPA 3546
 Extraction Date: 09/04/16 02:28
 Cleanup Method: EPA 3665A
 Cleanup Date: 09/04/16
 Cleanup Method: EPA 3660B
 Cleanup Date: 09/04/16

Parameter	Result	Qualifier	Units	RL	MDL	Column
PCB by GC - Westborough Lab for sample(s): 04,06 Batch: WG928866-1						
Aroclor 1016	ND		ug/kg	31.9	--	A
Aroclor 1221	ND		ug/kg	31.9	--	A
Aroclor 1232	ND		ug/kg	31.9	--	A
Aroclor 1242	ND		ug/kg	31.9	--	A
Aroclor 1248	ND		ug/kg	31.9	--	A
Aroclor 1254	ND		ug/kg	31.9	--	A
Aroclor 1260	ND		ug/kg	31.9	--	A
Aroclor 1262	ND		ug/kg	31.9	--	A
Aroclor 1268	ND		ug/kg	31.9	--	A
PCBs, Total	ND		ug/kg	31.9	--	A

Surrogate	%Recovery	Qualifier	Acceptance	
			Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	78		30-150	A
Decachlorobiphenyl	74		30-150	A
2,4,5,6-Tetrachloro-m-xylene	74		30-150	B
Decachlorobiphenyl	71		30-150	B

Lab Control Sample Analysis Batch Quality Control

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits	Column
PCB by GC - Westborough Lab Associated sample(s): 01-03,05 Batch: WG927841-2 WG927841-3									
Aroclor 1016	102		98		40-140	4		50	A
Aroclor 1260	88		87		40-140	1		50	A

Surrogate	LCS %Recovery	Qual	LCSD %Recovery	Qual	Acceptance Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	94		89		30-150	A
Decachlorobiphenyl	86		88		30-150	A
2,4,5,6-Tetrachloro-m-xylene	94		95		30-150	B
Decachlorobiphenyl	93		99		30-150	B

Lab Control Sample Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits	Column
PCB by GC - Westborough Lab Associated sample(s): 04,06 Batch: WG928866-2 WG928866-3									
Aroclor 1016	72		75		40-140	4		50	A
Aroclor 1260	70		62		40-140	12		50	A

Surrogate	LCS %Recovery	Qual	LCSD %Recovery	Qual	Acceptance Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	72		76		30-150	A
Decachlorobiphenyl	71		73		30-150	A
2,4,5,6-Tetrachloro-m-xylene	71		71		30-150	B
Decachlorobiphenyl	69		69		30-150	B

METALS

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-01
 Client ID: 1607530-B103(S1-S2)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Percent Solids: 93%

Date Collected: 08/26/16 09:25
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
Total Metals - Mansfield Lab											
Arsenic, Total	9.0		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 13:28	EPA 3050B	1,6010C	PS
Barium, Total	30		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 13:28	EPA 3050B	1,6010C	PS
Cadmium, Total	ND		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 13:28	EPA 3050B	1,6010C	PS
Chromium, Total	30		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 13:28	EPA 3050B	1,6010C	PS
Lead, Total	7.2		mg/kg	2.1	--	1	08/31/16 06:40	08/31/16 13:28	EPA 3050B	1,6010C	PS
Mercury, Total	ND		mg/kg	0.07	--	1	08/30/16 09:00	08/30/16 15:06	EPA 7471B	1,7471B	BV
Selenium, Total	ND		mg/kg	0.85	--	1	08/31/16 06:40	08/31/16 13:28	EPA 3050B	1,6010C	PS
Silver, Total	ND		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 13:28	EPA 3050B	1,6010C	PS



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-02
 Client ID: 1607530-B103(S3-S4)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Percent Solids: 92%

Date Collected: 08/26/16 09:55
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
Total Metals - Mansfield Lab											
Arsenic, Total	7.1		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 14:39	EPA 3050B	1,6010C	PS
Barium, Total	18		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 14:39	EPA 3050B	1,6010C	PS
Cadmium, Total	ND		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 14:39	EPA 3050B	1,6010C	PS
Chromium, Total	26		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 14:39	EPA 3050B	1,6010C	PS
Lead, Total	8.6		mg/kg	2.1	--	1	08/31/16 06:40	08/31/16 14:39	EPA 3050B	1,6010C	PS
Mercury, Total	ND		mg/kg	0.07	--	1	08/30/16 09:00	08/30/16 15:08	EPA 7471B	1,7471B	BV
Selenium, Total	ND		mg/kg	0.84	--	1	08/31/16 06:40	08/31/16 14:39	EPA 3050B	1,6010C	PS
Silver, Total	ND		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 14:39	EPA 3050B	1,6010C	PS



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-03
 Client ID: 1607530-B102(S1-S2)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Percent Solids: 84%

Date Collected: 08/26/16 10:45
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
Total Metals - Mansfield Lab											
Arsenic, Total	12		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 14:43	EPA 3050B	1,6010C	PS
Barium, Total	44		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 14:43	EPA 3050B	1,6010C	PS
Cadmium, Total	ND		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 14:43	EPA 3050B	1,6010C	PS
Chromium, Total	19		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 14:43	EPA 3050B	1,6010C	PS
Lead, Total	6.8		mg/kg	2.3	--	1	08/31/16 06:40	08/31/16 14:43	EPA 3050B	1,6010C	PS
Mercury, Total	ND		mg/kg	0.08	--	1	08/30/16 09:00	08/30/16 15:10	EPA 7471B	1,7471B	BV
Selenium, Total	ND		mg/kg	0.94	--	1	08/31/16 06:40	08/31/16 14:43	EPA 3050B	1,6010C	PS
Silver, Total	ND		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 14:43	EPA 3050B	1,6010C	PS



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-04
 Client ID: 1607530-B102(S3-S4)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Percent Solids: 79%

Date Collected: 08/26/16 11:00
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
Total Metals - Mansfield Lab											
Arsenic, Total	12		mg/kg	0.49	--	1	08/31/16 06:40	08/31/16 14:47	EPA 3050B	1,6010C	PS
Barium, Total	31		mg/kg	0.49	--	1	08/31/16 06:40	08/31/16 14:47	EPA 3050B	1,6010C	PS
Cadmium, Total	ND		mg/kg	0.49	--	1	08/31/16 06:40	08/31/16 14:47	EPA 3050B	1,6010C	PS
Chromium, Total	18		mg/kg	0.49	--	1	08/31/16 06:40	08/31/16 14:47	EPA 3050B	1,6010C	PS
Lead, Total	8.9		mg/kg	2.4	--	1	08/31/16 06:40	08/31/16 14:47	EPA 3050B	1,6010C	PS
Mercury, Total	ND		mg/kg	0.08	--	1	08/30/16 09:00	08/30/16 15:12	EPA 7471B	1,7471B	BV
Selenium, Total	ND		mg/kg	0.98	--	1	08/31/16 06:40	08/31/16 14:47	EPA 3050B	1,6010C	PS
Silver, Total	ND		mg/kg	0.49	--	1	08/31/16 06:40	08/31/16 14:47	EPA 3050B	1,6010C	PS



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-05
 Client ID: 1607530-B101(S1-S2)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Percent Solids: 84%

Date Collected: 08/26/16 11:45
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
Total Metals - Mansfield Lab											
Arsenic, Total	7.4		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 15:48	EPA 3050B	1,6010C	PS
Barium, Total	28		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 15:48	EPA 3050B	1,6010C	PS
Cadmium, Total	ND		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 15:48	EPA 3050B	1,6010C	PS
Chromium, Total	14		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 15:48	EPA 3050B	1,6010C	PS
Lead, Total	5.7		mg/kg	2.4	--	1	08/31/16 06:40	08/31/16 15:48	EPA 3050B	1,6010C	PS
Mercury, Total	ND		mg/kg	0.08	--	1	08/30/16 09:00	08/30/16 15:19	EPA 7471B	1,7471B	BV
Selenium, Total	ND		mg/kg	0.94	--	1	08/31/16 06:40	08/31/16 15:48	EPA 3050B	1,6010C	PS
Silver, Total	ND		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 15:48	EPA 3050B	1,6010C	PS



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-06
 Client ID: 1607530-B101(S3-S4)
 Sample Location: NEWINGTON, NH
 Matrix: Soil
 Percent Solids: 81%

Date Collected: 08/26/16 12:00
 Date Received: 08/29/16
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
Total Metals - Mansfield Lab											
Arsenic, Total	5.6		mg/kg	0.48	--	1	08/31/16 06:40	08/31/16 15:51	EPA 3050B	1,6010C	PS
Barium, Total	33		mg/kg	0.48	--	1	08/31/16 06:40	08/31/16 15:51	EPA 3050B	1,6010C	PS
Cadmium, Total	ND		mg/kg	0.48	--	1	08/31/16 06:40	08/31/16 15:51	EPA 3050B	1,6010C	PS
Chromium, Total	16		mg/kg	0.48	--	1	08/31/16 06:40	08/31/16 15:51	EPA 3050B	1,6010C	PS
Lead, Total	4.6		mg/kg	2.4	--	1	08/31/16 06:40	08/31/16 15:51	EPA 3050B	1,6010C	PS
Mercury, Total	ND		mg/kg	0.08	--	1	08/30/16 09:00	08/30/16 15:21	EPA 7471B	1,7471B	BV
Selenium, Total	ND		mg/kg	0.96	--	1	08/31/16 06:40	08/31/16 15:51	EPA 3050B	1,6010C	PS
Silver, Total	ND		mg/kg	0.48	--	1	08/31/16 06:40	08/31/16 15:51	EPA 3050B	1,6010C	PS



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Method Blank Analysis Batch Quality Control

Parameter	Result Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
Total Metals - Mansfield Lab for sample(s): 01-06 Batch: WG927131-1									
Mercury, Total	ND	mg/kg	0.08	--	1	08/30/16 09:00	08/30/16 14:37	1,7471B	BV

Prep Information

Digestion Method: EPA 7471B

Parameter	Result Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
Total Metals - Mansfield Lab for sample(s): 01-06 Batch: WG927532-1									
Arsenic, Total	ND	mg/kg	0.40	--	1	08/31/16 06:40	08/31/16 14:15	1,6010C	PS
Barium, Total	ND	mg/kg	0.40	--	1	08/31/16 06:40	08/31/16 14:15	1,6010C	PS
Cadmium, Total	ND	mg/kg	0.40	--	1	08/31/16 06:40	08/31/16 14:15	1,6010C	PS
Chromium, Total	ND	mg/kg	0.40	--	1	08/31/16 06:40	08/31/16 14:15	1,6010C	PS
Lead, Total	ND	mg/kg	2.0	--	1	08/31/16 06:40	08/31/16 14:15	1,6010C	PS
Selenium, Total	ND	mg/kg	0.80	--	1	08/31/16 06:40	08/31/16 14:15	1,6010C	PS
Silver, Total	ND	mg/kg	0.40	--	1	08/31/16 06:40	08/31/16 14:15	1,6010C	PS

Prep Information

Digestion Method: EPA 3050B



Lab Control Sample Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Project Number: 1607530

Lab Number: L1627010

Report Date: 09/15/16

Parameter	LCS		LCSD		%Recovery Limits	RPD	Qual	RPD Limits
	%Recovery	Qual	%Recovery	Qual				
Total Metals - Mansfield Lab Associated sample(s): 01-06 Batch: WG927131-2 SRM Lot Number: D089-540								
Mercury, Total	101		-		57-143	-		
Total Metals - Mansfield Lab Associated sample(s): 01-06 Batch: WG927532-2 SRM Lot Number: D089-540								
Arsenic, Total	100		-		80-120	-		
Barium, Total	93		-		83-117	-		
Cadmium, Total	95		-		82-117	-		
Chromium, Total	96		-		79-121	-		
Lead, Total	95		-		81-119	-		
Selenium, Total	90		-		78-121	-		
Silver, Total	97		-		75-125	-		

Matrix Spike Analysis Batch Quality Control

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Parameter	Native Sample	MS Added	MS Found	MS %Recovery	Qual	MSD Found	MSD %Recovery	Qual	Recovery Limits	RPD	Qual	RPD Limits
Total Metals - Mansfield Lab Associated sample(s): 01-06			QC Batch ID: WG927131-4			QC Sample: L1626498-01			Client ID: MS Sample			
Mercury, Total	ND	0.144	0.18	125	Q	-	-		80-120	-		20
Total Metals - Mansfield Lab Associated sample(s): 01-06			QC Batch ID: WG927532-4			QC Sample: L1627089-01			Client ID: MS Sample			
Arsenic, Total	1.7	9.93	10	84		-	-		75-125	-		20
Barium, Total	25	165	150	76		-	-		75-125	-		20
Cadmium, Total	ND	4.22	2.8	66	Q	-	-		75-125	-		20
Chromium, Total	3.5	16.5	14	63	Q	-	-		75-125	-		20
Lead, Total	3.3	42.2	30	63	Q	-	-		75-125	-		20
Selenium, Total	ND	9.93	7.8	78		-	-		75-125	-		20
Silver, Total	ND	24.8	21	85		-	-		75-125	-		20

Lab Duplicate Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Project Number: 1607530

Lab Number: L1627010

Report Date: 09/15/16

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
Total Metals - Mansfield Lab Associated sample(s): 01-06 QC Batch ID: WG927131-3 QC Sample: L1626498-01 Client ID: DUP Sample						
Mercury, Total	ND	ND	mg/kg	NC		20
Total Metals - Mansfield Lab Associated sample(s): 01-06 QC Batch ID: WG927532-3 QC Sample: L1627089-01 Client ID: DUP Sample						
Arsenic, Total	1.7	2.0	mg/kg	16		20
Barium, Total	25	29	mg/kg	15		20
Cadmium, Total	ND	ND	mg/kg	NC		20
Chromium, Total	3.5	4.4	mg/kg	23	Q	20
Lead, Total	3.3	3.6	mg/kg	9		20
Selenium, Total	ND	ND	mg/kg	NC		20
Silver, Total	ND	ND	mg/kg	NC		20

INORGANICS & MISCELLANEOUS

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-01
Client ID: 1607530-B103(S1-S2)
Sample Location: NEWINGTON, NH
Matrix: Soil

Date Collected: 08/26/16 09:25
Date Received: 08/29/16
Field Prep: Not Specified

Test Material Information

Source of Material: Unknown
Description of Material: Non-Metallic - Dry Soil
Particle Size: Fine
Preliminary Burning Time (sec): 120

Parameter	Result	Date Analyzed	Analytical Method	Analyst
Ignitability of Solids - Westborough Lab				
Ignitability	NI	08/30/16 15:55	1,1030	AB



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-02
Client ID: 1607530-B103(S3-S4)
Sample Location: NEWINGTON, NH
Matrix: Soil

Date Collected: 08/26/16 09:55
Date Received: 08/29/16
Field Prep: Not Specified

Test Material Information

Source of Material: Unknown
Description of Material: Non-Metallic - Damp Soil
Particle Size: Medium
Preliminary Burning Time (sec): 120

Parameter	Result	Date Analyzed	Analytical Method	Analyst
Ignitability of Solids - Westborough Lab				
Ignitability	NI	08/30/16 15:55	1,1030	AB



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-03
Client ID: 1607530-B102(S1-S2)
Sample Location: NEWINGTON, NH
Matrix: Soil

Date Collected: 08/26/16 10:45
Date Received: 08/29/16
Field Prep: Not Specified

Test Material Information

Source of Material: Unknown
Description of Material: Non-Metallic - Dry Clay
Particle Size: Medium
Preliminary Burning Time (sec): 120

Parameter	Result	Date Analyzed	Analytical Method	Analyst
Ignitability of Solids - Westborough Lab				
Ignitability	NI	08/30/16 15:55	1,1030	AB



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-04
Client ID: 1607530-B102(S3-S4)
Sample Location: NEWINGTON, NH
Matrix: Soil

Date Collected: 08/26/16 11:00
Date Received: 08/29/16
Field Prep: Not Specified

Test Material Information

Source of Material: Unknown
Description of Material: Non-Metallic - Wet Clay
Particle Size: Medium
Preliminary Burning Time (sec): 120

Parameter	Result	Date Analyzed	Analytical Method	Analyst
Ignitability of Solids - Westborough Lab				
Ignitability	NI	08/30/16 15:55	1,1030	AB



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-05
Client ID: 1607530-B101(S1-S2)
Sample Location: NEWINGTON, NH
Matrix: Soil

Date Collected: 08/26/16 11:45
Date Received: 08/29/16
Field Prep: Not Specified

Test Material Information

Source of Material: Unknown
Description of Material: Non-Metallic - Damp Soil
Particle Size: Medium
Preliminary Burning Time (sec): 120

Parameter	Result	Date Analyzed	Analytical Method	Analyst
Ignitability of Solids - Westborough Lab				
Ignitability	NI	08/30/16 23:45	1,1030	SB



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-06
Client ID: 1607530-B101(S3-S4)
Sample Location: NEWINGTON, NH
Matrix: Soil

Date Collected: 08/26/16 12:00
Date Received: 08/29/16
Field Prep: Not Specified

Test Material Information

Source of Material: Unknown
Description of Material: Non-Metallic - Damp Soil
Particle Size: Medium
Preliminary Burning Time (sec): 120

Parameter	Result	Date Analyzed	Analytical Method	Analyst
Ignitability of Solids - Westborough Lab				
Ignitability	NI	08/30/16 23:45	1,1030	SB



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-01
Client ID: 1607530-B103(S1-S2)
Sample Location: NEWINGTON, NH
Matrix: Soil

Date Collected: 08/26/16 09:25
Date Received: 08/29/16
Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
General Chemistry - Westborough Lab										
Specific Conductance @ 25 C	ND		umhos/cm	10	--	1	-	08/30/16 19:35	1,9050A	AS
Solids, Total	93.3		%	0.100	NA	1	-	08/30/16 16:09	121,2540G	RI
pH (H)	5.7		SU	-	NA	1	-	08/30/16 01:30	1,9045D	MC
Cyanide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 23:01	1,7.3	TL
Sulfide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 22:53	1,7.3	TL
Oxidation/Reduction Potential	170		mv	-	NA	1	-	08/30/16 02:19	68,1498	MC



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-02
Client ID: 1607530-B103(S3-S4)
Sample Location: NEWINGTON, NH
Matrix: Soil

Date Collected: 08/26/16 09:55
Date Received: 08/29/16
Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
General Chemistry - Westborough Lab										
Specific Conductance @ 25 C	44		umhos/cm	10	--	1	-	08/30/16 19:35	1,9050A	AS
Solids, Total	92.4		%	0.100	NA	1	-	08/30/16 16:09	121,2540G	RI
pH (H)	7.0		SU	-	NA	1	-	08/30/16 01:30	1,9045D	MC
Cyanide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 23:01	1,7.3	TL
Sulfide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 22:53	1,7.3	TL
Oxidation/Reduction Potential	150		mv	-	NA	1	-	08/30/16 02:19	68,1498	MC



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-03
Client ID: 1607530-B102(S1-S2)
Sample Location: NEWINGTON, NH
Matrix: Soil

Date Collected: 08/26/16 10:45
Date Received: 08/29/16
Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
General Chemistry - Westborough Lab										
Specific Conductance @ 25 C	ND		umhos/cm	10	--	1	-	08/30/16 19:35	1,9050A	AS
Solids, Total	83.6		%	0.100	NA	1	-	08/30/16 16:09	121,2540G	RI
pH (H)	6.3		SU	-	NA	1	-	08/30/16 01:30	1,9045D	MC
Cyanide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 23:01	1,7.3	TL
Sulfide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 22:53	1,7.3	TL
Oxidation/Reduction Potential	170		mv	-	NA	1	-	08/30/16 02:19	68,1498	MC



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-04
Client ID: 1607530-B102(S3-S4)
Sample Location: NEWINGTON, NH
Matrix: Soil

Date Collected: 08/26/16 11:00
Date Received: 08/29/16
Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
General Chemistry - Westborough Lab										
Specific Conductance @ 25 C	28		umhos/cm	10	--	1	-	08/30/16 19:35	1,9050A	AS
Solids, Total	79.2		%	0.100	NA	1	-	08/30/16 16:09	121,2540G	RI
pH (H)	7.4		SU	-	NA	1	-	08/30/16 01:30	1,9045D	MC
Cyanide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 23:01	1,7.3	TL
Sulfide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 22:53	1,7.3	TL
Oxidation/Reduction Potential	190		mv	-	NA	1	-	08/30/16 02:19	68,1498	MC



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-05
Client ID: 1607530-B101(S1-S2)
Sample Location: NEWINGTON, NH
Matrix: Soil

Date Collected: 08/26/16 11:45
Date Received: 08/29/16
Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
General Chemistry - Westborough Lab										
Specific Conductance @ 25 C	ND		umhos/cm	10	--	1	-	08/30/16 19:35	1,9050A	AS
Solids, Total	84.2		%	0.100	NA	1	-	08/30/16 16:09	121,2540G	RI
pH (H)	6.2		SU	-	NA	1	-	08/30/16 01:30	1,9045D	MC
Cyanide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 23:02	1,7.3	TL
Sulfide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 22:54	1,7.3	TL
Oxidation/Reduction Potential	180		mv	-	NA	1	-	08/30/16 02:19	68,1498	MC



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

SAMPLE RESULTS

Lab ID: L1627010-06
Client ID: 1607530-B101(S3-S4)
Sample Location: NEWINGTON, NH
Matrix: Soil

Date Collected: 08/26/16 12:00
Date Received: 08/29/16
Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
General Chemistry - Westborough Lab										
Specific Conductance @ 25 C	ND		umhos/cm	10	--	1	-	08/30/16 19:35	1,9050A	AS
Solids, Total	80.9		%	0.100	NA	1	-	08/30/16 16:09	121,2540G	RI
pH (H)	6.4		SU	-	NA	1	-	08/30/16 01:30	1,9045D	MC
Cyanide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 23:02	1,7.3	TL
Sulfide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 22:54	1,7.3	TL
Oxidation/Reduction Potential	170		mv	-	NA	1	-	08/30/16 02:19	68,1498	MC



Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Method Blank Analysis
Batch Quality Control

Parameter	Result Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
General Chemistry - Westborough Lab for sample(s): 01-06 Batch: WG927398-1									
Cyanide, Reactive	ND	mg/kg	10	--	1	08/30/16 22:05	08/30/16 23:00	1,7.3	TL
General Chemistry - Westborough Lab for sample(s): 01-06 Batch: WG927400-1									
Sulfide, Reactive	ND	mg/kg	10	--	1	08/30/16 22:05	08/30/16 22:52	1,7.3	TL

Lab Control Sample Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS		LCSD		%Recovery Limits	RPD	Qual	RPD Limits
	%Recovery	Qual	%Recovery	Qual				
General Chemistry - Westborough Lab Associated sample(s): 01-06 Batch: WG927110-1								
pH	100		-		99-101	-		
General Chemistry - Westborough Lab Associated sample(s): 01-06 Batch: WG927111-1								
Oxidation/Reduction Potential	98		-		90-110	-		20
General Chemistry - Westborough Lab Associated sample(s): 01-06 Batch: WG927398-2								
Cyanide, Reactive	48		-		30-125	-		40
General Chemistry - Westborough Lab Associated sample(s): 01-06 Batch: WG927400-2								
Sulfide, Reactive	98		-		60-125	-		40
General Chemistry - Westborough Lab Associated sample(s): 01-06 Batch: WG927422-1								
Specific Conductance	100		-		99-101	-		

Lab Duplicate Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Project Number: 1607530

Lab Number: L1627010

Report Date: 09/15/16

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
General Chemistry - Westborough Lab Associated sample(s): 01-06 QC Batch ID: WG927110-2 QC Sample: L1627010-01 Client ID: 1607530-B103(S1-S2)						
pH (H)	5.7	5.7	SU	0		5
General Chemistry - Westborough Lab Associated sample(s): 01-06 QC Batch ID: WG927111-2 QC Sample: L1627010-01 Client ID: 1607530-B103(S1-S2)						
Oxidation/Reduction Potential	170	170	mv	0		20
General Chemistry - Westborough Lab Associated sample(s): 01-06 QC Batch ID: WG927364-1 QC Sample: L1627010-01 Client ID: 1607530-B103(S1-S2)						
Solids, Total	93.3	92.4	%	1		20
General Chemistry - Westborough Lab Associated sample(s): 01-06 QC Batch ID: WG927398-3 QC Sample: L1627028-01 Client ID: DUP Sample						
Cyanide, Reactive	ND	ND	mg/kg	NC		40
General Chemistry - Westborough Lab Associated sample(s): 01-06 QC Batch ID: WG927400-3 QC Sample: L1627028-01 Client ID: DUP Sample						
Sulfide, Reactive	ND	ND	mg/kg	NC		40
General Chemistry - Westborough Lab Associated sample(s): 01-06 QC Batch ID: WG927422-2 QC Sample: L1627026-01 Client ID: DUP Sample						
Specific Conductance	74	97	umhos/cm	27	Q	20

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Sample Receipt and Container Information

Were project specific reporting limits specified? YES

Reagent H2O Preserved Vials Frozen on: 08/29/2016 22:27

Cooler Information Custody Seal

Cooler

A Absent
 B Absent

Container Information

Container ID	Container Type	Cooler	pH	Temp deg C	Pres	Seal	Analysis(*)
L1627010-01A	Vial MeOH preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-01B	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-01C	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-01D	Metals Only - Glass 60mL/2oz unp	A	N/A	2.4	Y	Absent	AS-TI(180),BA-TI(180),AG-TI(180),CR-TI(180),PB-TI(180),SE-TI(180),HG-T(28),CD-TI(180)
L1627010-01E	Glass 60mL/2oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-01F	Glass 120ml/4oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-01G	Glass 500ml/16oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-01H	Plastic 250ml unpreserved	B	N/A	3.1	Y	Absent	SUB-537()
L1627010-01X	Glass 120ml/4oz unpreserved/No H	A	N/A	2.4	Y	Absent	HEXCR-RELOG()
L1627010-02A	Vial MeOH preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-02B	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-02C	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-02D	Metals Only - Glass 60mL/2oz unp	A	N/A	2.4	Y	Absent	AS-TI(180),BA-TI(180),AG-TI(180),CR-TI(180),PB-TI(180),SE-TI(180),HG-T(28),CD-TI(180)

*Values in parentheses indicate holding time in days



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Container Information

Container ID	Container Type	Cooler	pH	Temp deg C	Pres	Seal	Analysis(*)
L1627010-02E	Glass 60mL/2oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-02F	Glass 120ml/4oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-02G	Glass 500ml/16oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-02H	Plastic 250ml unpreserved	B	N/A	3.1	Y	Absent	SUB-537()
L1627010-02X	Glass 120ml/4oz unpreserved/No H	A	N/A	2.4	Y	Absent	HEXCR-RELOG()
L1627010-03A	Vial MeOH preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-03B	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-03C	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-03D	Metals Only - Glass 60mL/2oz unp	A	N/A	2.4	Y	Absent	AS-TI(180),BA-TI(180),AG-TI(180),CR-TI(180),PB-TI(180),SE-TI(180),HG-T(28),CD-TI(180)
L1627010-03E	Glass 60mL/2oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-03F	Glass 120ml/4oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-03G	Glass 500ml/16oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-03H	Plastic 250ml unpreserved	B	N/A	3.1	Y	Absent	SUB-537()
L1627010-03X	Glass 120ml/4oz unpreserved/No H	A	N/A	2.4	Y	Absent	HEXCR-RELOG()
L1627010-04A	Vial MeOH preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-04B	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-04C	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)

*Values in parentheses indicate holding time in days



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Container Information

Container ID	Container Type	Cooler	pH	Temp deg C	Pres	Seal	Analysis(*)
L1627010-04D	Metals Only - Glass 60mL/2oz unp	A	N/A	2.4	Y	Absent	AS-TI(180),BA-TI(180),AG-TI(180),CR-TI(180),PB-TI(180),SE-TI(180),HG-T(28),CD-TI(180)
L1627010-04E	Glass 60mL/2oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-04F	Glass 120ml/4oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-04G	Glass 500ml/16oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-04H	Plastic 250ml unpreserved	B	N/A	3.1	Y	Absent	SUB-537()
L1627010-04X	Glass 120ml/4oz unpreserved/No H	A	N/A	2.4	Y	Absent	HEXCR-RELOG()
L1627010-05A	Vial MeOH preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-05B	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-05C	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-05D	Metals Only - Glass 60mL/2oz unp	A	N/A	2.4	Y	Absent	AS-TI(180),BA-TI(180),AG-TI(180),CR-TI(180),PB-TI(180),SE-TI(180),HG-T(28),CD-TI(180)
L1627010-05E	Glass 60mL/2oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-05F	Glass 120ml/4oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-05G	Glass 500ml/16oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-05H	Plastic 250ml unpreserved	B	N/A	3.1	Y	Absent	SUB-537()
L1627010-05X	Glass 120ml/4oz unpreserved/No H	A	N/A	2.4	Y	Absent	HEXCR-RELOG()
L1627010-06A	Vial MeOH preserved	A	N/A	2.4	Y	Absent	8260H(14)

*Values in parentheses indicate holding time in days



Project Name: EVERSOURCE NH SRP

Project Number: 1607530

Lab Number: L1627010

Report Date: 09/15/16

Container Information

Container ID	Container Type	Cooler	pH	Temp deg C	Pres	Seal	Analysis(*)
L1627010-06B	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-06C	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-06D	Metals Only - Glass 60mL/2oz unp	A	N/A	2.4	Y	Absent	AS-TI(180),BA-TI(180),AG-TI(180),CR-TI(180),PB-TI(180),SE-TI(180),HG-T(28),CD-TI(180)
L1627010-06E	Glass 60mL/2oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-06F	Glass 120ml/4oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-06G	Glass 500ml/16oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-06H	Plastic 250ml unpreserved	B	N/A	3.1	Y	Absent	SUB-537()
L1627010-06X	Glass 120ml/4oz unpreserved/No H	A	N/A	2.4	Y	Absent	HEXCR-RELOG()

*Values in parentheses indicate holding time in days



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

GLOSSARY

Acronyms

EDL	- Estimated Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The EDL includes any adjustments from dilutions, concentrations or moisture content, where applicable. The use of EDLs is specific to the analysis of PAHs using Solid-Phase Microextraction (SPME).
EPA	- Environmental Protection Agency.
LCS	- Laboratory Control Sample: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
LCSD	- Laboratory Control Sample Duplicate: Refer to LCS.
LFB	- Laboratory Fortified Blank: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
MDL	- Method Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The MDL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
MS	- Matrix Spike Sample: A sample prepared by adding a known mass of target analyte to a specified amount of matrix sample for which an independent estimate of target analyte concentration is available.
MSD	- Matrix Spike Sample Duplicate: Refer to MS.
NA	- Not Applicable.
NC	- Not Calculated: Term is utilized when one or more of the results utilized in the calculation are non-detect at the parameter's reporting unit.
NDPA/DPA	- N-Nitrosodiphenylamine/Diphenylamine.
NI	- Not Ignitable.
NP	- Non-Plastic: Term is utilized for the analysis of Atterberg Limits in soil.
RL	- Reporting Limit: The value at which an instrument can accurately measure an analyte at a specific concentration. The RL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
RPD	- Relative Percent Difference: The results from matrix and/or matrix spike duplicates are primarily designed to assess the precision of analytical results in a given matrix and are expressed as relative percent difference (RPD). Values which are less than five times the reporting limit for any individual parameter are evaluated by utilizing the absolute difference between the values; although the RPD value will be provided in the report.
SRM	- Standard Reference Material: A reference sample of a known or certified value that is of the same or similar matrix as the associated field samples.
STLP	- Semi-dynamic Tank Leaching Procedure per EPA Method 1315.
TIC	- Tentatively Identified Compound: A compound that has been identified to be present and is not part of the target compound list (TCL) for the method and/or program. All TICs are qualitatively identified and reported as estimated concentrations.

Footnotes

- 1 - The reference for this analyte should be considered modified since this analyte is absent from the target analyte list of the original method.

Terms

Total: With respect to Organic analyses, a 'Total' result is defined as the summation of results for individual isomers or Aroclors. If a 'Total' result is requested, the results of its individual components will also be reported. This is applicable to 'Total' results for methods 8260, 8081 and 8082.

Analytical Method: Both the document from which the method originates and the analytical reference method. (Example: EPA 8260B is shown as 1,8260B.) The codes for the reference method documents are provided in the References section of the Addendum.

Data Qualifiers

- A** - Spectra identified as "Aldol Condensation Product".
- B** - The analyte was detected above the reporting limit in the associated method blank. Flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For MCP-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For DOD-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank AND the analyte was detected above one-half the reporting limit (or above the reporting limit for common lab contaminants) in the associated method blank. For NJ-Air-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte above the reporting limit. For NJ-related projects (excluding Air), flag only applies to associated field samples that have detectable concentrations of the analyte, which was detected above the reporting limit in the associated method blank or above five times the

Report Format: Data Usability Report



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

Data Qualifiers

- reporting limit for common lab contaminants (Phthalates, Acetone, Methylene Chloride, 2-Butanone).
- C** - Co-elution: The target analyte co-elutes with a known lab standard (i.e. surrogate, internal standards, etc.) for co-extracted analyses.
 - D** - Concentration of analyte was quantified from diluted analysis. Flag only applies to field samples that have detectable concentrations of the analyte.
 - E** - Concentration of analyte exceeds the range of the calibration curve and/or linear range of the instrument.
 - G** - The concentration may be biased high due to matrix interferences (i.e. co-elution) with non-target compound(s). The result should be considered estimated.
 - H** - The analysis of pH was performed beyond the regulatory-required holding time of 15 minutes from the time of sample collection.
 - I** - The lower value for the two columns has been reported due to obvious interference.
 - M** - Reporting Limit (RL) exceeds the MCP CAM Reporting Limit for this analyte.
 - NJ** - Presumptive evidence of compound. This represents an estimated concentration for Tentatively Identified Compounds (TICs), where the identification is based on a mass spectral library search.
 - P** - The RPD between the results for the two columns exceeds the method-specified criteria.
 - Q** - The quality control sample exceeds the associated acceptance criteria. For DOD-related projects, LCS and/or Continuing Calibration Standard exceedences are also qualified on all associated sample results. Note: This flag is not applicable for matrix spike recoveries when the sample concentration is greater than 4x the spike added or for batch duplicate RPD when the sample concentrations are less than 5x the RL. (Metals only.)
 - R** - Analytical results are from sample re-analysis.
 - RE** - Analytical results are from sample re-extraction.
 - S** - Analytical results are from modified screening analysis.
 - J** - Estimated value. This represents an estimated concentration for Tentatively Identified Compounds (TICs).
 - ND** - Not detected at the reporting limit (RL) for the sample.

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1627010
Report Date: 09/15/16

REFERENCES

- 1 Test Methods for Evaluating Solid Waste: Physical/Chemical Methods. EPA SW-846. Third Edition. Updates I - IV, 2007.
- 68 Annual Book of ASTM (American Society for Testing and Materials) Standards following extraction by SW-846 EPA Method 9045C under the requirements of MADEP BWSC, WSC-CAM-VIB. August 2004.
- 121 Standard Methods for the Examination of Water and Wastewater. APHA-AWWA-WEF. Standard Methods Online.

LIMITATION OF LIABILITIES

Alpha Analytical performs services with reasonable care and diligence normal to the analytical testing laboratory industry. In the event of an error, the sole and exclusive responsibility of Alpha Analytical shall be to re-perform the work at it's own expense. In no event shall Alpha Analytical be held liable for any incidental, consequential or special damages, including but not limited to, damages in any way connected with the use of, interpretation of, information or analysis provided by Alpha Analytical.

We strongly urge our clients to comply with EPA protocol regarding sample volume, preservation, cooling, containers, sampling procedures, holding time and splitting of samples in the field.



Certification Information

The following analytes are not included in our Primary NELAP Scope of Accreditation:

Westborough Facility

EPA 624: m/p-xylene, o-xylene

EPA 8260C: NPW: 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene, Azobenzene; SCM: Iodomethane (methyl iodide), Methyl methacrylate, 1,2,4,5-Tetramethyl benzene; 4-Ethyltoluene.

EPA 8270D: NPW: Dimethylnaphthalene,1,4-Diphenylhydrazine; SCM: Dimethylnaphthalene,1,4-Diphenylhydrazine.

EPA 300: DW: Bromide

EPA 6860: NPW and SCM: Perchlorate

EPA 9010: NPW and SCM: Amenable Cyanide Distillation

EPA 9012B: NPW: Total Cyanide

EPA 9050A: NPW: Specific Conductance

SM3500: NPW: Ferrous Iron

SM4500: NPW: Amenable Cyanide, Dissolved Oxygen; SCM: Total Phosphorus, TKN, NO₂, NO₃.

SM5310C: DW: Dissolved Organic Carbon

Mansfield Facility

SM 2540D: TSS

EPA 3005A NPW

EPA 8082A: NPW: PCB: 1, 5, 31, 87,101, 110, 141, 151, 153, 180, 183, 187.

EPA TO-15: Halothane, 2,4,4-Trimethyl-2-pentene, 2,4,4-Trimethyl-1-pentene, Thiophene, 2-Methylthiophene,

3-Methylthiophene, 2-Ethylthiophene, 1,2,3-Trimethylbenzene, Indan, Indene, 1,2,4,5-Tetramethylbenzene, Benzothiophene, 1-Methylnaphthalene.

Biological Tissue Matrix: **EPA 3050B**

The following analytes are included in our Massachusetts DEP Scope of Accreditation

Westborough Facility:

Drinking Water

EPA 300.0: Nitrate-N, Fluoride, Sulfate; **EPA 353.2:** Nitrate-N, Nitrite-N; **SM4500NO3-F:** Nitrate-N, Nitrite-N; **SM4500F-C, SM4500CN-CE, EPA 180.1, SM2130B, SM4500CI-D, SM2320B, SM2540C, SM4500H-B**

EPA 332: Perchlorate; **EPA 524.2:** THMs and VOCs; **EPA 504.1:** EDB, DBCP.

Microbiology: **SM9215B; SM9223-P/A, SM9223B-Colilert-QT,SM9222D.**

Non-Potable Water

SM4500H,B, EPA 120.1, SM2510B, SM2540C, SM2320B, SM4500CL-E, SM4500F-BC, SM4500NH3-BH, EPA 350.1: Ammonia-N, **LACHAT 10-107-06-1-B:** Ammonia-N, **SM4500NO3-F, EPA 353.2:** Nitrate-N, **EPA 351.1, SM4500P-E, SM4500P-B, E, SM4500SO4-E, SM5220D, EPA 410.4, SM5210B, SM5310C, SM4500CL-D, EPA 1664, EPA 420.1, SM4500-CN-CE, SM2540D.**

EPA 624: Volatile Halocarbons & Aromatics,

EPA 608: Chlordane, Toxaphene, Aldrin, alpha-BHC, beta-BHC, gamma-BHC, delta-BHC, Dieldrin, DDD, DDE, DDT, Endosulfan I, Endosulfan II, Endosulfan sulfate, Endrin, Endrin Aldehyde, Heptachlor, Heptachlor Epoxide, PCBs

EPA 625: SVOC (Acid/Base/Neutral Extractables), **EPA 600/4-81-045:** PCB-Oil.

Microbiology: **SM9223B-Colilert-QT; Enterolert-QT, SM9222D-MF.**

Mansfield Facility:

Drinking Water

EPA 200.7: Ba, Be, Cd, Cr, Cu, Ni, Na, Ca. **EPA 200.8:** Sb, As, Ba, Be, Cd, Cr, Cu, Pb, Ni, Se, TL. **EPA 245.1** Hg.

Non-Potable Water

EPA 200.7: Al, Sb, As, Be, Cd, Ca, Cr, Co, Cu, Fe, Pb, Mg, Mn, Mo, Ni, K, Se, Ag, Na, Sr, TL, Ti, V, Zn.

EPA 200.8: Al, Sb, As, Be, Cd, Cr, Cu, Pb, Mn, Ni, Se, Ag, TL, Zn.

EPA 245.1 Hg.

SM2340B

For a complete listing of analytes and methods, please contact your Alpha Project Manager.

08/29/16

L1627010

Chain-of-Custody Record	Laboratory: Alpha	Laboratory Job # (Lab use only)
--------------------------------	--------------------------	---



Project Information	
Project Name: Eversource NH SRP	Project Location: Newington, NH
Project Number: 1607530	Project Manager: Mike Sabulis (office: 781-721-4114) (cell: 508-633-9544)
Send Report to: Jess Englehart	Preservative
Send EDD to: labdata@geiconsultants.com	Analysis

Page 1 of 1

Sample Handling

Samples Field Filtered
YES NO NA

Sampled Shipped
With Ice
YES NO

MCP PRESUMPTIVE CERTAINTY REQUIRED -- YES NO

If Yes, Are MCP Analytical Methods Required?	YES	NO	NA
If Yes, Are Drinking Water Samples Submitted?	YES	NO	NA
If Yes, Have You Met Minimum Field QC Requirements?	YES	NO	NA

Lab Sample Number	GEI Sample ID	Collection		Matrix	No. of Bottles	Sampler(s) Initials	PFOS	PFOA								Sample Specific Remarks
		Date	Time													
	1607530-B103(S1-S2)	8/26/16	09:25	SO	1	MEG	X	X								
	B103(S3-S4)	↓	09:55	↓	↓	↓	↓	↓								
	B102(S1-S2)	↓	10:45	↓	↓	↓	↓	↓								
	B102(S3-S4)	↓	11:00	↓	↓	↓	↓	↓								
	B101(S1-S2)	↓	11:45	↓	↓	↓	↓	↓								
	B101(S3-S4)	↓	12:00	↓	↓	↓	↓	↓								

MCP Level Needed: GEI requires the most stringent Method 1 MCP standard be met for all analytes whenever possible.

Relinquished by: (signature)	Date:	Time:	Received by: (signature)
1. Molly Owen	8/27/16	14:50	1. GEI Fridge
Relinquished by: (signature)	Date:	Time:	Received by: (signature)
2. GEI Fridge	8/29/16	11:20	2. J. Englehart
Relinquished by: (signature)	Date:	Time:	Received by: (signature)
3. J. Englehart	8/29/16	11:20	3. [Signature]
Relinquished by: (signature)	Date:	Time:	Received by: (signature)
4. [Signature]	8/29/16	17:20	4. [Signature]

Turnaround Time (Business days):	Before submitting rush turnaround samples, you must notify the laboratory to confirm that the TAT can be achieved.
Normal <input checked="" type="checkbox"/> Other <input type="checkbox"/>	
10-Day <input type="checkbox"/> 7-Day <input type="checkbox"/>	
5-Day <input type="checkbox"/> 3-Day <input type="checkbox"/>	
Additional Requirements/Comments/Remarks:	



September 15, 2016

Vista Work Order No. 1601099

Ms. Karyn Raymond
Alpha Analytical Laboratory
8 Walkup Drive
Westborough, MA 01581

Dear Ms. Raymond,

Enclosed are the amended results for the sample set received at Vista Analytical Laboratory on August 31, 2016. This sample set was analyzed on a rush turn-around time. The SDG Number is L1627010.

Vista Analytical Laboratory is committed to serving you effectively. If you require additional information, please contact me at 916-673-1520 or by email at mmaier@vista-analytical.com.

Thank you for choosing Vista as part of your analytical support team.

Sincerely,

A handwritten signature in black ink that reads "Karen Lopez" followed by the word "for" in a smaller, cursive font.

Martha Maier
Laboratory Director



Vista Analytical Laboratory certifies that the report herein meets all the requirements set forth by NELAP for those applicable test methods. Results relate only to the samples as received by the laboratory. This report should not be reproduced except in full without the written approval of Vista.

SDG Number L1627010

Vista Work Order No. 1601099

Case Narrative

Sample Condition on Receipt:

Six soil samples were received in good condition and within the method temperature requirements. The samples were received and stored securely in accordance with Vista standard operating procedures and EPA methodology. This report was amended to reflect Alpha job number L1627010 rather than L1626010.

Analytical Notes:

Modified EPA Method 537

The samples were extracted and analyzed for PFOA and PFOS using Modified EPA Method 537. The results include both linear and branched isomers.

Holding Times

The samples were extracted and analyzed within the method hold times.

Quality Control

The Initial Calibration and Continuing Calibration Verifications met the acceptance criteria.

A Method Blank and Ongoing Precision and Recovery (OPR) sample were extracted and analyzed with the preparation batch. No analytes were detected in the Method Blank above the Reporting Limit. The OPR recoveries were within the method acceptance criteria.

The recoveries of all internal standards in the QC and field samples were within the acceptance criteria.

TABLE OF CONTENTS

Case Narrative.....	1
Table of Contents.....	3
Sample Inventory.....	4
Analytical Results.....	5
Qualifiers.....	14
Certifications.....	15
Sample Receipt.....	18

Sample Inventory Report

Vista Sample ID	Client Sample ID	Sampled	Received	Components/Containers
1601099-01	1607530-B103(S1-S2)	26-Aug-16 09:25	31-Aug-16 09:33	HDPE Jar, 4 oz
1601099-02	1607530-B103(S3-S4)	26-Aug-16 09:55	31-Aug-16 09:33	HDPE Jar, 4 oz
1601099-03	1607530-B102(S1-S2)	26-Aug-16 10:45	31-Aug-16 09:33	HDPE Jar, 4 oz
1601099-04	1607530-B102(S3-S4)	26-Aug-16 11:00	31-Aug-16 09:33	HDPE Jar, 4 oz
1601099-05	1607530-B101(S1-S2)	26-Aug-16 11:45	31-Aug-16 09:33	HDPE Jar, 4 oz
1601099-06	1607530-B101(S3-S4)	26-Aug-16 12:00	31-Aug-16 09:33	HDPE Jar, 4 oz

Vista Project: 1601099

ANALYTICAL RESULTS

Sample ID: Method Blank				VAL - PFAS			
Matrix: Solid	QC Batch: B6I0041	Lab Sample: B6I0041-BLK1	Date Analyzed: 12-Sep-16 19:47	Column: BEH C18	Analyst: AC		
Sample Size: 1.00 g	Date Extracted: 08-Sep-2016 14:54						
Analyte	Conc. (ng/g)	RL	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	2.00		IS 13C2-PFOA	124	60 - 150	
PFOS	ND	2.00		IS 13C8-PFOS	109	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

The results are reported in dry weight

The sample size is reported in wet weight

Results reported to RL

When reported, PFBS, PFHxS and PFOS include both linear and branched isomers Only the linear isomer is reported for all other analytes

Sample ID: OPR					VAL - PFAS		
Matrix: Solid	QC Batch: B6I0041		Lab Sample: B6I0041-BS1				
Sample Size: 1.00 g	Date Extracted: 08-Sep-2016 14:54		Date Analyzed: 12-Sep-16 18:56 Column: BEH C18 Analyst: AC				
Analyte	Amt Found (ng/g)	Spike Amt	%R	Limits	Labeled Standard	%R	LCL-UCL
PFOA	9.89	10.0	98.9	70 - 130	IS 13C2-PFOA	123	60 - 150
PFOS	10.7	10.0	107	70 - 130	IS 13C8-PFOS	105	60 - 150

LCL-UCL - Lower control limit - upper control limit

Sample ID: 1607530-B103(S1-S2)**VAL - PFAS**

Client Data			Sample Data		Laboratory Data			
Name:	Alpha Analytical Laboratory		Matrix:	Soil	Lab Sample:	1601099-01	Date Received:	31-Aug-2016 9:33
Project:			Sample Size:	1.46 g	QC Batch:	B6I0041	Date Extracted:	08-Sep-2016 14:54
Date Collected:	26-Aug-2016 9:25		% Solids:	71.0	Date Analyzed:	13-Sep-16 02:56 Column: BEH C18 Analyst: AC		
Analyte	Conc. (ng/g)	RL	Qualifiers		Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	1.93			IS 13C2-PFOA	137	60 - 150	
PFOS	ND	1.93			IS 13C8-PFOS	76.3	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

The results are reported in dry weight

The sample size is reported in wet weight

Results reported to RL

When reported, PFBS, PFHxS and PFOS include both linear and branched isomers Only the linear isomer is reported for all other analytes

Sample ID: 1607530-B103(S3-S4)**VAL - PFAS**

Client Data			Sample Data		Laboratory Data			
Name:	Alpha Analytical Laboratory		Matrix:	Soil	Lab Sample:	1601099-02	Date Received:	31-Aug-2016 9:33
Project:			Sample Size:	1.23 g	QC Batch:	B6I0041	Date Extracted:	08-Sep-2016 14:54
Date Collected:	26-Aug-2016 9:55		% Solids:	80.4	Date Analyzed:	13-Sep-16 03:09 Column: BEH C18 Analyst: AC		
Analyte	Conc. (ng/g)	RL	Qualifiers		Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	2.02			IS 13C2-PFOA	130	60 - 150	
PFOS	ND	2.02			IS 13C8-PFOS	81.7	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

The results are reported in dry weight

The sample size is reported in wet weight

Results reported to RL

When reported, PFBS, PFHxS and PFOS include both linear and branched isomers Only the linear isomer is reported for all other analytes

Sample ID: 1607530-B102(S1-S2)**VAL - PFAS**

Client Data			Sample Data		Laboratory Data			
Name:	Alpha Analytical Laboratory		Matrix:	Soil	Lab Sample:	1601099-03	Date Received:	31-Aug-2016 9:33
Project:			Sample Size:	1.37 g	QC Batch:	B6I0041	Date Extracted:	08-Sep-2016 14:54
Date Collected:	26-Aug-2016 10:45		% Solids:	75.0	Date Analyzed:	13-Sep-16 03:21 Column: BEH C18 Analyst: AC		
Analyte	Conc. (ng/g)	RL	Qualifiers		Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	1.95			IS 13C2-PFOA	150	60 - 150	
PFOS	ND	1.95			IS 13C8-PFOS	99.6	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

The results are reported in dry weight

The sample size is reported in wet weight

Results reported to RL

When reported, PFBS, PFHxS and PFOS include both linear and branched isomers Only the linear isomer is reported for all other analytes

Sample ID: 1607530-B102(S3-S4)**VAL - PFAS**

Client Data			Sample Data		Laboratory Data			
Name:	Alpha Analytical Laboratory		Matrix:	Soil	Lab Sample:	1601099-04	Date Received:	31-Aug-2016 9:33
Project:			Sample Size:	1.36 g	QC Batch:	B6I0041	Date Extracted:	08-Sep-2016 14:54
Date Collected:	26-Aug-2016 11:00		% Solids:	75.3	Date Analyzed:	13-Sep-16 03:34 Column: BEH C18 Analyst: AC		
Analyte	Conc. (ng/g)	RL	Qualifiers		Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	1.95			IS 13C2-PFOA	141	60 - 150	
PFOS	ND	1.95			IS 13C8-PFOS	108	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

The results are reported in dry weight

The sample size is reported in wet weight

Results reported to RL

When reported, PFBS, PFHxS and PFOS include both linear and branched isomers Only the linear isomer is reported for all other analytes

Sample ID: 1607530-B101(S1-S2)**VAL - PFAS**

Client Data			Sample Data		Laboratory Data			
Name:	Alpha Analytical Laboratory		Matrix:	Soil	Lab Sample:	1601099-05	Date Received:	31-Aug-2016 9:33
Project:			Sample Size:	1.38 g	QC Batch:	B6I0041	Date Extracted:	08-Sep-2016 14:54
Date Collected:	26-Aug-2016 11:45		% Solids:	74.1	Date Analyzed:	13-Sep-16 03:47 Column: BEH C18 Analyst: AC		
Analyte	Conc. (ng/g)	RL	Qualifiers		Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	1.96			IS 13C2-PFOA	135	60 - 150	
PFOS	ND	1.96			IS 13C8-PFOS	103	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

The results are reported in dry weight

The sample size is reported in wet weight

Results reported to RL

When reported, PFBS, PFHxS and PFOS include both linear and branched isomers Only the linear isomer is reported for all other analytes

Sample ID: 1607530-B101(S3-S4)**VAL - PFAS**

Client Data			Sample Data		Laboratory Data			
Name:	Alpha Analytical Laboratory		Matrix:	Soil	Lab Sample:	1601099-06	Date Received:	31-Aug-2016 9:33
Project:			Sample Size:	1.30 g	QC Batch:	B6I0041	Date Extracted:	08-Sep-2016 14:54
Date Collected:	26-Aug-2016 12:00		% Solids:	78.5	Date Analyzed:	13-Sep-16 03:59 Column: BEH C18 Analyst: AC		
Analyte	Conc. (ng/g)	RL	Qualifiers		Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	1.96			IS 13C2-PFOA	148	60 - 150	
PFOS	ND	1.96			IS 13C8-PFOS	98.0	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

The results are reported in dry weight

The sample size is reported in wet weight

Results reported to RL

When reported, PFBS, PFHxS and PFOS include both linear and branched isomers Only the linear isomer is reported for all other analytes

DATA QUALIFIERS & ABBREVIATIONS

B	This compound was also detected in the method blank.
D	Dilution
E	The associated compound concentration exceeded the calibration range of the instrument.
H	Recovery and/or RPD was outside laboratory acceptance limits.
I	Chemical Interference
J	The amount detected is below the Reporting Limit/LOQ.
*	See Cover Letter
Conc.	Concentration
NA	Not applicable
ND	Not Detected
TEQ	Toxic Equivalency

Unless otherwise noted, solid sample results are reported in dry weight. Tissue samples are reported in wet weight.

CERTIFICATIONS

Accrediting Authority	Certificate Number
California Department of Health – ELAP	2892
DoD ELAP - A2LA Accredited - ISO/IEC 17025:2005	3091.01
Florida Department of Health	E87777
Hawaii Department of Health	N/A
Louisiana Department of Environmental Quality	01977
Maine Department of Health	2014022
Nevada Division of Environmental Protection	CA004132015-1
New Jersey Department of Environmental Protection	CA003
New York Department of Health	11411
Oregon Laboratory Accreditation Program	4042-004
Pennsylvania Department of Environmental Protection	012
South Carolina Department of Health	87002001
Texas Commission on Environmental Quality	T104704189-15-6
Virginia Department of General Services	7923
Washington Department of Ecology	C584
Wisconsin Department of Natural Resources	998036160

Current certificates and lists of licensed parameters are located in the Quality Assurance office and are available upon request

NELAP Accredited Test Methods

MATRIX: Air	
Description of Test	Method
Determination of Polychlorinated p-Dioxins & Polychlorinated Dibenzofurans	EPA 23

MATRIX: Biological Tissue	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Drinking Water	
Description of Test	Method
2,3,7,8-Tetrachlorodibenzo- p-dioxin (2,3,7,8-TCDD) GC/HRMS	EPA 1613
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537

MATRIX: Non-Potable Water	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Dioxin by GC/HRMS	EPA 613
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Solids	
Description of Test	Method
Tetra-Octa Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope	EPA 1613B

Dilution GC/HRMS	
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

SAMPLE LOG-IN CHECKLIST



Vista Project #: 1601099

TAT

Samples Arrival:	Date/Time <u>08/31/16 0933</u>	Initials: <u>BBB</u>	Location: <u>WR-2</u>
			Shelf/Rack: <u>NA</u>
Logged In:	Date/Time <u>09/01/16 1235</u>	Initials: <u>BBB</u>	Location: <u>WR-2</u>
			Shelf/Rack: <u>AS</u>
Delivered By:	FedEx <input type="checkbox"/> <u>UPS</u> <input checked="" type="checkbox"/> On Trac <input type="checkbox"/> DHL <input type="checkbox"/> Hand Delivered <input type="checkbox"/> Other <input type="checkbox"/>		
Preservation:	<u>Ice</u> <input checked="" type="checkbox"/> Blue Ice <input type="checkbox"/> Dry Ice <input type="checkbox"/> None <input type="checkbox"/>		
Temp °C: <u>1.9</u> (uncorrected)	Time:	Thermometer ID: IR-1	
Temp °C: <u>1.6</u> (corrected)	Probe used: Yes <input type="checkbox"/> No <input type="checkbox"/>		

	YES	NO	NA
Adequate Sample Volume Received?			
Holding Time Acceptable?			
Shipping Container(s) Intact?	✓		
Shipping Custody Seals Intact?			✓
Shipping Documentation Present?	✓		
Airbill	✓		
Trk # <u>1Z E 30654 019384 2982</u>			
Sample Container Intact?			
Sample Custody Seals Intact?	✓		
Chain of Custody / Sample Documentation Present?	✓		
COC Anomaly/Sample Acceptance Form completed?			
If Chlorinated or Drinking Water Samples, Acceptable Preservation?			
Na ₂ S ₂ O ₃ Preservation Documented?			
	COC	Sample Container	None
Shipping Container	Vista	<u>Client</u>	Retain
		<u>Return</u>	Dispose

Comments:



September 15, 2016

Vista Work Order No. 1601114

Ms. Karyn Raymond
Alpha Analytical Laboratory
8 Walkup Drive
Westborough, MA 01581

Dear Ms. Raymond,

Enclosed are the results for the sample set received at Vista Analytical Laboratory on September 03, 2016. This sample set was analyzed on a rush turn-around time. The SDG Number is L1627653.

Vista Analytical Laboratory is committed to serving you effectively. If you require additional information, please contact me at 916-673-1520 or by email at mmaier@vista-analytical.com.

Thank you for choosing Vista as part of your analytical support team.

Sincerely,

A handwritten signature in black ink that reads "Martha Maier".

Martha Maier
Laboratory Director



Vista Analytical Laboratory certifies that the report herein meets all the requirements set forth by NELAP for those applicable test methods. Results relate only to the samples as received by the laboratory. This report should not be reproduced except in full without the written approval of Vista.

Vista Analytical Laboratory 1104 Windfeld Way El Dorado Hills, CA 95762 ph: 916-673-1520 fx: 916-673-0106 www.vista-analytical.com

SDG Number L1627653

Vista Work Order No. 1601114

Case Narrative

Sample Condition on Receipt:

Three water samples were received in good condition and within the method temperature requirements. The samples were received and stored securely in accordance with Vista standard operating procedures and EPA methodology.

Analytical Notes:

Modified EPA Method 537

The samples were extracted and analyzed for PFOA and PFOS using Modified EPA Method 537. The results include both linear and branched isomers.

Holding Times

The samples were extracted and analyzed within the method hold times.

Quality Control

The Initial Calibration and Continuing Calibration Verifications met the acceptance criteria.

A Method Blank and Ongoing Precision and Recovery (OPR) sample were extracted and analyzed with the preparation batch. No analytes were detected in the Method Blank above the Reporting Limit. The OPR recoveries were within the method acceptance criteria.

The recoveries of all internal standards in the QC and field samples were within the acceptance criteria.

TABLE OF CONTENTS

Case Narrative.....	1
Table of Contents.....	3
Sample Inventory.....	4
Analytical Results.....	5
Qualifiers.....	11
Certifications.....	12
Sample Receipt.....	15

Sample Inventory Report

Vista Sample ID	Client Sample ID	Sampled	Received	Components/Containers
1601114-01	1607530-B101 (MW)	01-Sep-16 10:00	03-Sep-16 09:45	HDPE Bottle, 125 mL HDPE Bottle, 125 mL
1601114-02	1607530-B102 (MW)	01-Sep-16 10:10	03-Sep-16 09:45	HDPE Bottle, 125 mL HDPE Bottle, 125 mL
1601114-03	1607530-SW1	01-Sep-16 10:35	03-Sep-16 09:45	HDPE Bottle, 125 mL HDPE Bottle, 125 mL

ANALYTICAL RESULTS

Sample ID: Method Blank				Modified EPA Method 537			
Matrix: Aqueous		QC Batch: B6I0058		Lab Sample: B6I0058-BLK1		Date Analyzed: 13-Sep-16 17:52	
Sample Size: 0.125 L		Date Extracted: 13-Sep-2016 7:28		Column: BEH C18 Analyst: AC			
Analyte	Conc. (ng/L)	RL	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	8.00		IS 13C2-PFOA	92.7	60 - 150	
PFOS	ND	8.00		IS 13C8-PFOS	88.3	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit
 Results reported to RL
 When reported, PFBS, PFHxS, PFOA and PFOS include both linear and branched isomers. Only the linear isomer is reported for all other analytes

Sample ID: OPR					Modified EPA Method 537		
Matrix: Aqueous	QC Batch: B6I0058	Lab Sample: B6I0058-BS1		Date Analyzed: 13-Sep-16 17:14 Column: BEH C18 Analyst: AC			
Sample Size: 0.125 L	Date Extracted: 13-Sep-2016 7:28						
Analyte	Amt Found (ng/L)	Spike Amt	%R	Limits	Labeled Standard	%R	LCL-UCL
PFOA	73.9	80.0	92.4	70 - 130	IS 13C2-PFOA	104	60 - 150
PFOS	79.1	80.0	98.9	70 - 130	IS 13C8-PFOS	90.7	60 - 150

LCL-UCL - Lower control limit - upper control limit

Sample ID: 1607530-B101 (MW)

Modified EPA Method 537

Client Data		Sample Data		Laboratory Data	
Name:	Alpha Analytical Laboratory	Matrix:	Water	Lab Sample:	1601114-01
Project:		Sample Size:	0.127 L	Date Received:	03-Sep-2016 9:45
Date Collected:	01-Sep-2016 10:00			QC Batch:	B6I0058
				Date Analyzed:	13-Sep-16 18:18
				Column:	BEH C18
				Analyst:	AC

Analyte	Conc. (ng/L)	RL	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	7.86		IS 13C2-PFOA	117	60 - 150	
PFOS	ND	7.86		IS 13C8-PFOS	68.2	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

Results reported to RL

When reported, PFBS, PFHxS, PFOA and PFOS include both linear and branched isomers

Only the linear isomer is reported for all other analytes

Sample ID: 1607530-B102 (MW)

Modified EPA Method 537

Client Data		Sample Data		Laboratory Data	
Name:	Alpha Analytical Laboratory	Matrix:	Water	Lab Sample:	1601114-02
Project:		Sample Size:	0.125 L	Date Received:	03-Sep-2016 9:45
Date Collected:	01-Sep-2016 10:10			QC Batch:	B6I0058
				Date Analyzed:	13-Sep-16 18:30
				Column:	BEH C18
				Analyst:	AC

Analyte	Conc. (ng/L)	RL	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	11.2	8.01		IS 13C2-PFOA	101	60 - 150	
PFOS	16.1	8.01		IS 13C8-PFOS	88.9	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

Results reported to RL

When reported, PFBS, PFHxS, PFOA and PFOS include both linear and branched isomers

Only the linear isomer is reported for all other analytes

Sample ID: 1607530-SW1**Modified EPA Method 537**

Client Data		Sample Data		Laboratory Data	
Name:	Alpha Analytical Laboratory	Matrix:	Water	Lab Sample:	1601114-03
Project:		Sample Size:	0.123 L	Date Received:	03-Sep-2016 9:45
Date Collected:	01-Sep-2016 10:35			QC Batch:	B6I0058
				Date Analyzed:	13-Sep-16 18:43
					Column: BEH C18 Analyst: AC
					14-Sep-16 10:33
					Column: BEH C18 Analyst: AC

Analyte	Conc. (ng/L)	RL	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	842	8.12		IS 13C2-PFOA	101	60 - 150	
PFOS	2910	40.6	D	IS 13C8-PFOS	95.4	60 - 150	D

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

Results reported to RL

When reported, PFBS, PFHxS, PFOA and PFOS include both linear and branched isomers

Only the linear isomer is reported for all other analytes

DATA QUALIFIERS & ABBREVIATIONS

B	This compound was also detected in the method blank.
D	Dilution
E	The associated compound concentration exceeded the calibration range of the instrument.
H	Recovery and/or RPD was outside laboratory acceptance limits.
I	Chemical Interference
J	The amount detected is below the Reporting Limit/LOQ.
*	See Cover Letter
Conc.	Concentration
NA	Not applicable
ND	Not Detected
TEQ	Toxic Equivalency

Unless otherwise noted, solid sample results are reported in dry weight. Tissue samples are reported in wet weight.

CERTIFICATIONS

Accrediting Authority	Certificate Number
California Department of Health – ELAP	2892
DoD ELAP - A2LA Accredited - ISO/IEC 17025:2005	3091.01
Florida Department of Health	E87777
Hawaii Department of Health	N/A
Louisiana Department of Environmental Quality	01977
Maine Department of Health	2014022
Nevada Division of Environmental Protection	CA004132015-1
New Jersey Department of Environmental Protection	CA003
New York Department of Health	11411
Oregon Laboratory Accreditation Program	4042-004
Pennsylvania Department of Environmental Protection	012
South Carolina Department of Health	87002001
Texas Commission on Environmental Quality	T104704189-15-6
Virginia Department of General Services	7923
Washington Department of Ecology	C584
Wisconsin Department of Natural Resources	998036160

Current certificates and lists of licensed parameters are located in the Quality Assurance office and are available upon request

NELAP Accredited Test Methods

MATRIX: Air	
Description of Test	Method
Determination of Polychlorinated p-Dioxins & Polychlorinated Dibenzofurans	EPA 23

MATRIX: Biological Tissue	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Drinking Water	
Description of Test	Method
2,3,7,8-Tetrachlorodibenzo- p-dioxin (2,3,7,8-TCDD) GC/HRMS	EPA 1613
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537

MATRIX: Non-Potable Water	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Dioxin by GC/HRMS	EPA 613
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Solids	
Description of Test	Method
Tetra-Octa Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope	EPA 1613B

Dilution GC/HRMS	
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

SAMPLE LOG-IN CHECKLIST



Vista Project #: 1601114 TAT 14

Samples Arrival:	Date/Time: 9/3/16 09:45	Initials: WL	Location: WR2
			Shelf/Rack: NA
Logged In:	Date/Time: 09/06/16 1325	Initials: RAB	Location: WR-2
			Shelf/Rack: F6
Delivered By:	FedEx	<u>UPS</u>	On Trac
			DHL
			Hand Delivered
			Other
Preservation:	<u>Ice</u>	Blue Ice	Dry Ice
			None
Temp °C: 0.90 (uncorrected)	Time: 09:50		Thermometer ID: IR-1
Temp °C: 0.5 (corrected)	Probe used: Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		

	YES	NO	NA
Adequate Sample Volume Received?	✓		
Holding Time Acceptable?	✓		
Shipping Container(s) Intact?	✓		
Shipping Custody Seals Intact?			✓
Shipping Documentation Present?			✓
Airbill			
Trk #	1ZE30654449441588		
Sample Container Intact?	✓		
Sample Custody Seals Intact?			✓
Chain of Custody / Sample Documentation Present?	✓		
COC Anomaly/Sample Acceptance Form completed?		✓	
If Chlorinated or Drinking Water Samples, Acceptable Preservation?			✓
Na ₂ S ₂ O ₃ Preservation Documented?	COC	Sample Container	<u>None</u>
Shipping Container	Vista	<u>Client</u>	Retain
			Return
			Dispose

Comments:

Chain-of-Custody Record

Laboratory: **Alpha**

Laboratory Job # **21627653**

(Lab use only)



400 Unicorn Park Drive
Woburn, MA 01801
PH: 781.721.4000
FX: 781.721.4073

Project Information

Project Name: Eversource NH SRP

Project Location: Newington, NH

Project Number: 1607530

Project Manager: Mike Sabulis
(office: 781-721-4114) (cell: 508-633-9544)

Send Report to: Jess Englehart

Send EDD to: labdata@geiconsultants.com

Page 1 of 1

Sample Handling

Samples Field Filtered
YES NO NA

Sampled Shipped
With Ice

YES NO

Sample Specific Remarks

MCP PRESUMPTIVE CERTAINTY REQUIRED -- YES NO

If Yes, Are MCP Analytical Methods Required? YES NO NA

If Yes, Are Drinking Water Samples Submitted? YES NO NA

If Yes, Have You Met Minimum Field QC Requirements? YES NO NA

Lab Sample Number	GEI Sample ID	Collection		Matrix	No. of Bottles	Sampler(s) Initials	PFOS	PFOA	Analysis										
		Date	Time																
21627653-01	1607530-B101(MW)	9/1/2016	10:00	water	2	CRC	x	x											
02	1607530-B102(MW)	9/1/2016	10:10	water	2	MEG	x	x											
03	1607530-SW1	9/1/2016	10:35	water	2	CRC	x	x											

MCP Level Needed: GEI requires the most stringent Method 1 MCP standard be met for all analytes whenever possible.

Turnaround Time (Business days):

Normal X Other
10-Day 7-Day
5-Day 3-Day

Before submitting rush turnaround samples, you **must** notify the laboratory to confirm that the TAT can be achieved.

Additional Requirements/Comments/Remarks:

Relinquished by: (signature) 1. <i>Molly E Green</i>	Date: <i>9/1/16</i>	Time: <i>12:53</i>	Received by: (signature) 1. <i>GEI Sample Fridge</i>
Relinquished by: (signature) 2. <i>GEI Fridge</i>	Date: <i>9/2/16</i>	Time: <i>9:56</i>	Received by: (signature) 2. <i>Sabulis EOD</i>
Relinquished by: (signature) 3. <i>Sabulis EOD</i>	Date: <i>9/2/16</i>	Time: <i>9:57</i>	Received by: (signature) 3. <i>Lab Manager AAL 9-2-16 9:56</i>
Relinquished by: (signature) 4. <i>Lab Manager AAL</i>	Date: <i>9-2-16</i>	Time: <i>13:40</i>	Received by: (signature) 4. <i>Well Miller</i>



ANALYTICAL REPORT

Lab Number:	L1718562
Client:	GEI Consultants 400 Unicorn Park Drive Woburn, MA 01801
ATTN:	Mike Sabulis
Phone:	(781) 721-4114
Project Name:	EVERSOURCE NH SRP
Project Number:	1607530
Report Date:	06/21/17

The original project report/data package is held by Alpha Analytical. This report/data package is paginated and should be reproduced only in its entirety. Alpha Analytical holds no responsibility for results and/or data that are not consistent with the original.

Certifications & Approvals: MA (M-MA086), NH NELAP (2064), NJ NELAP (MA935), CT (PH-0574), IL (200077), ME (MA00086), MD (348), NY (11148), NC (25700/666), PA (68-03671), RI (LAO00065), TX (T104704476), VT (VT-0935), VA (460195), USDA (Permit #P330-14-00197).

320 Forbes Boulevard, Mansfield, MA 02048-1806
508-822-9300 (Fax) 508-822-3288 800-624-9220 - www.alphalab.com



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1718562
Report Date: 06/21/17

Alpha Sample ID	Client ID	Matrix	Sample Location	Collection Date/Time	Receive Date
L1718562-01	1607530-B101(MW)	WATER	NEWINGTON, NH	06/02/17 15:15	06/06/17
L1718562-02	1607530-B102(MW)	WATER	NEWINGTON, NH	06/02/17 12:45	06/06/17
L1718562-03	1607530-B103(MW)	WATER	NEWINGTON, NH	06/02/17 17:40	06/06/17
L1718562-04	1607530-FB	WATER	NEWINGTON, NH	06/02/17 15:15	06/06/17

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1718562
Report Date: 06/21/17

Case Narrative

The samples were received in accordance with the Chain of Custody and no significant deviations were encountered during the preparation or analysis unless otherwise noted. Sample Receipt, Container Information, and the Chain of Custody are located at the back of the report.

Results contained within this report relate only to the samples submitted under this Alpha Lab Number and meet NELAP requirements for all NELAP accredited parameters unless otherwise noted in the following narrative. The data presented in this report is organized by parameter (i.e. VOC, SVOC, etc.). Sample specific Quality Control data (i.e. Surrogate Spike Recovery) is reported at the end of the target analyte list for each individual sample, followed by the Laboratory Batch Quality Control at the end of each parameter. Tentatively Identified Compounds (TICs), if requested, are reported for compounds identified to be present and are not part of the method/program Target Compound List, even if only a subset of the TCL are being reported. If a sample was re-analyzed or re-extracted due to a required quality control corrective action and if both sets of data are reported, the Laboratory ID of the re-analysis or re-extraction is designated with an "R" or "RE", respectively. When multiple Batch Quality Control elements are reported (e.g. more than one LCS), the associated samples for each element are noted in the grey shaded header line of each data table. Any Laboratory Batch, Sample Specific % recovery or RPD value that is outside the listed Acceptance Criteria is bolded in the report. All specific QC information is also incorporated in the Data Usability format of our Data Merger tool where it can be reviewed along with any associated usability implications. Soil/sediments, solids and tissues are reported on a dry weight basis unless otherwise noted. Definitions of all data qualifiers and acronyms used in this report are provided in the Glossary located at the back of the report.

In reference to questions H (CAM) or 4 (RCP) when "NO" is checked, the performance criteria for CAM and RCP methods allow for some quality control failures to occur and still be within method compliance. In these instances the specific failure is not narrated but noted in the associated QC table. The information is also incorporated in the Data Usability format of our Data Merger tool where it can be reviewed along with any associated usability implications.

Please see the associated ADEx data file for a comparison of laboratory reporting limits that were achieved with the regulatory Numerical Standards requested on the Chain of Custody.

HOLD POLICY

For samples submitted on hold, Alpha's policy is to hold samples (with the exception of Air canisters) free of charge for 21 calendar days from the date the project is completed. After 21 calendar days, we will dispose of all samples submitted including those put on hold unless you have contacted your Client Service Representative and made arrangements for Alpha to continue to hold the samples. Air canisters will be disposed after 3 business days from the date the project is completed.

Please contact Client Services at 800-624-9220 with any questions.

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1718562
Report Date: 06/21/17

Case Narrative (continued)


Semivolatile Organics

WG1012571-3 LCSD: The internal standard (IS) response for 13C2-PFOA was below the acceptance criteria when compared to the continuing calibration, but within criteria when compared to the initial calibration. Target analytes recovered within criteria, therefore no further action was taken.

The WG1012571-4 Laboratory Duplicate RPD, performed on L1718562-01, is above the acceptance criteria for perfluorooctanesulfonic acid (pfos) (36%); however, the sample and duplicate results are less than five times the reporting limit. Therefore, the RPD is valid.

I, the undersigned, attest under the pains and penalties of perjury that, to the best of my knowledge and belief and based upon my personal inquiry of those responsible for providing the information contained in this analytical report, such information is accurate and complete. This certificate of analysis is not complete unless this page accompanies any and all pages of this report.

Authorized Signature:

 Susan O'Neil

Title: Technical Director/Representative

Date: 06/21/17

ORGANICS

SEMIVOLATILES

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1718562
Report Date: 06/21/17

SAMPLE RESULTS

Lab ID: L1718562-01
 Client ID: 1607530-B101(MW)
 Sample Location: NEWINGTON, NH

Date Collected: 06/02/17 15:15
 Date Received: 06/06/17
 Field Prep: Not Specified
 Extraction Method: EPA 537
 Extraction Date: 06/13/17 10:00

Matrix: Water
 Analytical Method: 122,537
 Analytical Date: 06/20/17 18:56
 Analyst: AR

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Perfluorinated Alkyl Acids by EPA 537 - Mansfield Lab						
Perfluorooctanoic Acid (PFOA)	2.48		ng/l	1.78	--	1
Perfluorooctanesulfonic Acid (PFOS)	3.05		ng/l	1.78	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
Perfluoro-n-[1,2-13C2]hexanoic Acid (13C-PFHxA)	102		70-130
Perfluoro-n-[1,2-13C2]decanoic Acid (13C-PFDA)	127		70-130
N-Deuterioethylperfluoro-1-octanesulfonamidoacetic Acid (d5-NEtFOSAA)	97		70-130

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1718562
Report Date: 06/21/17

SAMPLE RESULTS

Lab ID: L1718562-02
 Client ID: 1607530-B102(MW)
 Sample Location: NEWINGTON, NH

Date Collected: 06/02/17 12:45
 Date Received: 06/06/17
 Field Prep: Not Specified
 Extraction Method: EPA 537
 Extraction Date: 06/13/17 10:00

Matrix: Water
 Analytical Method: 122,537
 Analytical Date: 06/20/17 19:15
 Analyst: AR

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Perfluorinated Alkyl Acids by EPA 537 - Mansfield Lab						
Perfluorooctanoic Acid (PFOA)	7.11		ng/l	1.85	--	1
Perfluorooctanesulfonic Acid (PFOS)	14.2		ng/l	1.85	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
Perfluoro-n-[1,2-13C2]hexanoic Acid (13C-PFHxA)	83		70-130
Perfluoro-n-[1,2-13C2]decanoic Acid (13C-PFDA)	72		70-130
N-Deuterioethylperfluoro-1-octanesulfonamidoacetic Acid (d5-NEtFOSAA)	74		70-130

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1718562
Report Date: 06/21/17

SAMPLE RESULTS

Lab ID: L1718562-03
 Client ID: 1607530-B103(MW)
 Sample Location: NEWINGTON, NH
 Matrix: Water
 Analytical Method: 122,537
 Analytical Date: 06/20/17 19:33
 Analyst: AR

Date Collected: 06/02/17 17:40
 Date Received: 06/06/17
 Field Prep: Not Specified
 Extraction Method: EPA 537
 Extraction Date: 06/13/17 10:00

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Perfluorinated Alkyl Acids by EPA 537 - Mansfield Lab						
Perfluorooctanoic Acid (PFOA)	ND		ng/l	1.85	--	1
Perfluorooctanesulfonic Acid (PFOS)	1.87		ng/l	1.85	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
Perfluoro-n-[1,2-13C2]hexanoic Acid (13C-PFHxA)	77		70-130
Perfluoro-n-[1,2-13C2]decanoic Acid (13C-PFDA)	85		70-130
N-Deuterioethylperfluoro-1-octanesulfonamidoacetic Acid (d5-NEtFOSAA)	86		70-130

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1718562
Report Date: 06/21/17

SAMPLE RESULTS

Lab ID: L1718562-04
 Client ID: 1607530-FB
 Sample Location: NEWINGTON, NH
 Matrix: Water
 Analytical Method: 122,537
 Analytical Date: 06/20/17 18:47
 Analyst: AR

Date Collected: 06/02/17 15:15
 Date Received: 06/06/17
 Field Prep: Not Specified
 Extraction Method: EPA 537
 Extraction Date: 06/13/17 10:00

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
Perfluorinated Alkyl Acids by EPA 537 - Mansfield Lab						
Perfluorooctanoic Acid (PFOA)	ND		ng/l	1.78	--	1
Perfluorooctanesulfonic Acid (PFOS)	ND		ng/l	1.78	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
Perfluoro-n-[1,2-13C2]hexanoic Acid (13C-PFHxA)	87		70-130
Perfluoro-n-[1,2-13C2]decanoic Acid (13C-PFDA)	97		70-130
N-Deuterioethylperfluoro-1-octanesulfonamidoacetic Acid (d5-NEtFOSAA)	98		70-130

Project Name: EVERSOURCE NH SRP

Lab Number: L1718562

Project Number: 1607530

Report Date: 06/21/17

**Method Blank Analysis
Batch Quality Control**

Analytical Method: 122,537
 Analytical Date: 06/20/17 18:38
 Analyst: AR

Extraction Method: EPA 537
 Extraction Date: 06/13/17 10:00

Parameter	Result	Qualifier	Units	RL	MDL
Perfluorinated Alkyl Acids by EPA 537 - Mansfield Lab for sample(s): 01-04 Batch: WG1012571-1					
Perfluorooctanoic Acid (PFOA)	ND		ng/l	2.00	--
Perfluorooctanesulfonic Acid (PFOS)	ND		ng/l	2.00	--

Surrogate	%Recovery	Qualifier	Acceptance Criteria
Perfluoro-n-[1,2-13C2]hexanoic Acid (13C-PFHxA)	96		70-130
Perfluoro-n-[1,2-13C2]decanoic Acid (13C-PFDA)	116		70-130
N-Deuterioethylperfluoro-1-octanesulfonamidoacetic Acid (d5-NEtFOSAA)	99		70-130

Lab Control Sample Analysis Batch Quality Control

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1718562
Report Date: 06/21/17

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Perfluorinated Alkyl Acids by EPA 537 - Mansfield Lab Associated sample(s): 01-04 Batch: WG1012571-2 WG1012571-3								
Perfluorooctanoic Acid (PFOA)	94		108		70-130	14		30
Perfluorooctanesulfonic Acid (PFOS)	86		110		70-130	24		30

Surrogate	LCS %Recovery	Qual	LCSD %Recovery	Qual	Acceptance Criteria
Perfluoro-n-[1,2-13C2]hexanoic Acid (13C-PFHxA)	95		111		70-130
Perfluoro-n-[1,2-13C2]decanoic Acid (13C-PFDA)	98		112		70-130
N-Deuterioethylperfluoro-1-octanesulfonamidoacetic Acid (d5-NEtFOSAA)	92		122		70-130

Matrix Spike Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1718562

Project Number: 1607530

Report Date: 06/21/17

Parameter	Native Sample	MS Added	MS Found	MS %Recovery	Qual	MSD Found	MSD %Recovery	Qual	Recovery Limits	RPD	Qual	RPD Limits
Perfluorinated Alkyl Acids by EPA 537 - Mansfield Lab Associated sample(s): 01-04 QC Batch ID: WG1012571-5 QC Sample: L1718562-02 Client ID: 1607530-B102(MW)												
Perfluorooctanoic Acid (PFOA)	7.11	463	454	96		-	-		70-130	-		30
Perfluorooctanesulfonic Acid (PFOS)	14.2	428	444	100		-	-		70-130	-		30

Surrogate	MS % Recovery	Qualifier	MSD % Recovery	Qualifier	Acceptance Criteria
N-Deuterioethylperfluoro-1-octanesulfonamidoacetic Acid (d5-NEtFOSAA)	86				70-130
Perfluoro-n-[1,2-13C2]decanoic Acid (13C-PFDA)	90				70-130
Perfluoro-n-[1,2-13C2]hexanoic Acid (13C-PFHxA)	94				70-130

Lab Duplicate Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Project Number: 1607530

Lab Number: L1718562

Report Date: 06/21/17

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
Perfluorinated Alkyl Acids by EPA 537 - Mansfield Lab Associated sample(s): 01-04 QC Batch ID: WG1012571-4 QC Sample: L1718562-01 Client ID: 1607530-B101(MW)						
Perfluorooctanoic Acid (PFOA)	2.48	2.24	ng/l	10		30
Perfluorooctanesulfonic Acid (PFOS)	3.05	2.13	ng/l	36	Q	30

Surrogate	%Recovery	Qualifier	%Recovery	Qualifier	Acceptance Criteria
Perfluoro-n-[1,2-13C2]hexanoic Acid (13C-PFHxA)	102		88		70-130
Perfluoro-n-[1,2-13C2]decanoic Acid (13C-PFDA)	127		104		70-130
N-Deuterioethylperfluoro-1-octanesulfonamidoacetic Acid (d5-NEtFOSAA)	97		88		70-130

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Serial_No:06211716:15
Lab Number: L1718562
Report Date: 06/21/17

Sample Receipt and Container Information

Were project specific reporting limits specified?

YES

Cooler Information

Cooler **Custody Seal**
A Absent

Container Information

Container ID	Container Type	Cooler	Initial pH	Final pH	Temp deg C	Pres	Seal	Frozen Date/Time	Analysis(*)
L1718562-01A	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-01B	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-01C	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-02A	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-02B	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-02C	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-03A	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-03B	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-03C	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-04A	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)

*Values in parentheses indicate holding time in days



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1718562
Report Date: 06/21/17

GLOSSARY

Acronyms

EDL	- Estimated Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The EDL includes any adjustments from dilutions, concentrations or moisture content, where applicable. The use of EDLs is specific to the analysis of PAHs using Solid-Phase Microextraction (SPME).
EPA	- Environmental Protection Agency.
LCS	- Laboratory Control Sample: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
LCSD	- Laboratory Control Sample Duplicate: Refer to LCS.
LFB	- Laboratory Fortified Blank: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
MDL	- Method Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The MDL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
MS	- Matrix Spike Sample: A sample prepared by adding a known mass of target analyte to a specified amount of matrix sample for which an independent estimate of target analyte concentration is available.
MSD	- Matrix Spike Sample Duplicate: Refer to MS.
NA	- Not Applicable.
NC	- Not Calculated: Term is utilized when one or more of the results utilized in the calculation are non-detect at the parameter's reporting unit.
NDPA/DPA	- N-Nitrosodiphenylamine/Diphenylamine.
NI	- Not Ignitable.
NP	- Non-Plastic: Term is utilized for the analysis of Atterberg Limits in soil.
RL	- Reporting Limit: The value at which an instrument can accurately measure an analyte at a specific concentration. The RL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
RPD	- Relative Percent Difference: The results from matrix and/or matrix spike duplicates are primarily designed to assess the precision of analytical results in a given matrix and are expressed as relative percent difference (RPD). Values which are less than five times the reporting limit for any individual parameter are evaluated by utilizing the absolute difference between the values; although the RPD value will be provided in the report.
SRM	- Standard Reference Material: A reference sample of a known or certified value that is of the same or similar matrix as the associated field samples.
STLP	- Semi-dynamic Tank Leaching Procedure per EPA Method 1315.
TIC	- Tentatively Identified Compound: A compound that has been identified to be present and is not part of the target compound list (TCL) for the method and/or program. All TICs are qualitatively identified and reported as estimated concentrations.

Footnotes

- 1 - The reference for this analyte should be considered modified since this analyte is absent from the target analyte list of the original method.

Terms

Analytical Method: Both the document from which the method originates and the analytical reference method. (Example: EPA 8260B is shown as 1,8260B.) The codes for the reference method documents are provided in the References section of the Addendum.

Final pH: As it pertains to Sample Receipt & Container Information section of the report, Final pH reflects pH of container determined after adjustment at the laboratory, if applicable. If no adjustment required, value reflects Initial pH.

Frozen Date/Time: With respect to Volatile Organics in soil, Frozen Date/Time reflects the date/time at which associated Reagent Water-preserved vials were initially frozen. Note: If frozen date/time is beyond 48 hours from sample collection, value will be reflected in 'bold'.

Initial pH: As it pertains to Sample Receipt & Container Information section of the report, Initial pH reflects pH of container determined upon receipt, if applicable.

Total: With respect to Organic analyses, a 'Total' result is defined as the summation of results for individual isomers or Aroclors. If a 'Total' result is requested, the results of its individual components will also be reported. This is applicable to 'Total' results for methods 8260, 8081 and 8082.

Data Qualifiers

- A** - Spectra identified as "Aldol Condensation Product".
- B** - The analyte was detected above the reporting limit in the associated method blank. Flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For MCP-related

Report Format: Data Usability Report



Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1718562
Report Date: 06/21/17

Data Qualifiers

projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For DOD-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank AND the analyte was detected above one-half the reporting limit (or above the reporting limit for common lab contaminants) in the associated method blank. For NJ-Air-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte above the reporting limit. For NJ-related projects (excluding Air), flag only applies to associated field samples that have detectable concentrations of the analyte, which was detected above the reporting limit in the associated method blank or above five times the reporting limit for common lab contaminants (Phthalates, Acetone, Methylene Chloride, 2-Butanone).

- C** - Co-elution: The target analyte co-elutes with a known lab standard (i.e. surrogate, internal standards, etc.) for co-extracted analyses.
- D** - Concentration of analyte was quantified from diluted analysis. Flag only applies to field samples that have detectable concentrations of the analyte.
- E** - Concentration of analyte exceeds the range of the calibration curve and/or linear range of the instrument.
- G** - The concentration may be biased high due to matrix interferences (i.e. co-elution) with non-target compound(s). The result should be considered estimated.
- H** - The analysis of pH was performed beyond the regulatory-required holding time of 15 minutes from the time of sample collection.
- I** - The lower value for the two columns has been reported due to obvious interference.
- M** - Reporting Limit (RL) exceeds the MCP CAM Reporting Limit for this analyte.
- NJ** - Presumptive evidence of compound. This represents an estimated concentration for Tentatively Identified Compounds (TICs), where the identification is based on a mass spectral library search.
- P** - The RPD between the results for the two columns exceeds the method-specified criteria.
- Q** - The quality control sample exceeds the associated acceptance criteria. For DOD-related projects, LCS and/or Continuing Calibration Standard exceedences are also qualified on all associated sample results. Note: This flag is not applicable for matrix spike recoveries when the sample concentration is greater than 4x the spike added or for batch duplicate RPD when the sample concentrations are less than 5x the RL. (Metals only.)
- R** - Analytical results are from sample re-analysis.
- RE** - Analytical results are from sample re-extraction.
- S** - Analytical results are from modified screening analysis.
- J** - Estimated value. This represents an estimated concentration for Tentatively Identified Compounds (TICs).
- ND** - Not detected at the reporting limit (RL) for the sample.

Project Name: EVERSOURCE NH SRP
Project Number: 1607530

Lab Number: L1718562
Report Date: 06/21/17

REFERENCES

- 122 Determination of Selected Perfluorinated Alkyl Acids in Drinking Water by Solid Phase Extraction and Liquid Chromatography/Tandem Mass Spectrometry (LC/MS/MS). EPA Method 537, EPA/600/R-08/092. Version 1.1, September 2009.

LIMITATION OF LIABILITIES

Alpha Analytical performs services with reasonable care and diligence normal to the analytical testing laboratory industry. In the event of an error, the sole and exclusive responsibility of Alpha Analytical shall be to re-perform the work at its own expense. In no event shall Alpha Analytical be held liable for any incidental, consequential or special damages, including but not limited to, damages in any way connected with the use of, interpretation of, information or analysis provided by Alpha Analytical.

We strongly urge our clients to comply with EPA protocol regarding sample volume, preservation, cooling, containers, sampling procedures, holding time and splitting of samples in the field.



Certification Information

The following analytes are not included in our Primary NELAP Scope of Accreditation:

Westborough Facility

EPA 624: m/p-xylene, o-xylene

EPA 8260C: NPW: 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene, Azobenzene; SCM: Iodomethane (methyl iodide), Methyl methacrylate, 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene.

EPA 8270D: NPW: Dimethylnaphthalene,1,4-Diphenylhydrazine; SCM: Dimethylnaphthalene,1,4-Diphenylhydrazine.

EPA 300: DW: Bromide

EPA 6860: NPW and SCM: Perchlorate

EPA 9010: NPW and SCM: Amenable Cyanide Distillation

EPA 9012B: NPW: Total Cyanide

EPA 9050A: NPW: Specific Conductance

SM3500: NPW: Ferrous Iron

SM4500: NPW: Amenable Cyanide, Dissolved Oxygen; SCM: Total Phosphorus, TKN, NO₂, NO₃.

SM5310C: DW: Dissolved Organic Carbon

Mansfield Facility

SM 2540D: TSS

EPA 3005A NPW

EPA 8082A: NPW: PCB: 1, 5, 31, 87,101, 110, 141, 151, 153, 180, 183, 187.

EPA TO-15: Halothane, 2,4,4-Trimethyl-2-pentene, 2,4,4-Trimethyl-1-pentene, Thiophene, 2-Methylthiophene,

3-Methylthiophene, 2-Ethylthiophene, 1,2,3-Trimethylbenzene, Indan, Indene, 1,2,4,5-Tetramethylbenzene, Benzothiophene, 1-Methylnaphthalene.

Biological Tissue Matrix: EPA 3050B

The following analytes are included in our Massachusetts DEP Scope of Accreditation

Westborough Facility:

Drinking Water

EPA 300.0: Nitrate-N, Fluoride, Sulfate; **EPA 353.2:** Nitrate-N, Nitrite-N; **SM4500NO3-F:** Nitrate-N, Nitrite-N; **SM4500F-C, SM4500CN-CE, EPA 180.1, SM2130B, SM4500CI-D, SM2320B, SM2540C, SM4500H-B**

EPA 332: Perchlorate; **EPA 524.2:** THMs and VOCs; **EPA 504.1:** EDB, DBCP.

Microbiology: **SM9215B; SM9223-P/A, SM9223B-Colilert-QT, SM9222D.**

Non-Potable Water

SM4500H,B, EPA 120.1, SM2510B, SM2540C, SM2320B, SM4500CL-E, SM4500F-BC, SM4500NH3-BH, EPA 350.1: Ammonia-N, **LACHAT 10-107-06-1-B:** Ammonia-N, **SM4500NO3-F, EPA 353.2:** Nitrate-N, **EPA 351.1, SM4500P-E, SM4500P-B, E, SM4500SO4-E, SM5220D, EPA 410.4, SM5210B, SM5310C, SM4500CL-D, EPA 1664, EPA 420.1, SM4500-CN-CE, SM2540D.**

EPA 624: Volatile Halocarbons & Aromatics,

EPA 608: Chlordane, Toxaphene, Aldrin, alpha-BHC, beta-BHC, gamma-BHC, delta-BHC, Dieldrin, DDD, DDE, DDT, Endosulfan I, Endosulfan II, Endosulfan sulfate, Endrin, Endrin Aldehyde, Heptachlor, Heptachlor Epoxide, PCBs

EPA 625: SVOC (Acid/Base/Neutral Extractables), **EPA 600/4-81-045:** PCB-Oil.

Microbiology: **SM9223B-Colilert-QT; Enterolert-QT, SM9221E.**

Mansfield Facility:

Drinking Water

EPA 200.7: Ba, Be, Cd, Cr, Cu, Ni, Na, Ca. **EPA 200.8:** Sb, As, Ba, Be, Cd, Cr, Cu, Pb, Ni, Se, TL. **EPA 245.1 Hg.**

Non-Potable Water

EPA 200.7: Al, Sb, As, Be, Cd, Ca, Cr, Co, Cu, Fe, Pb, Mg, Mn, Mo, Ni, K, Se, Ag, Na, Sr, TL, Ti, V, Zn.

EPA 200.8: Al, Sb, As, Be, Cd, Cr, Cu, Pb, Mn, Ni, Se, Ag, TL, Zn.

EPA 245.1 Hg.

SM2340B

For a complete listing of analytes and methods, please contact your Alpha Project Manager.

Appendix D

Groundwater Model Description

NEWINGTON NH – SRP INSTALLATION DEWATERING FLOW ESTIMATE FOR INSTALLATION TRENCH GW MODFLOW MODEL DESCRIPTION

Objective:

A trench excavation for a 115 kV transmission main installation is proposed across a farm field. Objective is to estimate dewatering rates to maintain dry excavation for utility trench.

Method:

Three-dimensional MODFLOW groundwater model used that directly outputs flow rate. Visual MODFLOW ® is a graphical user interface that runs the industry standard USGS MODFLOW code solving the groundwater continuity equation.

Assumptions:

Groundwater flow into excavations was modeled as steady state flow, assuming excavation open to full depth. Model space is shown on Figure 1. The model extends downward to elevation +10 ft. NAVD, which corresponds to an approximate 50 – 65-ft. aquifer thickness with impermeable base.

The water table aquifer is of relatively large extent such that a steady state cone of depression from dewatering is not expected to extend to the aquifer boundary during the dewatering period. The model therefore represents partial drawdown. For predictive model, the modeled east and west trench segments were boxed in with head boundaries relatively close to the trenches (40 ft.) to represent assumed extent of aquifer influence from temporary dewatering (Figure 2). A close head boundary provides a higher, more conservative flow rate estimate than infinite-extent assumptions. In a sensitivity analysis, moving the head boundary closer to the excavation (20 feet) resulted in a 30% increase in estimated flow. As the sensitivity prediction is within an order of magnitude, head boundary distance is not considered significant in this range.

Soil data: Soil borings indicate the water table aquifer is comprised of fine-grained alluvium, with occasional thin sand lenses. Hydraulic conductivity testing was performed at two locations, where values of 0.06 and 0.22 ft./day were estimated for monitoring wells in the western and eastern project areas, respectively. Hydraulic conductivity zones are shown on Figure 1.

The predictive model was run using dry and wet weather water table conditions. Depths to water in

Method:

Dewatering rates were estimated assuming a 25-foot trench length open at a time, with 5-foot width. Two trench lengths were modeled separately, representing the two soil conductivity zones, where shown on Figure 2. The computational grid is also shown on Figure 2. The model contains 61 vertical layers for discretization of vertical flow.

NEWINGTON NH – SRP INSTALLATION DEWATERING FLOW ESTIMATE FOR INSTALLATION TRENCH GW MODFLOW MODEL DESCRIPTION

Method (continued):

The model was bounded to include the full run of trench. Constant head cells were assigned within trench segments assuming sumps control water level. Both segments were boxed in with head boundaries approximately 40 feet from the trench (Figure 2), assuming a cone of influence would not extend very far during the period of open excavation. Head boundaries were assigned the elevations shown on Figure 3. The head boundaries create two separate model domains for each segment.

Site-specific elevations and the head boundary enclosures were used for reference purposes as shown on Figure 2. A 25-foot trench segment two feet below water table in soil of similar hydraulic conductivity would yield similar results. Similarly, smaller models the size of the head boundary enclosures would yield similar results.

For both trench segments, dewatering estimates were computed with and without inclusion of an approximately 6-inch sand seam (hydraulic conductivity = 5 ft./d) about a foot above excavation base.


Results:

Results shown and tabulated on Figure 4. Comparatively, predicted rates increase disproportionately higher with the sand seam assumption in the east segment.



Limitations:

Model simulations represent seepage from soil strata represented as uniform, homogeneous, and isotropic. The soil properties modeled are represented by two borings and two hydraulic conductivity test results, which is a relatively low data density. Flow rate estimates may vary with additional information. Actual variability encountered may result in dewatering rates different than those predicted.


Potential water sources not modeled may also need to be considered for planning purposes, including but not limited to free drainage from soil while being excavated, storm runoff, channeling from high conductivity zones or other hydraulic connections to surface water, and subsurface features with contained or perched water.



BASE PLAN SOURCE:
 "115KV F107 UNDERGROUND TRANSMISSION LINE",
 PLAN AND PROFILE VIEW, REVISION 7, 6/24/16

<p>TRANSMISSION MAIN TRENCH DEWATERING SEACOAST RELIABILITY PROJECT NEWINGTON, NEW HAMPSHIRE</p>		<p>MODEL SPACE</p>
	<p>Project 1607530</p>	<p>June 2017 Figure 1</p>


NEWINGTON



EAST – WEST CROSS SECTION ALONG TRENCH

LEGEND

- WATER TABLE ELEVATION USED IN MODEL FOR RESPECTIVE TRENCH SEGMENT. WEST USES MW101, EAST USES MW102.
- IDEALIZED WATER TABLE



DRAWING SOURCE:
"115kV F107 UNDERGROUND TRANSMISSION LINE",
PLAN AND PROFILE VIEW, REVISION 7, 6/24/16

TRANSMISSION MAIN TRENCH DEWATERING
SEACOAST RELIABILITY PROJECT
NEWINGTON, NEW HAMPSHIRE



IDEALIZED WATER TABLE
PROFILE

Project 1607530


June 2017

Figure 3

RESULTS SUMMARY

Trench Segment	Units	LOW GROUNDWATER		HIGH GROUNDWATER	
		West	East	West	East
Station	Ft.	500+00 to 500+25	503+75 to 504+00	500+00 to 500+25	503+75 to 504+00
Assumed Ground Surface	Ft.	41	55	41	55
Static Depth to Water (a)	Ft.	4.8	3.8	0.83	1.12
Static GW elev	ft. NAVD	37	51	40.2	54
Depth of Trench	Ft.	7	8	7	8
Drawdown	Ft.	3	4	6.2	7
Hyd. Conductivity	ft./day	0.06	0.22	0.06	0.22
Target GW elev	ft. NAVD	34	47	34	47
Dewatering Rate - no sand seam	gpd	45	486	104	942
Dewatering Rate - with sand seam	gpd	82	770	187	1466

a. Depth below ground surface at MW101 (west segment) or MW102 (east segment).



TRANSMISSION MAIN TRENCH DEWATERING
SEACOAST RELIABILITY PROJECT
NEWINGTON, NEW HAMPSHIRE

EVERSOURCE
ENERGY



Project 1607530

**DEWATERING
ESTIMATE AND
DRAWDOWN PLOTS**

June 2017

Figure 4