

**REVISED SOIL AND GROUNDWATER MANAGEMENT PLAN**  
**July 18, 2018**  
**Eversource Seacoast Reliability Project**  
**Gundalow Landing Newington to Portsmouth Substation Portsmouth, New Hampshire**

**1. Introduction**

This document presents the requirements and procedures to be undertaken by Eversource personnel or hired contractors that excavate soil or manage soil or groundwater during installation of a new electric transmission line from Gundalow Landing in Newington to the Portsmouth Substation in Portsmouth, New Hampshire (the Project Area; Fig. 1). The new 115 kV transmission line is being installed as part of Eversource's Seacoast Reliability Project (SRP). The SRP will be installed in an existing distribution right-of-way corridor. The Project Area subject to this plan is approximately 4.25 miles long and begins at Gundalow Landing adjacent to Little Bay in the west and terminates at the Portsmouth Substation in the east (Fig. 1).

A site specific *Updated Soil and Water Investigation and Management Plan*, dated December 15, 2017, has been developed for the Darius Frink Farm property in Newington and is included in Appendix A. This plan is referenced in a Memorandum of Understanding (MOU) between Eversource and the Rockingham County Conservation District (RCCD) dated January 24, 2018.

**2. Background and Regulatory History**

The SRP alignment in Newington begins at Gundalow Landing and proceeds northeast for approximately 1.8 miles where it then turns southeasterly and continues along the Spaulding Turnpike for approximately 1.5 miles. The SRP then proceeds east over the Spaulding Turnpike and continues for 1 mile, terminating at the Portsmouth Substation. The project route is in proximity to the northern and eastern boundaries of the former Pease Air Force Base. Several historical releases are being managed at Pease including releases of jet fuel and other petroleum constituents, chlorinated solvents, and perfluorinated compounds (PFCs).

On behalf of Eversource, GEI Consultants, Inc. (GEI) filed an Area of Special Notice (ASN) request with the Pease Development Authority in May 2017 and was forwarded a letter from the United States Air Force (USAF) in August 2017, included in Appendix B. The letter documented that the project was located within (or in proximity to) two delineated Groundwater Management Zones associated with the former Pease Air Force Base as well as in areas known to have PFCs in groundwater. Specifically, the eastern boundaries of the GMZs associated with the historical chlorinated solvent release at Landfill Site 5 and Bulk Fuel Storage Area Site 13 are transected by the project as shown on the Institutional Controls Map included in Appendix B. In October of 2017, Scott Hilton of the New Hampshire Department of Environmental Services (NHDES) Waste Management Division, informed Eversource and GEI that the delineation of the GMZ for PFCs associated with Pease Site 8 is ongoing and that it is likely that the project route currently transects portions of the eventual GMZ. However, the timeline for establishment of the new GMZ was not available. Therefore, Eversource has conservatively assumed that soil and groundwater between Gundalow Landing and the Spaulding Turnpike may be impacted by PFCs.

Proper procedures, including best management practices, for on-site management and off-site disposal of soil and groundwater are necessary to reduce the potential for exposure to oil and hazardous materials (OHM) and be protective of workers, the public, and environment. The objectives of this Soil and Groundwater Management Plan are to:

- Ensure that soil and groundwater is managed appropriately on-site or disposed of appropriately off site if necessary; and

- Specify procedures to limit exposures to contaminated soil or groundwater via dermal contact, inhalation, and/or ingestion.

## **2.1 2.1 NHDES Emergency Rule for PFCs**

In May 2016, NHDES enacted Emergency Rule 05-31-16 under Env-Or-600 which includes the addition of perfluorooctanoic acid (PFOA) and perfluorooctane sulfonate (PFOS) to the New Hampshire state ambient groundwater quality standards (AGQS). The AGQS for PFOA, PFOS, and the combined concentration of PFOA and PFOS is 0.07 µg/L. Env-Or-600 does not currently include soil standards or regulations for PFOA or PFOS.

## **2.2 Adoption of Regulatory Changes**

Eversource recognizes that PFOA and PFOS are emerging contaminants and that regulatory standards may be adjusted during the course of the project. If NHDES adopts new standards during the timeframe of this project, the new standards will be applied, where applicable, for soil and groundwater management. As stated above, Eversource has conservatively assumed that soil and groundwater between Gundalow Landing and the Portsmouth Substation may be impacted by PFCs and will require the selected Contractor(s) to manage soil and groundwater accordingly.

## **3. Preconstruction Requirements**

The following must be completed before subsurface work commences, and approved by Eversource:

- **Notify Eversource Personnel:** The Eversource Project Manager shall be notified at least 10 business days prior to performing planned (non-emergency) soil excavation or other subsurface work that will require management of soil or groundwater. Also, Eversource shall be notified immediately (within one hour) if unanticipated conditions are encountered such as buried debris including drums, tanks or other containers.
- **Health and Safety Plan (HASP):** The contractor selected to perform the work in the Project Area is expected to prepare a HASP for its workers and the public to address the anticipated contaminants of concern, specifically PFOA, PFOS, and arsenic as well as potential contaminants including petroleum compounds or chlorinated compounds. The HASP shall include historical site characterization data. The HASP shall be prepared by a Certified Industrial Hygienist or other qualified individual appropriately trained in worker health and safety procedures and requirements. The contractor is solely responsible for conducting the work in a manner that is protective of workers and the public. Employees that will be handling contaminated or potentially contaminated soil or water are required to have OSHA HAZWOPER 40-hour training in accordance with standard 1910.120(e).
- **Regulatory Review and Submittals:** A review of other federal, state, or local regulatory requirements (e.g., National Pollutant Discharge Elimination System permits) shall be conducted before work commences depending on the location and type of planned activity.

## **4. Work Area Perimeter Monitoring for PFCs**

General screening levels for PFOA and PFOS in soil and groundwater are not available. Based on information from the United States Environmental Protection Agency (USEPA) and New Hampshire Environmental Health Program (EHP), GEI derived the following suggested construction worker PFC screening levels for the project, where applicable. The selected contractor may use these screening levels to develop their Health and Safety Plan (HASP) and Job Hazard Analysis (JHA), as appropriate.



#### **4.1 Soil**

GEI derived a human health risk-based screening level (SL) for a construction worker exposure to PFOA and PFOS in soil based on the EHP and NHDES methodology applied to derive a Direct Contact Risk-Based (DCRB) soil concentration for PFOA and PFOS in soil. Exposure assumptions used to derive these soil SLs were similar to NHDES Soil Category S-3 exposures considered protective of adult exposures to soil during short but intense exposures, such as during excavation work. These risk-based soil SLs account for exposure to impacted soil as a result of incidental ingestion and dermal contact during excavation work. Table 1 presents the soil SL derived for both PFOA and PFOS of 0.5 mg/kg.

The adult construction worker was assumed to be exposed to outdoor soil a total of 250 days a year. This assumption was based on an excavation worker exposed to soil 5 days per week for a 1-year excavation project (350 days) assuming a worker takes 2 weeks of vacation in a year. Based on NHDES guidance, the adult excavation worker was assumed to ingest 480 mg of soil per day of intense excavation work. Also based on NHDES guidance, a soil adherence factor equal to 0.2 mg/cm<sup>2</sup> was assumed and an exposed skin surface area of 3,104 cm<sup>2</sup> was assumed, which includes hands, forearms, face and neck. Additional exposure parameters based on NHDES guidance are presented in Table 1. USEPA applies different exposure assumptions for the construction worker exposure scenario in the derivation of Regional Screening Levels (RSLs) for soil. Based on USEPA exposure assumptions for the construction worker, which are noted in Table 1, a slightly higher Construction Worker Soil Screening Level for PFOA and PFOS of 0.7 mg/kg could be derived.

The USEPA derived a Reference Dose (RfD) to evaluate non-cancer effects for PFOA and PFOS of  $2 \times 10^{-5}$  mg/kg-day, based on developmental effects. USEPA also derived a Cancer Slope Factor (CSF) for PFOA of 0.07 (mg/kg-day)<sup>-1</sup>; however, according to USEPA, the non-cancer developmental endpoint for PFOA represented by the RfD is protective of the cancer endpoint. In addition, because the critical effect identified for PFOA and PFOS is a developmental endpoint and can potentially result from a short-term exposure during a critical period of development, USEPA concludes that the chronic RfD is applicable to both short-term and chronic risk assessment scenarios. Therefore, it is appropriate to use the chronic RfD derived for both PFOA and PFOS to estimate short-term or subchronic risk-based SLs for a construction worker. As a result, it is GEI's opinion that a conservative SL for construction workers of 0.5 mg/kg be used for both PFOA and PFOS as stated above and shown in Table 1.

#### **4.2 Water**

USEPA derived a drinking water Health Advisory (HA) and NHDES derived the AGQS for PFOA and PFOS of 0.07 µg/L. This HA is considered protective of lifetime exposures to PFOA and PFOS from residential ingestion of drinking water. This HA does not consider potential exposure to PFOA and PFOS as a result of dermal exposure or inhalation exposure. However, USEPA notes that neither PFOA nor PFOS are volatile and are therefore not expected to be present in air except if bound to particulate matter. According to USEPA's Health Effects Support Document for PFOA (May 2016), there is evidence that PFOA is absorbed following dermal exposure. The EPA document presents a permeability coefficient for PFOA of  $9.49 \times 10^{-7}$  cm/hour for human skin. USEPA risk based equations for deriving RSLs (May 2016) for dermal exposure to water were used to derive the Construction Worker Groundwater Screening Level for PFOA and PFOS of 1,000 µg/Liter.

## **5. Soil Management**

### **5.1 Soil Excavation**

Excavated material shall be handled in general accordance with *The New Hampshire Code of Administrative Rules, Chapter Env-Or 600 - Contaminated Site Management (Env-Or-600)* and all other applicable federal, state, and local laws, regulations, and bylaws. Specifically, the following methods will be used during excavation, temporary stockpiling, and transportation to centralized stockpile locations off-site, and off-site disposal.

#### **5.1.1 Dust Control**

As needed, the contractor shall employ control measures to minimize airborne particulates during excavation or soil management (e.g. water sprays, mists, etc.). Water used for dust control shall be managed to avoid accumulation of water on the ground surface or within temporary stockpiles.

#### **5.1.2 Materials Management Areas**

Excavated materials may be placed in temporary stockpiles adjacent to excavation areas and reused for backfill as appropriate. Excess excavated material will be transported to a centralized, off-site, materials management area approved by Eversource. Excess wet or saturated soils will be loaded into a 10-mil polyethylene sheeting lined, slurry-tight, roll-off or dump truck and transported to the central materials management area. The Materials Management Areas shall be approved by Eversource and managed in accordance with NHDES Env-Or 611.05(b).

Excavated soils shall be placed on 20-mil polyethylene sheeting and covered with properly secured, 6-mil (minimum) polyethylene sheeting at the end of each work day (or more frequently if rain or wind events present the potential for stockpile erosion, dust blow off, or odor migration). Stockpile sheeting shall be ultraviolet resistant, cold crack resistant to -40 degrees Fahrenheit, and free of holes and foreign matter. Stockpiles shall not contain free liquids. If necessary, erosion control will be installed around stockpiles that will be left overnight or generated during precipitation events.

### **5.2 Soil Classification**

#### **5.2.1 On-Site Reuse**

Excavated material from above the observed groundwater interface should be backfilled within excavations to the extent feasible if the visual/olfactory, chemical, or geotechnical properties of the excavated soil are suitable for reuse.

As soil is excavated, the contractor's Professional Engineer (PE) or Professional Geologist (PG) shall observe and field screen the material for visual or olfactory indications of contamination. If visual or olfactory evidence of contamination is observed, soil will be screened for the presence of VOCs with a photoionization detector (PID) using the jar-headspace method. A minimum of one sample should be screened for visual or olfactory evidence of contamination per foundation element or open length of trench. Soils shall be screened more frequently if visual or olfactory indications of contamination are observed. Soil shall be segregated, if necessary, based on results of field screening and stockpiled for disposal characterization and off-site disposal.

Soil excavated from the saturated zone along the project alignment between Gundalow Landing and the Portsmouth Substation may only be reused as backfill in the saturated zone. Any uncharacterized excess soil from the saturated zone will be stockpiled and characterized for off-site disposal.

## 5.2.2 Characterization for Off-site Reuse, Recycling, or Disposal (if necessary)

Excess soils shall be stockpiled at one or more designated materials management areas to be approved by Eversource as discussed in Section 5.1. The PE or PG will sample and test soil based on the acceptance criteria of the approved receiving facility.

Excess excavated material shall be loaded and transported to an appropriate off-site reuse, recycling or disposal location approved by Eversource. Person(s) transporting the excavated materials shall be licensed and permitted to transport such material in state(s) having jurisdiction. Trailers, dump bodies, or roll-offs used for transport shall have covers to prevent dust blow-off. The Contractor may also use polyethylene liners for transport of materials classified as a hazardous waste if encountered.

The contractor shall prepare disposal documentation and shall provide Eversource with material tracking and disposal records and certifications. Project documentation shall be maintained, including accurate records of material tracking, disposal transportation manifests (e.g., Straight BOL), and if necessary, additional environmental testing required by the receiving location.

## 6. Dewatering

Given the proximity of the project area to Pease and given that the boundaries of the pending GMZ for PFCs from Pease Site 8 have not yet been defined, all groundwater recovered from the alignment will be managed by either of the management options listed below:

- **On-Site Surface Water Discharge:** On-site surface water discharge would require use of a water treatment system, including equipment such as fractionation (frac) tanks and carbon units, to adequately treat groundwater before discharge. It may be possible to discharge dewatering effluent into storm drains or surface water bodies under a NPDES Dewatering General Permit (DGP) with minimal treatment. Additional water testing for NPDES DGP requirements and approval from NHDES, and treatment for, at a minimum, total suspended solids (TSS) would be necessary. If, based on NHDES requirements or NPDES DGP testing results, a NPDES DGP is not appropriate, a NPDES Remediation General Permit (RGP) would likely be required to discharge dewatering effluent. Additional water treatment requirements would also likely apply.
- **Off-Site Disposal:** The contractor shall identify an appropriate off-site groundwater disposal method and facility. Dewatering effluent may be pumped into a tanker truck or other appropriate containers, and transported off-site to the selected facility. All receiving facilities must be pre-approved by Eversource. No excess effluent may be recharged or disposed of at an uncontrolled location.

### Attachments:

Table 1 – Derivation of Soil Screening Levels for PFCs

Figure 1 – Site Location Map

Appendix A – Darius Frink Farm Soil and Water Investigation Report and Soil and Water Management Plan- Updated 12/15/2017

Appendix B – Pease Area of Special Notice Documents

**Table 1. Derivation of Soil Screening Levels for PFCs**  
**Eversource NH Seacoast Reliability Project**  
**Newington, New Hampshire**

**Development of NHDES Direct Contact Risk-Based Concentration (DCRB) for PFOA and PFOS in Soil**



Soil Category	S-3	
Sensitive Receptor	Adult Construction/Excavation Worker	
RSCF	0.2	NHDES = Relative Source Contribution Factor
RfD (mg/kg-day)	2.00E-05	USEPA, 2016
CF (mg/kg)	1.00E+06	conversion factor
IR (mg/day)	480	MADEP uses 100 mg/day and USEPA uses 330 mg/day for CW
RAFo	1	NHDES
RAFd	0.1	NHDES
SA (cm2)	3,104	NHDES; USEPA uses 3,527 cm2 for CW
AF (mg/cm2)	0.2	NHDES; USEPA uses 0.3 mg/cm2 for CW
EF (days per year)	250	12 month project (5 days/week for 350 days in a year)
ED (years)	1	professional judgement
AT (days)	250	averaging period for a subchronic exposure is the subchronic period
BW (kg)	70	NHDES; USEPA uses 80 kg
<b>S-3 DCRB Soil Concentration (mg/kg)=</b>	<b>0.5</b>	

Concentration in Soil (mg/kg) = 
$$\frac{RSCF * RfD * CF}{[(IR * RAFo) + (SA * AF * RAFd)] * [(EF * ED)/(AT * BW)]}$$

Notes:

1. NHDES Soil S-1 = 0.5 mg/kg for PFOA and PFOS
2. NHDES Soil S-2 = 4.3 mg/kg for PFOA and PFOS





Soil and Groundwater Management Plan  
Gundalow Landing to Portsmouth Substation  
Newington and Portsmouth, New Hampshire

Eversource Energy  
Manchester, New Hampshire



Project 1607530

SITE LOCATION MAP

July 2018

Fig. 1

# **Appendix A**

---

**Darius Frink Farm Soil and Water Investigation Report and Soil and Water Management Plan – Updated 12/15/2017**



Consulting  
Engineers and  
Scientists

December 15, 2017  
Project 1607530

VIA EMAIL: [Kurt.Nelson@eversource.com](mailto:Kurt.Nelson@eversource.com)

Mr. Kurt I. Nelson  
Eversource Energy  
13 Legends Way  
Hookset, NH 03106

Dear Mr. Nelson:

Re: **Updated Soil and Water Investigation and Management Plan  
Darius Frink Farm  
Newington, New Hampshire**

GEI Consultants, Inc. (GEI) prepared this letter report to summarize the results of our soil, groundwater, and surface water investigations and to provide recommendations for soil and water management to support Eversource Energy's installation of a new electric transmission line at Darius Frink Farm in Newington, New Hampshire (the Property; Fig. 1). The new transmission line is being installed as part of Eversource Energy's Seacoast Reliability Project (SRP).

The Property consists primarily of farm land and wetlands. Eversource has a Right of Way (ROW) through the Property that is currently used for an above-ground electric distribution line. The current design of the SRP consists of the construction of a new 115 kilovolt (kV) underground transmission line through the Property. These investigations were conducted to develop appropriate soil, groundwater, and surface water management practices to support the construction on the Property.

The Property is located within the downgradient contaminant plume of Site 8 located at Pease Air Force Base (Pease; Fig. 1). Therefore, soil and water management must be performed in accordance with State of New Hampshire Department of Environmental Services (NHDES) regulatory requirements. NHDES does not provide specific guidance for utility related work; therefore, the process for investigation, cleanup, and reporting for this project was performed in general accordance with *The New Hampshire Code of Administrative Rules, Chapter Env-Or 600 - Contaminated Site Management* (Env-Or-600). Our recommendations for soil and water management are in Appendix A.

Our scope of work included the following tasks:

- Reviewing project information provided by Eversource.
- Advancing three borings on the Property which were completed as monitoring wells.
- Collecting soil, groundwater, and surface water samples for laboratory analytical testing.
- Performing hydraulic conductivity testing.
- Developing recommendations for management of soil and water generated during construction.
- Preparing a Soil and Water Management Plan for the Property.

## 1. Summary & Findings

GEI's investigation indicated the following:

- Perfluorinated compounds (PFCs) were not present in the soil tested.
- PFC concentrations in groundwater, where encountered, were less than New Hampshire state ambient groundwater quality standards (AGQS) of 0.07 µg/L.
- PFC concentrations in surface water from Knight's Brook tributary exceeded the NH AGQS of 0.07 µg/L.
- Soils at the Property are primarily silts underlain by clay. Based on hydraulic conductivity testing, the estimated dewatering rates for the trench range from approximately 45 to 1,500 gallons per day.
- Where the SRP crosses the Knight's Brook Tributary, the conduit will be installed in the low permeability silts and clays. Since the conduit will be installed within a relatively narrow band within the subsurface zone, we do not expect that the SRP will impact the current existing conditions.
- Under current high-water conditions, the Knights Brook Tributary overtops its banks and floods adjacent wetlands indicating that PFOA and PFOS contaminated surface water may be impacting the soils currently. Though soils and groundwater within the wetland adjacent to the Knights Brook Tributary were not tested, at the nearby upland soil boring location, B101MW, PFOA and PFOS were not detected in soils, and PFOA and PFOS concentrations in groundwater, when encountered at this location, were less than New Hampshire AGQS of 0.07 ug/L.

### 1.1. Soil, Groundwater, & Surface Water Management

Based on the results of our investigation, GEI recommends the following for soil, groundwater, and surface water management:

- **Soil:** All excess soil will be disposed of offsite at a licensed disposal facility or reused offsite in accordance with applicable reuse regulations and guidelines.
- **Groundwater:** If dewatering is necessary, groundwater will be treated and discharged to Knight's Brook Tributary under a National Pollutant Discharge Elimination System (NPDES) Remediation General Permit or will be transported offsite for disposal.
- **Surface Water:** Surface water will be diverted during construction in a manner that does not produce excess water or require additional water management, treatment, or offsite disposal.

The proposed alignment including station locations are shown on Fig. 2 and the Soil and Water Management Plan for Darius Drink Farm is in Appendix A.

## 2. Background

### 2.1. Site Description

Eversource proposes to pass the SRP through an existing overhead transmission line corridor on the Darius Frink Farm, located to the north of Pease in Newington, NH (Fig. 1). Darius Frink Farm consists of several buildings, a cultivated vegetable garden, a cow pasture, and uncultivated fields. The work will be performed within an uncultivated field, which is currently maintained for haying operations (the Project Area; Fig. 2). The Project Area is approximately 1,600 feet long and begins at the riser structure on the western edge of the property and ends at Nimble Hill Road (Fig. 2). The proposed trench in the Project Area will be approximately 5-foot-wide and up to 6.5-foot-deep (Fig. 3A).



## **2.2. Regulatory History**

There have been no releases of oil or hazardous material (OHM) reported at the Property, which has been owned by the Frink family for five generations. However, the Property and Project Area are located downgradient of the Pease Site 8 contaminated groundwater plume which contains PFCs associated with former firefighting activities. Since the portion of the SRP in the Project Area will be underground, there is potential to encounter contaminated soil and groundwater during construction activities. PFCs have also been detected in surface water in Knight's Brook Tributary along the western edge of the Project Area and within the proposed SRP alignment.

In May 2016, NHDES enacted Emergency Rule 05-31-16 under Env-Or-600 which includes the addition of PFCs to the New Hampshire AGQS. The AGQS for perfluorooctanoic acid (PFOA), perfluorooctane sulfonate (PFOS), and the combined concentration of PFOA and PFOS is 0.07 µg/L. Env-Or-600 does not currently include soil standards or regulations for PFOA or PFOS.

## **2.3. Chemicals of Concern**

PFOA and PFOS are the primary contaminants of concern in the Project Area. PFOA and PFOS are PFCs and part of a group of man-made chemicals that have been used to manufacture a large range of products including nonstick cookware, carpets, some food packaging, paints, cleaning products, and firefighting foams. PFCs are very persistent in the environment, and are known to travel long distances in groundwater.

PFOA and PFOS contamination has been previously identified downgradient of Pease Site 8 in surface water in local streams (e.g. Knight's Brook tributary, Knights Brook, and Pickering Brook; Fig. 1). The presence of PFOA and PFOS downgradient of Site 8 has been associated with the historic use of aqueous film forming foam (AFFF) at Site 8 at Pease. Around 1970, the US Air Force began using aqueous AFFF for extinguishing petroleum fires during firefighting training activities at the current Site 8 location. Site 8 was used to simulate aircraft crash fires in a pit area using jet fuel, mixed waste oils, and solvents. The mixture was burned before being extinguished with AFFF. Excess fuels and AFFF were discharged from the burn pit into a drainage ditch at the northern end of Site 8.

Prior to this investigation, there was limited information on the presence of PFOA or PFOS at the Property or in the Project Area. The results of our investigation are summarized below and our recommendations for managing soil and water are presented in Appendix A.

## **3. Site Characterization**

In August and September 2016 and April and June 2017, GEI performed an investigation to characterize soil groundwater, and surface water within the Project Area to assess conditions that may be encountered during construction activities. GEI performed soil borings, sampled soil, installed monitoring wells, sampled groundwater, performed hydraulic conductivity tests, and sampled surface water. During sampling, we took special precautions to prevent potential PFC cross-contamination from outside sources including:

- No use of Teflon®-containing materials (i.e. Teflon® tubing, bailers, tape, plumbing paste);
- No Tyvek® clothing was worn;
- Clothes treated with stain- or rain-resistant coatings were avoided or had gone through several washings; no PostIt® Notes were handled or brought on site;
- No fast food wrappers, disposable cups or microwave popcorn were brought on site during sampling;
- Hands were washed after handling such items and prior to any sampling activities;

- No use of chemical (blue) ice packs was allowed; and
- Nitrile gloves were worn during all sample collection activities.

### **3.1. Soil Boring Advancement and Monitoring Well Installation – August 2016**

On August 26, 2016, GEI observed DrillEx Environmental (DrillEx) of West Boylston, Massachusetts advance three borings and install three groundwater monitoring wells (B101[MW], B102[MW], and B103[MW]) to evaluate environmental site conditions in the Project Area. Borings were advanced to approximately 8 feet below grade, which is approximately 1.5 feet below the bottom of the proposed trench depth, using hollow stem augers with continuous split spoon sampling. Boring locations are shown on Fig. 2. Boring and monitoring well installation logs are included in Appendix B.

GEI collected two soil samples from each boring consisting of composite samples from the 0 to 4-foot interval and the 4 to 8-foot interval (B101[S1-S2], B101[S3-S4], B102 [S1-S2], B102 [S3-S4], B103[S1-S2], B103[S3-S4]). GEI submitted the soil samples to Alpha Analytical, Inc. (Alpha) of Westborough, Massachusetts to be tested for PFOA, PFOS, and offsite disposal characterization parameters including: volatile organic compounds (VOCs), semi-volatile organic compounds (SVOCs), total petroleum hydrocarbons (TPH), polychlorinated biphenyls (PCBs), RCRA 8 Metals (arsenic, barium, cadmium, chromium (total), lead, mercury, selenium, silver), conductivity, corrosivity, ignitability, and reactivity (cyanide and sulfide). Soil chemical testing results are summarized in Table 1 and the laboratory data report is in Appendix C.

Based on conditions we observed during our subsurface investigation, the shallow subsurface in the Project Area generally consists of silt underlain by clay. The soils encountered during our subsurface investigation are described below, starting at the ground surface. The soil conditions are known only at the boring locations. Conditions between borings may differ significantly from those described below.

- Silt: A sandy silt with mostly non-plastic fines, composes the upper layer of the soil profile.
- Clay: A lean and sandy clay with low plasticity fines.
- Gravel (in B103[MW] only): Widely graded gravel with silt and sand.

### **3.2. Hand Auger Borings – April 2017**

On April 7, 2017, GEI advanced two shallow borings (HA1 and HA2) in the vicinity of Knight's Brook tributary to assess soil stratigraphy in the proposed trench alignment. The purpose of the April 2017 investigation was to assess the depth of clay and the potential for encountering artesian conditions during trench installation. Borings HA1 and HA2 were advanced to 6.5 feet and 6 feet, respectively and consistent with the proposed trench depth. The borings were sampled continuously using hand auger techniques. Soil samples were not collected for analytical testing because the soil collection method (e.g. hand augers) could result in soil samples being exposed to the contaminated surface water column during extraction. This scenario could potentially result in a false positive for PFCs and not be representative of existing conditions. Surface water sampling and testing results are discussed in Sections 3.3 and 4.2, respectively. Boring locations are shown on Fig. 2. Boring logs are included in Appendix B.

Based on the conditions we observed, the shallow subsurface in the Knight's Brook tributary area generally consists of sandy silt underlain by clay. The soils encountered during our subsurface investigation are described below, starting at the ground surface. The soil conditions are known only at the boring locations. Conditions between borings may differ significantly from those described below.

- Organic Soil: A layer of organic soil composed of low plasticity fines and organic matter at the surface.

- Sandy Silt: A sandy silt with mostly non-plastic fines, composes the upper layer of the soil profile.
- Clay: A lean and sandy clay with low plasticity fines.

We prepared a cross-section of the Knight's Brook tributary based on and interpolated from the information collected from the hand augers and previous investigations by GEI and others. Based on the available boring information, the general subsurface conditions appear to be consistent between F107-109 and GEI-101 with silty sands overlying clay layer. Boring logs are included in Appendix B and the cross-section is shown on Fig. 3A.

### **3.3. Groundwater & Surface Water Sampling – 2016**

On August 29, 2016, GEI developed monitoring wells B101(MW) and B102(MW). Groundwater was measured at 4.79 feet and 3.77 feet in B101(MW) and in B102(MW), respectively. B103(MW) was not developed because the well was dry. GEI developed the wells by surging and removing water using a dedicated Watera® check valve and tubing. A well was considered developed when either:

- 10-well volumes were removed; or
- Water removed from the well was relatively free of fine-grained material; or
- The well ran dry.

Wells B101(MW) and B102 (MW) ran dry after removing approximately 2.25 gallons and 6 gallons, respectively.

On September 1, 2016, GEI returned to the Property to collect groundwater samples from B101(MW) and B102(MW) using low-flow methods. Groundwater was not detected in B103(MW); therefore, a groundwater sample was not collected. GEI used peristaltic pumps for low flow purging. Dedicated tubing was lowered to the mid-point of the saturated screen interval and a water level was used to periodically measure the water level in the well during purging. Purge rates were adjusted to minimize drawdown to the extent feasible. During low flow purging a YSI Sonde 6200 was used to measure temperature, pH, specific conductivity, dissolved oxygen, oxidation reduction potential, and turbidity. GEI collected a groundwater sample from the well when each of the parameters was stable for a minimum of three consecutive readings. Additionally, we collected a surface water sample (SW1) from Knight's Brook Tributary. Groundwater and surface water samples were submitted to Alpha to be tested for PFOA and PFOS.

Groundwater and surface water chemical testing results are summarized in Table 2 and the laboratory data report is in Appendix C. Groundwater measurements observed during each visit are included in Table 3.

### **3.4. Groundwater Sampling – 2017**

On April 7, 2017, GEI returned to the property to gauge wells during spring conditions. At that time, we observed the field was flooded due to spring melt and heavy rains. As a result, groundwater levels in all three wells (B101[MW], B102[MW], and B103[MW]) was at approximately the ground surface. Due to these flooding conditions groundwater sampling was not performed.

On June 2, 2017 GEI returned to the property to collect groundwater level information and samples from the three monitoring wells under normalized spring conditions. During this groundwater sampling event water was detected in all three wells and groundwater samples were collected from each using the methods described in Section 3.3. Groundwater was measured at 0.83 feet, 1.12 feet, and 2.31 feet in B101(MW), B102(MW), and B103(MW), respectively. Groundwater and surface water samples were submitted to Alpha to be tested for PFOA and PFOS.

Groundwater and surface water chemical testing results are summarized in Table 2 and the laboratory data report is in Appendix C. Groundwater measurements observed during each visit are included in Table 3.

### **3.5. Hydraulic Conductivity Testing**

On September 15, 2016, GEI conducted rising head well permeability tests on B101(MW) and B102(MW). The tests were performed using dedicated In-Situ Level TROLL 700 data loggers. Prior to starting the test, GEI collected water level and total depth readings from the wells. Groundwater was measured at 4.92 feet and 4.39 in B101(MW) and B102(MW), respectively. Groundwater was not detected in B103(MW). The data loggers were then placed near the bottom of each well and a peristaltic pump was used to draw down the water level. The water was then allowed to recharge to approximately the pre-purge level while the data loggers recorded the rebound in water level. GEI collected manual water level measurements throughout the duration of each test in order to perform quality control checks on the TROLL readings. We performed two tests on B101(MW) and three tests on B102(MW). B103(MW) was not tested because it was dry. Groundwater measurements observed during each visit are included in Table 3. The hydraulic conductivity testing results are summarized in Table 4.

## **4. Results**

### **4.1. Soil Analytical Results**

Soil samples did not contain detectable levels of PFOA, PFOS, VOCs, SVOCs, or PCBs. Soil chemical testing results indicated that presence of the following compounds above the laboratory detection limits:

- TPH
- Metals: arsenic, barium, chromium and lead.

TPH was detected above laboratory detection limit in samples B101(S1-S2); however, the concentration was well below the NHDES Method 1 Soil Standard (NH S-1). Barium, chromium, and lead were detected in all the soil samples at concentrations less than NH S-1. Arsenic was detected in B102(S1-S2) and B102(S3-S4) at 12 milligrams per kilogram (mg/kg). This is slightly above the NH S-1 standard and the NHDES Background Concentration of 11 mg/kg but is still likely attributable to background conditions at the Property. Soil testing results are summarized in Table 1 and the laboratory data report is in Appendix C.

### **4.2. Groundwater & Surface Water Analytical Results**

Groundwater and surface water testing results indicated the following:

- PFOA and PFOS were not detected in B101(MW) in September 2016. PFOA and PFOS were detected in B101(MW) in June 2017 but at concentrations below the NH AGQS of 0.07 µg/L.
- PFOA and PFOS were detected in B102(MW) in both September 2016 and June 2017 but at concentrations below the NH AGQS of 0.07 µg/L.
- PFOA was not detected in B103(MW). PFOS was detected in B103(MW) but at concentrations below the NH AGQS of 0.07 µg/L.
- PFOA and PFOS were detected in sample SW1 from Knight's Brook at 0.842 µg/L and 2.91 µg/L, respectively. The total PFOA/PFOS concentration was 3.752 µg/L. Both the individual and total concentrations exceed the NH AGQS of 0.07 µg/L.

- PFOA and PFOS were not detected in a field blank sample collected during the June 2017 groundwater sampling event.

Groundwater and surface water testing results are summarized in Table 2 and the laboratory data report is in Appendix C.

#### **4.3. Hydraulic Conductivity**

Based on the testing results, we estimated the following average hydraulic conductivities:

- B101(MW) has an average hydraulic conductivity of 0.062 feet/day which is likely due to the silt and clay observed during installation of the well.
- B102(MW) has an average hydraulic conductivity of 0.222 feet/day which is likely due to the sand seam observed within the well screen interval. The sand seam was observed in the boring at approximately 5 feet below the ground surface.
- B103(MW) hydraulic conductivity was not calculated because the well was dry at the time of testing.

The hydraulic conductivity testing results are summarized in Table 4.

#### **4.4. Groundwater Model & Dewatering Estimate**

GEI calculated the expected dewatering rates of groundwater within the proposed trench alignment for both low and high groundwater conditions, as experienced in the fall of 2016 and spring of 2017, respectively. Based on our calculations, we estimate dewatering may range from 45 to 1,500 gallons per day (gpd) depending on the location of the excavation and groundwater levels. Our calculations are based on the limited geologic information observed during installation of B101(MW), B102(MW), and B103(MW). The estimated dewatering rates are as follows:

- Near B101(MW): Approximately 45 to 82 gpd during a low water condition and approximately 486 to 770 gpd during a high groundwater condition.
- Near B102(MW): Approximately 104 to 187 gpd during a low groundwater condition and approximately 942 to 1466 gpd during a high groundwater condition.
- Near B103: Based on the soil encountered in B103(MW), we estimate the dewatering rates near B103(MW) will likely be between the estimated ranges for B101(MW) and B102(MW). The trench near B103(MW) may also be dry if construction takes place during low groundwater conditions similar August and September of 2017.

The groundwater flow model and dewatering estimate is in Appendix D.

GEI has additionally evaluated the potential for changes in groundwater flow patterns and the potential for damming of surface water or groundwater due to the installation of the new conduit duct bank. The duct bank measures approximately 2-feet 6-inches tall by 3-feet 5-inches wide and consists of several polyvinyl chloride (PVC) and high-density polyethylene (HDPE) conduits encased in concrete. The top of the duct bank will be approximately 2.5-feet below grade and topped with fluidized thermal backfill west of Station 499+50 and 4-feet below grade and topped with native soils in the agricultural area east of Station 499+50. The soil boring data indicate that the duct bank will be located within shallow soils in a stratum consisting primarily of low permeability clays and silts. Given that the duct bank will occupy a relatively narrow band area in low permeability material, it should not impede the flow of groundwater.

With respect to surface water flows, the top of the proposed duct bank will be buried approximately 2.5' below the bottom of the tributary; therefore, surface water flow will not be impacted by the duct

bank. The Knight's Brook Tributary is spring fed and the general subsurface conditions observed consist of a sandy bottom underlain by silt and clay. The presence of this type of subsurface stratification indicates that there is likely minimal contribution from groundwater to surface water flow other than from the source spring(s). It is our opinion that that contamination present in surface water is a result of the springs that feed the Knight's Brook Tributary and not from impacted groundwater in adjacent shallow soils. Eversource understands, and has observed, that under current conditions the Knights Brook Tributary overtops its banks and floods the adjacent wetlands under high water conditions indicating that PFOA and PFOS contaminated surface water may be impacting the Property currently. However, based on the results of the subsurface investigation performed by GEI and presented in the Soil and Water Investigation and Management Plan for Darius Frink Farm:

- Though soils and groundwater within the wetland adjacent to the Knights Brook Tributary were not tested, at the nearby upland soil boring location, B101MW, PFOA and PFOS were not detected in soils, and PFOA and PFOS concentrations in groundwater, when encountered at this location, were less than New Hampshire AGQS of 0.07 ug/L.

## 5. Construction Worker Screening Levels

General screening levels for construction worker exposure to PFOA and PFOS in soil and groundwater are not available. Based on information from the United States Environmental Protection Agency (USEPA) and New Hampshire Environmental Health Program (EHP) we have derived the following construction work screening levels for this project, where applicable:

### 5.1. Soil

GEI derived a human health risk-based screening level (SL) for a construction worker exposure to PFOA and PFOS in soil based on the New Hampshire Environmental Health Program (EHP) and NHDES methodology applied to derive a Direct Contact Risk-Based (DCRB) soil concentration for PFOA and PFOS in soil. Exposure assumptions used to derive these soil SLs were similar to NHDES Soil Category S-3 exposures considered protective of adult exposures to soil during short but intense exposures, such as during excavation work. These risk-based soil SLs account for exposure to impacted soil as a result of incidental ingestion and dermal contact during excavation work. Table 5 presents the soil SL derived for both PFOA and PFOS of 0.5 mg/kg.

The adult construction worker was assumed to be exposed to outdoor soil a total of 250 days a year. This assumption was based on an excavation worker exposed to soil 5 days per week for a 1-year excavation project (assumes 350 total days of excavation) and assuming a worker takes 2 weeks of vacation in a year. Based on NHDES guidance, the adult excavation worker was assumed to ingest 480 mg of soil per day of intense excavation work. Also based on NHDES guidance, a soil adherence factor equal to 0.2 mg/cm<sup>2</sup> was assumed and an exposed skin surface area of 3,104 cm<sup>2</sup> was assumed, which includes hands, forearms, face and neck. Additional exposure parameters based on NHDES guidance are presented in Table 5. USEPA applies different exposure assumptions for the construction worker exposure scenario in the derivation of Regional Screening Levels (RSLs) for soil. Based on USEPA exposure assumptions for the construction worker, which are noted in Table 5, a slightly higher Construction Worker Soil Screening Level for PFOA and PFOS of 0.7 mg/kg could be derived.

The USEPA derived a chronic Reference Dose (RfD) to evaluate non-cancer effects for PFOA and PFOS of  $2 \times 10^{-5}$  mg/kg-day, based on developmental effects. USEPA also derived a Cancer Slope Factor (CSF) for PFOA of 0.07 (mg/kg-day)<sup>-1</sup>; however, according to USEPA, the non-cancer developmental endpoint for PFOA represented by the RfD is protective of the cancer endpoint. In addition, because the critical effect identified for PFOA and PFOS is a developmental endpoint and can potentially result from a short-term exposure during a critical period of development, USEPA concludes that the chronic RfD is applicable to both short-term and chronic risk assessment scenarios.

Therefore, it is appropriate to use the chronic RfD of  $2 \times 10^{-5}$  mg/kg-day derived for both PFOA and PFOS to estimate short-term or subchronic risk-based SLs for a construction worker.

## 5.2. Water

USEPA derived a drinking water Health Advisory (HA) and NHDES derived the AGQS for PFOA and PFOS of 0.07 µg/L. This HA is considered protective of lifetime exposures to PFOA and PFOS from residential ingestion of drinking water. This HA does not consider potential exposure to PFOA and PFOS as a result of dermal exposure or inhalation exposure. However, USEPA notes that neither PFOA nor PFOS are volatile and are therefore not expected to be present in air except if bound to particulate matter. According to USEPA's Health Effects Support Document for PFOA (May 2016), there is evidence that PFOA is absorbed following dermal exposure. The EPA document presents a permeability coefficient for PFOA of  $9.49 \times 10^{-7}$  cm/hour for human skin. USEPA risk based equations for deriving RSLs (May 2016) for dermal exposure to water were used to derive the Construction Worker Water Screening Level for PFOA and PFOS of 1,000 µg/Liter.

## 6. Soil and Water Management

Since the work is being performed in the downgradient plume of Site 8, proper procedures for on-site management and off-site disposal of soil and groundwater are necessary to reduce the potential for exposure to PFOA and PFOS and be protective of workers and the public. GEI prepared a Soil and Water Management Plan that presents the requirements and procedures to be undertaken by Eversource personnel or hired contractors that excavate soil or manage soil, groundwater, or surface water during installation of a new overhead or underground electric transmission line at Darius Frink Farm. The Soil and Water Management Plan is in Appendix A.

Based on the results of our investigation, GEI recommends the following for soil, groundwater, and surface water management:

- **Soil:** All excess soil will be disposed of offsite at a licensed disposal facility or reused offsite in accordance with applicable state and federal regulations.
- **Groundwater:** If dewatering is necessary, groundwater will be managed by one or more of the following methods:
  - Groundwater may be treated and discharged to Knight's Brook Tributary under a National Pollutant Discharge Elimination System (NPDES) Remediation General Permit
  - Groundwater may be temporarily stored onsite in a fractionation (frac) tank and then pumped and transported offsite for disposal.
  - Groundwater may be directly pumped from the excavation into a vacuum truck for offsite disposal.
- **Surface Water:** Surface water will be diverted during construction in a manner that does not produce excess water or require additional water management, treatment, or offsite disposal.


## 7. Limitations

This report was prepared for the exclusive use of Eversource Energy. The conclusions provided by GEI in this report are based on the information contained in this report. Additional information not available to GEI at the time this report was prepared may result in a modification of our conclusions. This report has been prepared in accordance with generally accepted engineering and geohydrological practices. No warranty, express or implied, is made.


Please contact Jim Ash at [JAsh@geiconsultants.com](mailto:JAsh@geiconsultants.com) or 781-721-4018 or Mike Sabulis at [MSabulis@geiconsultants.com](mailto:MSabulis@geiconsultants.com) or 781-721-4114 if you have any questions.

Sincerely,

GEI CONSULTANTS, INC.



James R. Ash, P.E., LSP  
Senior Vice President



Michael W. Sabulis  
Project Manager

CRC/MWS/JRA:jam

Attachments:

- Table 1 – Laboratory Testing Results – Soil
- Table 2 – Laboratory Testing Results – Groundwater and Surface Water
- Table 3 – Water Level Measurements
- Table 4 – Hydraulic Conductivity Test Results
- Table 5 – Derivation of Soil Screening Levels
- Fig. 1 – Site Location Map
- Fig. 2 – Project Area Plan
- Fig. 3A – Cross Section – Knight’s Brook Tributary
- Appendix A – Soil and Water Management Plan
- Appendix B – Boring and Monitoring Well Installation Logs
- Appendix C – Laboratory Test Reports
- Appendix D – Groundwater Model Description



# Tables

---

**Table 1. Laboratory Testing Results - Soil**  
**Darius Frink Farm**  
**Eversource NH Seacoast Reliability Project**  
**Newington, New Hampshire**

Analyte	Method	Units	NH S-1	NHDES Background	B101		B102		B103	
					S1-S2	S3-S4	S1-S2	S3-S4	S1-S2	S3-S4
					0-4	4-8	0-4	4-6.8	0-4	4-8
					8/26/2016	8/26/2016	8/26/2016	8/26/2016	8/26/2016	8/26/2016
<b>Perfluorinated Compounds (PFCs)</b>	537	ng/g								
Perfluorooctanoic Acid (PFOA)			NS	NS	< 1.96	< 1.96	< 1.95	< 1.95	< 1.93	< 2.02
Perfluorooctane Sulfonate (PFOS)			NS	NS	< 1.96	< 1.96	< 1.95	< 1.95	< 1.93	< 2.02
<b>Volatile Organic Compounds (VOCs)</b>	8260C	mg/kg								
Total VOCs			NS	NS	ND	ND	ND	ND	ND	ND
<b>Semi-Volatile Organic Compounds (SVOCs)</b>	8270D	mg/kg								
Total SVOCs			NS	NS	ND	ND	ND	ND	ND	ND
<b>Total Petroleum Hydrocarbons (TPH)</b>	8015	mg/kg								
Total Petroleum Hydrocarbons			10000	NS	39.0	< 39.8	< 39.5	< 39.9	< 35.5	< 34.1
<b>Polychlorinated Biphenyls (PCBs)</b>	8082A	mg/kg								
Total PCBs			1	NS	ND	ND	ND	ND	ND	ND
<b>Total Metals</b>		mg/kg								
Arsenic	6010C		11	11	7.4	5.6	<b>12</b>	<b>12</b>	9.0	7.1
Barium	6010C		1,000	NS	28	33	44	31	30	18
Cadmium	6010C		33	2	< 0.47	< 0.48	< 0.47	< 0.49	< 0.42	< 0.42
Chromium (Total)	6010C		1,000	33	14 F-,G	16 F-,G	19 F-,G	18 F-,G	30 F-,G	26 F-,G
Lead	6010C		400	51	5.7 F-	4.6 F-	6.8 F-	8.9 F-	7.2 F-	8.6 F-
Mercury	7471B		7	0.3	< 0.08	< 0.08	< 0.08	< 0.08	< 0.07	< 0.07
Selenium	6010C		180	5	< 0.94	< 0.96	< 0.94	< 0.98	< 0.85	< 0.84
Silver	6010C		89	NS	< 0.47	< 0.48	< 0.47	< 0.49	< 0.42	< 0.42
<b>Other</b>										
Conductivity	EPA 120.1M	umhos/cm	NS	NS	< 10	< 10	< 10	28 G	< 10	44 G
Corrosivity (pH)	9045D	S.U.	NS	NS	6.2 A	6.4 A	6.3 A	7.4 A	5.7 A	0.3
Oxidation-Reduction Potential	ASTM D1498-76M	mv	NS	NS	180 A	170 A	170 A	190 A	170 A	150 A
Flashpoint	1030	deg F	NS	NS	NI	NI	NI	NI	NI	NI
Reactive Cyanide	CHAP7	mg/kg	NS	NS	< 10	< 10	< 10	< 10	< 10	< 10
Reactive Sulfide	CHAP7	mg/kg	NS	NS	< 10	< 10	< 10	< 10	< 10	< 10
Percent Solids	SM 2540G-97 MOD	%	NS	NS	84.2	80.9	83.6	79.2	93.3	92.4

**General Notes**

- In general, analytes detected in at least one sample are reported here. For a complete list of analytes see the laboratory data sheets.
- "<" = The analyte was not detected at a concentration above the specified laboratory reporting limit.
- NH S-1 and NHDES Background standards from The New Hampshire Code of Administrative Rules, Chapter Env-Or 600 - Contaminated Site Management.
- Values in bold exceed the NH S-1 and/or NDHES Background values.
- NS = No standard or criteria has been established for this analyte.
- NI = Not Ignitable
- ND = Not detected.
- Soil samples for VOC analysis were preserved in the field with methanol.
- mg/kg = milligrams per kilogram.
- umhos/cm = micromhos per centimeter.
- S.U. = standard units.
- mv = millivolts.
- deg F = degrees Fahrenheit.
- ng/g = nanograms per gram.

**Qualifying Notes**

- A The result is estimated due to exceedance of holding time criteria.
- F- The result has a low bias due to matrix spike recovery below lower control limits.
- G The result is estimated due to duplicate precision outside control limits.

**Table 2. Laboratory Testing Results - Groundwater and Surface Water**  
**Darius Frink Farm**  
**Eversource NH Seacoast Reliability Project**  
**Newington, New Hampshire**

				Sample Location:		1607530-B101(MW)		1607530-B102(MW)		1607530-B103(MW)	1607530-SW1
				Sample Date:	Screen Interval:	9/1/2016	6/2/2017	9/1/2016	6/2/2017	6/2/2017	9/1/2016
				2-8'	2-8'	2-7'	2-7'	2-8'	NA		
Analyte	Method	Units	NH AGQS								
<b>Perfluorinated Compounds (PFCs)</b>				537	ug/L						
Perfluorooctanoic Acid (PFOA)			0.07	< 0.00786	0.00248	0.0112	0.00711	< 0.00185	<b>0.842</b>		
Perfluorooctane Sulfanate (PFOS)			0.07	< 0.00786	0.00305	0.0161	0.0142	0.00187	<b>2.91</b>		
Total PFCs			0.07	ND	0.00553	0.0273	0.02131	0.00187	<b>3.752</b>		

**General Notes:**

1. In general, analytes detected in at least one sample are reported here. For a complete list of analytes see the laboratory data sheets.
2. "<" = The analyte was not detected at a concentration above the specified laboratory reporting limit.
3. NH AGQS = New Hampshire Ambient Groundwater Quality Standards
4. NH AGQS for PFOA and PFOS from Emergency Rule 05-31-16 to Amend The New Hampshire Code of Administrative Rules Env-OR 603.03(b), eff 6-1-15
5. Values in bold exceed the NH AGQS values.
6. ND = Not detected.
7. ug/L = milligrams per liter.

**Table 3. Water Level Measurements**  
**Darisu Frink Farm**  
**Eversource NH Seacoast Reliability Project**  
**Newington, New Hampshire**

Well ID	August 26, 2016		August 29, 2016		September 1, 2016		September 15, 2016		April 7, 2017		June 2, 2017	
	Depth to GW from Top of PVC (ft)	Depth to GW from Ground Surface (ft)	Depth to GW from Top of PVC (ft)	Depth to GW from Ground Surface (ft)	Depth to GW from Top of PVC (ft)	Depth to GW from Ground Surface (ft)	Depth to GW from Top of PVC (ft)	Depth to GW from Ground Surface (ft)	Depth to GW from Top of PVC (ft)	Depth to GW from Ground Surface (ft)	Depth to GW from Top of PVC (ft)	Depth to GW from Ground Surface (ft)
MW101	ND	ND	7.91	4.79	7.79	4.67	8.04	4.92	3.41	0.29	3.95	0.83
MW102	7.29	4.39	6.67	3.77	6.79	3.89	7.18	4.28	3.61	0.71	4.02	1.12
MW103	NM	NM	ND	ND	ND	ND	ND	ND	At ground surface		2.11	2.31

Notes:

1. ft = feet
2. GW = groundwater
3. NM = Not measured
4. ND = Not detected

**Table 4. Hydraulic Conductivity Test Results - Rising Head Test**  
**Darius Frink Farm**  
**Eversource NH Seacoast Reliability Project**  
**Newington, New Hampshire**

Well ID	Hydraulic Conductivity (ft/day)			
	Test 1	Test 2	Test 3	Average
B101(MW)	0.08	0.05	NA	0.062
B102(MW)	0.23	0.22	0.22	0.222
B103(MW)	NT	NT	NT	

Notes:

1. NA = Not applicable
2. NT = Not tested due to dry well
3. ft = feet

**Table 5. Derivation of Soil Screening Levels for PFCs**

Darius Frink Farm  
 Eversource NH Seacoast Reliability Project  
 Newington, New Hampshire

**Development of NHDES Direct Contact Risk-Based Concentration (DCRB) for PFOA and PFOS in Soil**

Soil Category	S-3	
Sensitive Receptor	Adult Construction/Excavation Worker	
RSCF	0.2	NHDES = Relative Source Contribution Factor
RfD (mg/kg-day)	2.00E-05	USEPA, 2016
CF (mg/kg)	1.00E+06	conversion factor
IR (mg/day)	480	MADEP uses 100 mg/day and USEPA uses 330 mg/day for CW
RAFo	1	NHDES
RAFd	0.1	NHDES
SA (cm2)	3,104	NHDES; USEPA uses 3,527 cm2 for CW
AF (mg/cm2)	0.2	NHDES; USEPA uses 0.3 mg/cm2 for CW
EF (days per year)	250	12 month project (5 days/week for 350 days in a year)
ED (years)	1	professional judgement
AT (days)	250	averaging period for a subchronic exposure is the subchronic period
BW (kg)	70	NHDES; USEPA uses 80 kg
<b>S-3 DCRB Soil Concentration (mg/kg)=</b>	<b>0.5</b>	

Concentration in Soil (mg/kg) =


$$\frac{RSCF * RfD * CF}{[(IR * RAFo) + (SA * AF * RAFd)] * [(EF * ED)/(AT * BW)]}$$

Notes:

1. NHDES Soil S-1 = 0.5 mg/kg for PFOA and PFOS
2. NHDES Soil S-2 = 4.3 mg/kg for PFOA and PFOS

# Figures

---



This Image from U.S.G.S. Topographic 7.5 Minute Series  
 Portsmouth, NH - ME Quadrangle, 1981.  
 Datum is National Geodetic Vertical Datum of 1929 (NGVD29).  
 Contour Interval is 20 Feet.



QUADRANGLE LOCATION

Soil and Water Management Plan  
 Darius Frink Farm  
 Newington, New Hampshire  
 Eversource Energy  
 Manchester, New Hampshire




SITE LOCATION MAP

Project 1607530



December 2017


Fig. 1






**LEGEND:**

-  MONITORING WELL INSTALLED BY GEI IN AUGUST 2016
-  SURFACE WATER SAMPLE COLLECTED BY GEI IN SEPTEMBER 2016
-  HAND AUGER BY GEI IN APRIL 2017
-  BORING BY TERRACON IN SEPTEMBER 2016

498+00  
 TRENCH ALIGNMENT AND STATION

**NOTES:**

1. LOCATIONS ARE APPROXIMATE.



Soil and Water Investigation  
 Darius Frink Farm  
 Newington, New Hampshire

Eversource  
 Manchester, New Hampshire




Project 1607530

PROJECT AREA PLAN

December 2017

Fig. 2






**LEGEND:**

--- INTERPOLATED STRATA BOUNDARIES

**NOTES:**

- EXISTING GRADE AND DUCTBANK PROFILE FROM POWER ENGINEERS DRAWINGS, RECEIVED SEPTEMBER 2017.
- ELEVATION APPROXIMATED FROM PROJECT PLANS, CIVIL DRAWINGS.
- TERRACON BORING ELEVATIONS AND SOIL PROFILE FROM TERRACON BORING LOG.




Soil and Water Investigation Darius Frink Farm Newington, New Hampshire Eversource Manchester, New Hampshire	 <b>GEI</b> Consultants	CROSS SECTION - KNIGHT'S BROOK TRIBUTARY	
		Project 1607530	December 2017

Fig. 3A

# **Appendix A**

---

## **Soil and Water Management Plan**

# SOIL AND WATER MANAGEMENT PLAN

## Eversource Seacoast Reliability Project Darius Frink Farm Newington, New Hampshire

### 1. Introduction

This document presents the requirements and procedures to be undertaken by Eversource personnel or hired contractors that excavate soil or manage soil, groundwater, or surface water during installation of a new underground electric transmission line at Darius Frink Farm in Newington, New Hampshire (the Property; Fig. 1). The new transmission line is being installed as part of Eversource's Seacoast Reliability Project (SRP). The new transmission line will be installed in Eversource's Right of Way (ROW) through the Property (the Project Area; Fig. 1) that is currently used for above-ground electric lines and towers. The Project Area is approximately 1,600 feet long and begins at the riser structure on the western edge of the property (Station 496+80) and ends at Nimble Hill Road (Station 511+00) (Fig. 2). This Soil and Water Management Plan is applicable only to the Project Area shown on the plan, not the entire Property.

### 2. Background and Regulatory History

There have been no releases of oil or hazardous material (OHM) reported at the Property, which has been owned by the Frink family for five generations. However, the Property and Project Area are located downgradient of the Pease Site 8 contaminated groundwater plume which contains perfluorinated compounds (PFCs) associated with former firefighting activities. Since the portion of the SRP in the Project Area will be underground, there is potential to encounter contaminated soil and groundwater during construction activities. Additionally, PFCs have been detected in surface water along the eastern edge of the Project Area in Knight's Brook.

In May 2016, NHDES enacted Emergency Rule 05-31-16 under Env-Or-600 which includes the addition of perfluorooctanoic acid (PFOA) and perfluorooctane sulfonate (PFOS) to the New Hampshire state ambient groundwater quality standards (AGQS). The AGQS for PFOA, PFOS, and the combined concentration of PFOA and PFOS is 0.07 µg/L. Env-Or-600 does not currently include soil standards or regulations for PFOA or PFOS.

Proper procedures for on-site management and off-site disposal of soil and water are necessary to reduce the potential for exposure to oil and hazardous materials (OHM) and be protective of workers and the public. The objectives of this Soil and Water Management Plan are to:

- a) Ensure that soil and water are managed appropriately on-site or disposed of appropriately off-site if necessary; and
- b) Specify procedures to limit exposures to contaminated soil or water via dermal contact, inhalation, and/or ingestion.

### 3. Preconstruction Requirements

The following must be completed before subsurface work commences, and approved by Eversource:

- **Notify Eversource Personnel:** The Eversource Project Manager shall be notified at least 10 business days prior to performing planned (non-emergency) soil excavation or other subsurface work that will require management of soil, groundwater, or surface water. Also, Eversource shall be notified immediately (within one hour) if unanticipated conditions are encountered such as buried debris including drums, tanks or other containers.

- **Health and Safety Plan (HASP):** The contractor selected to perform the work in the Project Area is expected to prepare a HASP for its workers and the public to address the anticipated contaminants of concern, specifically PFOA, PFOS, and arsenic. The HASP shall include historical site characterization data. The HASP shall be prepared by a Certified Industrial Hygienist or other qualified individual appropriately trained in worker health and safety procedures and requirements. The contractor is solely responsible for conducting the work in a manner that is protective of workers and the public. Employees that will be handling contaminated soil or water are required to have OSHA HAZWOPER 40-hour training.
- **Regulatory Review and Submittals:** A review of other federal, state, or local regulatory requirements (e.g., National Pollutant Discharge Elimination System permits) shall be conducted before work commences depending on the location and type of planned activity.

#### 4. Soil Pre-Characterization and Classification

GEI conducted soil pre-characterization in August 2016 which did not indicate the presence of PFCs in soil at the property. However, since the extent of the investigation was limited and testing of soil and sediments within the Knight's Brook Tributary was not performed, all excess soil will be disposed of offsite at a licensed disposal facility. All backfill and restoration activities, including soil decompaction, fertilization, and seeding, shall be in accordance with the *Soil Management Plan for Easement* prepared by Gove Environmental Services (Attachment A-1).

The Contractor shall identify an appropriate off-site reuse or disposal facility and submit the facility name and location to Eversource for review and approval. GEI's pre-characterization data may be sufficient to meet acceptance criteria for offsite reuse, recycling or disposal. If required by the selected reuse, recycling or disposal location, additional characterization for waste profiling of Project Area soil may be performed in-situ or from excavated or stockpiled material.

Based on the proposed Project Area trench dimensions of 5-feet wide by up to 6.5-feet-deep and 1,600-feet-long, a total of approximately 1,925 cubic yards of soil may be generated during trenching activities on Frink Farm. For portions of the new underground duct bank located in the agricultural zone between approximately 499+50 to 511+00 the transmission line must be covered with at least 4 feet of native material (Fig. 2). All excess soil will be disposed of offsite at a licensed disposal facility or reused offsite in accordance with applicable reuse regulations and guidelines.

#### 5. Soil Excavation

Excavated material shall be handled in general accordance with *The New Hampshire Code of Administrative Rules, Chapter Env-Or 600 - Contaminated Site Management* (Env-Or-600) and all other applicable federal, state, and local laws, regulations, and bylaws.

- **Materials Management Area:** If excavated materials are to be stored or stockpiled in the Project Area, an Excavated Material Management Area will be established by the contractor and approved by Eversource, ensuring it is in accordance with NHDES Env-Or 611.05(b). The Materials Management Area shall be within the Eversource Project Area.
- **Dust Monitoring:** As needed, the contractor shall employ control measures to minimize airborne particulates during excavation or soil management (e.g. water sprays, mists, etc.).
- **Offsite Transport and Documentation:** The Contractor shall select a location for off-site reuse and submit to Eversource for approval. Excess excavated material shall be loaded and transported to an appropriate off-site reuse, recycling or disposal location. Person(s) transporting the excavated materials shall be licensed and permitted to transport such material in state(s) having jurisdiction. Trailers used for transport shall have covers to prevent dust blow-off.

The contractor shall prepare disposal documentation and shall provide Eversource with material tracking and disposal records and certifications. Project documentation shall be maintained, including accurate records of material tracking, disposal transportation manifests (e.g., Straight BOL), and if necessary, additional environmental testing required by the receiving location.

- **Stream Crossing:** While performing the excavation through the Knight's Brook Tributary, the Contractor will:
  - Construct an access road to cross the tributary that meets the specified requirements and permit obligations for the project.
  - Install the necessary equipment to divert surface water around the excavation.
  - Install the necessary materials to prevent surface water from entering the excavation during construction.

The requirements for crossing the Knight's Brook Tributary and diverting the stream during work is shown on Fig. 3B.

## 6. Dewatering

- **Groundwater Pre-characterization and Classification:** GEI tested groundwater for PFOA and PFOS in September 2016 and June 2017. Groundwater testing results indicated the following:
  - PFOA and PFOS were not detected in B101(MW) in September 2016. PFOA and PFOS were detected in B101(MW) in June 2017 but at concentrations below the NH AGQS of 0.07 µg/L.
  - PFOA and PFOS were detected in B102(MW) in both September 2016 and June 2017 but at concentrations below the NH AGQS of 0.07 µg/L.
  - PFOA was not detected in B103(MW). PFOS was detected in B103(MW) but at concentrations below the NH AGQS of 0.07 µg/L.

Prior to the start of construction, additional groundwater samples will be collected, if possible, from B101(MW), B102(MW), and B103(MW), to assess site conditions at the time of construction.

- **Groundwater Management**

GEI conducted hydraulic conductivity testing and calculated expected dewatering rates of groundwater within the trench. The estimated dewatering rates are as follows:

- Near B101(MW): Approximately 45 to 82 gpd during a low water condition and approximately 486 to 770 gpd during a high groundwater condition.
- Near B102(MW): Approximately 104 to 187 gpd during a low groundwater condition and approximately 942 to 1466 gpd during a high groundwater condition.
- Near B103: Based on the soil encountered in B103(MW), we estimate the dewatering rates near B103(MW) will likely be between the estimated ranges for B101(MW) and B102(MW). The trench near B103(MW) may also be dry if construction takes place during low groundwater conditions similar August and September of 2017.

Our calculations are based on the limited geologic information observed during installation of B101(MW) and B102(MW). Actual dewatering rates may be higher or lower depending on site-specific and seasonal conditions.

Although, groundwater testing results did not exceed the AGQS for PFOA/PFOS, Eversource has elected to manage groundwater by one or a combination of the following methods:

- **Treatment and discharge to surface water:** Groundwater generated as part of dewatering may be discharged to surface water under a NPDES Remediation General Permit (RGP). On-site surface water discharge will likely require use of a water treatment system, including equipment such as fractionation (frac) tanks and carbon units, to adequately treat the groundwater for contaminants before discharging into Knight's Brook Tributary. Additional water testing for NPDES RGP requirements as well as approval from USEPA and NHDES will be obtained prior to treatment and discharge of water.
- **Offsite disposal of groundwater:** Groundwater may be temporarily stored onsite in a frac tank and then pumped to a vacuum truck and transported offsite for disposal or directly pumped from the excavation with a vacuum truck and transported offsite for disposal. All receiving facilities must be pre-approved by Eversource. No excess effluent may be recharged or disposed of at an uncontrolled location
- **Surface Water Pre-characterization and Classification:** Surface water testing from September 2016 indicated that PFOA and PFOS were detected in sample SW1 from Knight's Brook tributary at 0.842 µg/L and 2.91 µg/L, respectively. The total PFOA/PFOS concentration was 3.752 µg/L. Both the individual and total concentrations exceed the NH AGQS of 0.07 µg/L.

We understand that Knight's Brook tributary will be diverted during construction in a manner that does not produce excess water or require additional water management, treatment, or offsite disposal. However, if excess water is generated, the contractor shall propose methods of treatment or disposal of the surface water for approval by Eversource.

Attachments:

- Fig. 1 – Site Location Map
- Fig. 2 – Project Area Plan
- Fig. 3B – Temporary Stream Crossing Section & Details
- Attachment A-1 – Gove Environmental Services Soil Management Plan


CRC/MWS/JRA:jam

B:\Working\EVERSOURCE\1607530 - EVS-SRP NH\01\_ADMIN\Soil and GW Mgtm Plan Frink rev 12\_2017\A Soil and GW Management Plan\A - Soil and Water Management Plan rev 12\_15\_2017.docx

# Figures

---





This Image from U.S.G.S. Topographic 7.5 Minute Series  
 Portsmouth, NH - ME Quadrangle, 1981.  
 Datum is National Geodetic Vertical Datum of 1929 (NGVD29).  
 Contour Interval is 20 Feet.



QUADRANGLE LOCATION

Soil and Water Management Plan  
 Darius Frink Farm  
 Newington, New Hampshire  
 Eversource Energy  
 Manchester, New Hampshire




SITE LOCATION MAP

Project 1607530

December 2017

Fig. 1






**LEGEND:**

- ⊕ MONITORING WELL INSTALLED BY GEI IN AUGUST 2016
- ◆ SURFACE WATER SAMPLE COLLECTED BY GEI IN SEPTEMBER 2016
- HAND AUGER BY GEI IN APRIL 2017
- BORING BY TERRACON IN SEPTEMBER 2016

498+00  
 ───+──+ TRENCH ALIGNMENT AND STATION



**NOTES:**  
 1. LOCATIONS ARE APPROXIMATE.



Soil and Water Investigation Darius Frink Farm Newington, New Hampshire		PROJECT AREA PLAN	
Eversource Manchester, New Hampshire		Project 1607530	December 2017

Fig. 2






1 TYPICAL DETAIL (PLAN VIEW)  
TEMPORARY CROSSING (OPTIONAL)  
SCALE: N.T.S.

**DIMENSIONS**

DIM X	LOCATION REQUIRED
4'-0" (MIN)	CROSSING AT DUCTBANK EXCAVATION
12'-0" (MIN)	CROSSING AT CONSTRUCTION ACCESS ROAD


- CROSSING NOTES:**
- LOCATIONS OF THE TEMPORARY STREAM CROSSING ARE TO BE DETERMINED IN THE FIELD BY THE CONTRACTOR.
  - THE DESIGN AND CONSTRUCTION OF THE TEMPORARY CROSSING AND ABUTMENTS ARE THE RESPONSIBILITY OF THE CONTRACTOR AND MAY DIFFER FROM THE LAYOUT SHOWN.
  - THE TOTAL AREA OF MATTING IN WETLAND NW-16, AS SHOWN IN THE SEACOAST RELIABILITY PROJECT ENVIRONMENTAL MAP SET, SHALL NOT EXCEED 16,577 SQUARE FEET.
  - THE EXISTING GRADE SHALL BE CUT AND FILLED AS NECESSARY TO PROVIDE A LEVEL SURFACE FOR THE CROSSING.
  - REMOVE THE TEMPORARY STREAM CROSSING WHEN WORK IS COMPLETE, RESTORE EXISTING GRADES, AND STABILIZE THE AREA OF TEMPORARY IMPACT AT THE DIRECTION OF THE ENVIRONMENTAL MONITOR.




3A TYPICAL SECTION  
TEMPORARY CROSSING (OPTIONAL)  
SCALE: N.T.S.

**NOTE:**  
A. SET LEADING EDGE OF ABUTMENTS 2 FEET OR H FEET FROM THE TOP OF THE BANK, WHICHEVER IS LARGER.


- STREAM DIVERSION NOTES:**
- THE CONTRACTOR SHALL CONSTRUCT, MAINTAIN, AND OPERATE A STREAM DIVERSION STRUCTURE AS NEEDED TO DIVERT STREAM FLOWS AROUND THE DUCT BANK TRENCH. THE DIVERSION STRUCTURE SHALL BE MADE OF NON-ERODIBLE MATERIAL SUCH AS SAND BAGS, RIP RAP, CONCRETE OR OTHER SUITABLE MATERIAL ABLE TO WITHSTAND THE ANTICIPATED FLOWS.
  - THE LOCATION OF THE TEMPORARY STREAM DIVERSION STRUCTURE UPSTREAM OF THE PROPOSED DUCT BANK ALIGNMENT IS TO BE DETERMINED IN THE FIELD BY THE CONTRACTOR.
  - IF SURFACE AND/OR GROUNDWATER FLOW CONDITIONS REQUIRE, A CONTINUOUS STEEL PLATE, SHEET PILES, OR OTHER IMPERVIOUS BARRIER MAY BE DRIVEN INTO THE SUBSURFACE SOILS BOTH UPSTREAM AND DOWNSTREAM OF THE TRENCH TO PROVIDE A CUTOFF AND TO PREVENT SURFACE WATER AND GROUNDWATER FROM INFILTRATING INTO THE WORK AREA.
  - TRENCH SHORING AND EXCAVATION SLOPING TO BE CONDUCTED IN ACCORDANCE WITH OSHA REQUIREMENTS.
  - CONTRACTOR TO INSTALL AN APPROPRIATELY SIZED BYPASS PUMP UPSTREAM OF THE WORK AREA. THE PUMP SHALL BE OPERATED TO APPROXIMATE STREAM FLOW RATES AND NOT CAUSE UPSTREAM FLOODING OR OVERTOPPING OF THE STREAM BANK. AN APPROPRIATELY SIZED BASIN MAY BE INSTALLED UPSTREAM OF THE DIVERSION. FILTERING METHODS SHOULD BE EMPLOYED TO REDUCE THE MIGRATION OF FINES.
  - A STABILIZED DISCHARGE POINT DOWNSTREAM OF THE TRENCH SHALL BE CONSTRUCTED TO DISSIPATE ENERGY OF DIVERTED FLOWS. THE STABILIZED DISCHARGE POINT MAY CONSIST OF STONE PLACED ON A GEOTEXTILE SEPARATION LAYER OR OTHER SOLID SURFACE THAT RESULTS IN LOW-VELOCITY SHEET FLOW DISCHARGE TO THE STREAM. THE CONTRACTOR SHALL LOCATE THE STABILIZED DISCHARGE POINT SUFFICIENTLY DOWNSTREAM OF THE WORK AREA TO MITIGATE THE POTENTIAL FOR BACKWATER FROM THE BYPASS SYSTEM FROM IMPACTING THE WORK AREA.
  - GROUNDWATER MANAGEMENT IN THE IMMEDIATE WORK AREA IS THE RESPONSIBILITY OF THE CONTRACTOR AND SHOULD BE MANAGED IN ACCORDANCE WITH THE FRINK FARM AREA SOIL AND GROUNDWATER MANAGEMENT PLAN PREPARED BY GEI, DATED NOVEMBER 2017.
  - FOLLOWING INSTALLATION OF THE DUCT BANK, RESTORE SURFACE SOIL IN ACCORDANCE WITH THE SOIL MANAGEMENT PLAN FOR EASEMENT FRINK FARM, NIMBLE HILL ROAD, NEWINGTON, NH, PREPARED BY GOVE ENVIRONMENTAL SERVICES, DATED AUGUST 2016. RESTORE AND STABILIZE STREAM BANKS AND REMOVE THE DIVERSION STRUCTURE AT THE DIRECTION OF THE ENVIRONMENTAL MONITOR.



(PLAN VIEW) EXCAVATION AND  
CONSTRUCTION ACCESS CONCEPT  
TEMPORARY CROSSING  
SCALE: 1" = 5'



TYPICAL DETAIL (PLAN VIEW)  
TEMPORARY STREAM DIVERSION



3B TYPICAL SECTION  
TEMPORARY STREAM DIVERSION  
SCALE: N.T.S.

**NOTE:**  
A. BYPASS PUMP, HOSE, STABILIZED DISCHARGE LOCATION, AND SAND BAGS NOT SHOWN FOR CLARITY.


Frink Farm 115kV Underground Transmission Line Newington, New Hampshire		TEMPORARY STREAM CROSSING PLAN, SECTION & DETAILS
Eversource Manchester, New Hampshire		Project 1607530 December 2017

Fig. 3B

# **Attachment A-1**

---

## **Gove Environmental Services Soil Management Plan**




GOVE ENVIRONMENTAL SERVICES, INC.

December 15, 2017

SOIL MANAGEMENT PLAN FOR EASEMENT  
FRINK FARM, NIMBLE HILL ROAD, NEWINGTON, NH

- 1- A meeting will be held with the contractor, prior to construction, to discuss handling of soil.
- 2- The concept is to segregate the topsoil (A horizon) from the subsoil (B horizon) from the substratum (C horizon). The natural soil profile is a topsoil over a subsoil over a substratum. The intent is to replicate the natural soil profile when the excavation in the field is to be restored.
- 3- A qualified person will be on site during the excavation of the line to identify the soil horizons for the contractor.
- 4- The contractor, during the course of the excavation, shall segregate the topsoil, segregate the subsoil and segregate the substratum such that they are individually stock piled and not intermixed.
- 5- At 25-foot intervals along the trench in the field, the depth of the topsoil, subsoil and substratum shall be recorded as a basis for replicating the soil profile during restoration.
- 6- After the transmission line duct bank is constructed, the substratum shall be placed in the trench and slightly compacted up to the depth of the bottom of the subsoil layer.
- 7- The subsoil shall be placed into the trench, over the substratum layer, up to the depth of the bottom of the topsoil layer. Care will be taken to remove any open voids, but shall not compact the subsoil layer.
- 8- The topsoil shall be placed over the subsoil, mounded 2 inches above the natural grade on either side of the trench to allow for natural settling. Care will be taken to remove any open voids, but shall not compact the topsoil layer. . The surface will be disk harrowed to break up any clods or root balls.
- 9- The topsoil shall be seeded with a seed mix recommended by the Rockingham County Conservation District and mulched with straw.
- 10- All ground surface areas impacted construction activities shall be scarified to remove compaction, and shall be seeded and mulched as specified in 9.
- 11- Excess substratum/subsoil soil material shall be removed from the field. Excess topsoil shall be spread evenly in the easement area in the stock pile areas and seeded and mulched as noted in 9.
- 12 – Monitor success of seeding and reseed as necessary.

Compiled by Jim Gove, President of Gove Environmental Services, Inc.  
GES Project Number 2015138



8 Continental Dr Bldg 2 Unit H, Exeter, NH 03833-7526  
Ph (603) 778 0644 / Fax (603) 778 0654  
[www.gesinc.biz](http://www.gesinc.biz)  
[info@gesinc.biz](mailto:info@gesinc.biz)

# **Appendix B**

---

## **Boring Logs**


<b>BORING INFORMATION</b>		<b>BORING B101 PAGE 1 of 1</b>
LOCATION: <u>West end of field at Frink Farm</u>	DATE START/END: <u>8/26/2016 - 8/26/2016</u>	
GROUND SURFACE EL. (ft): <u>NM</u>	DRILLING COMPANY: <u>Drillex Environmental</u>	
VERTICAL DATUM: <u>NA</u>	DRILLER NAME: <u>J Jalutkewicz</u>	
TOTAL DEPTH (ft): <u>8 0</u>	RIG TYPE: <u>CME 45</u>	
LOGGED BY: <u>C Conti</u>		

<b>DRILLING INFORMATION</b>		
HAMMER TYPE: <u>Automatic</u>	CASING I.D./O.D.: <u>4 25 inch/ 8 inch</u>	CORE BARREL TYPE: <u>NA</u>
AUGER I.D./O.D.: <u>NA / NA</u>	DRILL ROD O.D.: _____	CORE BARREL I.D./O.D. <u>NA / NA</u>
DRILLING METHOD: <u>Hollow Stem Auger</u>		
WATER LEVEL DEPTHS (ft): <u>Not Encountered</u>		

**ABBREVIATIONS:**

Pen = Penetration Length	S = Split Spoon Sample	Qp = Pocket Penetrometer Strength	NA NM = Not Applicable Not Measured
Rec = Recovery Length	C = Core Sample	Sv = Pocket orvane Shear Strength	Blows per 6 in 140-lb hammer falling
RQD = Rock Quality Designation	U = Undisturbed Sample	LL = Liquid Limit	30 inches to drive a 2-inch-O D
= Length o Sound Cores>4 in / Pen %	SC = Sonic Core	P = Plasticity ndex	split spoon sampler
WOR = Weight o Rods	DP = Direct Push Sample	P D = Photoionization Detector	
WOH = Weight o Hammer	HSA = Hollow-Stem Auger	D /O D = nside Diameter/Outside Diameter	

Elev. (ft)	Depth (ft)	Sample Information				Drilling Remarks/ Field Test Data	Layer Name	Soil and Rock Description
		Sample No.	Depth (ft)	Pen./Rec. (n)	Blows per 6 in. or RQD			
		S1	0 to 2	24/18	3 4 4 6	S1= 32.5 ppm	SLT	S1: SILT WITH SAND (ML); ~90% nonplastic fines, ~10% fine sand, gray, dry, roots.
		S2	2 to 4	24/20	6 6 5 5	S2= 7.0 ppm		S2: LEAN CLAY WITH SAND (CL); ~90% low plasticity fines, ~10% mostly fine sand, gray. Moist in bottom 6 inches.
	5	S3	4 to 6	24/21	1 2 2 2	S3= 5.6 ppm	CLAY	S3: Similar to S2. Wet starting at ~4.5 to 5 feet. Some reddish orange mottling.
		S4	6 to 8	24/17	3 3 2 1	S4= 4.6 ppm		S4: Similar to S2. Gray light brown, wet, some mottling with reddish orange.
	10							Bottom of boring at ~8 feet. Installed monitoring well.
	15							
	20							

<b>NOTES:</b> Samples collected B101(S1-S2) composite and B101(S3-S4) composite	<b>PROJECT NAME:</b> Eversource New Hampshire Seacoast Reliability Project <b>CITY/STATE:</b> Newington NH <b>GEI PROJECT NUMBER:</b> 1607530	
--	---	---

GE WOBURN S D 1-1-LOCAL ON-LAYER NAME EYS NH SRP GPJ GE DA A EMPLA E 2011 GD 8/29/16



<b>BORING INFORMATION</b>		<b>BORING B102 PAGE 1 of 1</b>
LOCATION: Middle of field at Frink Farm	DATE START/END: 8/26/2016 - 8/26/2016	
GROUND SURFACE EL. (ft): NM	DRILLING COMPANY: Drilrex Environmental	
VERTICAL DATUM: NA	DRILLER NAME: J Jalutkewicz	
TOTAL DEPTH (ft): 7.5	RIG TYPE: CME 45	
LOGGED BY: C Conti		

<b>DRILLING INFORMATION</b>		
HAMMER TYPE: Automatic	CASING I.D./O.D.: 4.25 inch/ 8 inch	CORE BARREL TYPE: NA
AUGER I.D./O.D.: NA / NA	DRILL ROD O.D.: _____	CORE BARREL I.D./O.D. NA / NA
DRILLING METHOD: Hollow Stem Auger		
WATER LEVEL DEPTHS (ft): Not Encountered		

**ABBREVIATIONS:**

Pen = Penetration Length Rec = Recovery Length RQD = Rock Quality Designation = Length of Sound Cores > 4 in / Pen % WOR = Weight of Rods WOH = Weight of Hammer	S = Split Spoon Sample C = Core Sample U = Undisturbed Sample SC = Sonic Core DP = Direct Push Sample HSA = Hollow-Stem Auger	Qp = Pocket Penetrometer Strength Sv = Pocket or vane Shear Strength LL = Liquid Limit P = Plasticity Index P D = Photoionization Detector D / O D = Inside Diameter / Outside Diameter
---	--	--

NA NM = Not Applicable Not Measured  
 Blows per 6 in 140-lb hammer falling  
 30 inches to drive a 2-inch-O D  
 split spoon sampler

Elev. (ft)	Depth (ft)	Sample Information				Drilling Remarks / Field Test Data	Layer Name	Soil and Rock Description
		Sample No.	Depth (ft)	Pen./ Rec. (n)	Blows per 6 in. or RQD			
	5	S1	0 to 2	24/14	3 3 5 5	S1= 5.6 ppm	SILT	S1: SILT WITH SAND (ML); ~85% nonplastic fines, ~15% mostly fine sand, light brown to gray, roots.
		S2	2 to 4	24/20	8 9 10 10	S2= 5.1 ppm		S2: SILT (ML); ~95% low plasticity fines, ~5% fine sand, gray.
		S3	4 to 6	24/19	2 2 2 2	S3= 5.4 ppm	CLAY	S3: LEAN CLAY WITH SAND (CL); ~85% low plasticity fines, ~15% mostly fine sand, brown gray. Wet at 5 feet with 2" seam of fine sand at ~ 5 feet. Increasing fine sand with depth.
		S4	6 to 6.8	9/9	18 55/3"	S4= 5.1 ppm Weathered rock n t p. Auger refusal at 7.5 feet.		S4: SANDY LEAN CLAY (CL); ~75% low plasticity fines, ~25% mostly fine sand, light brown gray, wet, rock n t p.
	10							Bottom of boring @ 7.5 feet. Installed monitoring well. Rock shaled, bottom of screen at 7 feet.
	15							
	20							

<b>NOTES:</b> Samples collected B102(S1-S2) composite and B102 (S3-S4) composite	<b>PROJECT NAME:</b> Eversource New Hampshire Seacoast Reliability Project <b>CITY/STATE:</b> Newington NH <b>GEI PROJECT NUMBER:</b> 1607530
---	---



GE WOBU R N S D 1-1-LOCAL ON-LAYER NAME EYS NH SRP GP J GE DA A EMPLA E 2011 GD 8/29/16




<b>BORING INFORMATION</b>		<b>BORING B103 PAGE 1 of 1</b>
LOCATION: East end of field Frink Farm		
GROUND SURFACE EL. (ft): NM	DATE START/END: 8/26/2016 - 8/26/2016	
VERTICAL DATUM: NA	DRILLING COMPANY: Drilex Environmental	
TOTAL DEPTH (ft): 8.0	DRILLER NAME: J Jalutkewicz	
LOGGED BY: C Conti	RIG TYPE: CME 45	

<b>DRILLING INFORMATION</b>		
HAMMER TYPE: Automatic	CASING I.D./O.D.: 4.25 inch/ 8 inch	CORE BARREL TYPE: NA
AUGER I.D./O.D.: NA / NA	DRILL ROD O.D.: _____	CORE BARREL I.D./O.D. NA / NA
DRILLING METHOD: Hollow Stem Auger		
WATER LEVEL DEPTHS (ft): Not Encountered		

**ABBREVIATIONS:**

Pen = Penetration Length	S = Split Spoon Sample	Qp = Pocket Penetrometer Strength	NA NM = Not Applicable Not Measured
Rec = Recovery Length	C = Core Sample	Sv = Pocket orvane Shear Strength	Blows per 6 in 140-lb hammer falling
RQD = Rock Quality Designation	U = Undisturbed Sample	LL = Liquid Limit	30 inches to drive a 2-inch-O D
= Length of Sound Cores > 4 in / Pen %	SC = Sonic Core	P = Plasticity Index	split spoon sampler
WOR = Weight of Rods	DP = Direct Push Sample	P D = Photoionization Detector	
WOH = Weight of Hammer	HSA = Hollow-Stem Auger	D / O D = Inside Diameter/Outside Diameter	

Elev. (ft)	Depth (ft)	Sample Information				Drilling Remarks/ Field Test Data	Layer Name	Soil and Rock Description
		Sample No.	Depth (ft)	Pen./Rec. (n)	Blows per 6 in. or RQD			
		S1	0 to 2	24/13	3588	S1= 0.3 ppm	SILT	S1: SILT WITH SAND (ML); ~70% nonplastic fines, ~25% most fine sand, ~5% gravel to 3/4", light brown, dry, some roots on top 3".
		S2	2 to 2.9	11/11	1865/5"	S2= 0.5 ppm		S2: Same as S1, no roots.
	5	S3	4 to 6	24/13	1819 2532	Cobble from 3-4 feet. S3= 0.6 ppm	GRAVEL	S3: WIDELY GRADED GRAVEL WITH SILT AND SAND (GW GM); ~75% fine to coarse gravel, ~15% most fine sand, ~10% nonplastic fines, brown.
		S4			5530 80/7"	S4= 0.8 ppm		S4: WIDELY GRADED GRAVEL WITH SILT AND SAND (GW GM); ~60% fine to coarse gravel, ~30% fine to coarse sand, ~10% nonplastic fines, brown to reddish brown.
	10					Refusal on cobble/ weathered rock. Augered to 8 feet.		Bottom of boring at 8 feet. Installed monitoring well.
	15							
	20							

<b>NOTES:</b> Samples collected B103(S1-S2) composite and B103 (S3-S4) composite	<b>PROJECT NAME:</b> Eversource New Hampshire Seacoast Reliability Project <b>CITY/STATE:</b> Newington NH <b>GEI PROJECT NUMBER:</b> 1607530	
---	---	---

GEI WOBURN S. D 1-1-LOCAL ON-LAYER NAME EYS NH\_SRP\_GPJ\_GE\_DA\_A\_EMPLA\_E 2011.GD 8/29/16

<b>BORING INFORMATION</b>		<b>BORING HA1 PAGE 1 of 1</b>
LOCATION: East side of tributary	DATE START/END: 4/7/2017 - 4/7/2017	
GROUND SURFACE EL. (ft): NM	DRILLING COMPANY: GE Consultants	
VERTICAL DATUM: NM	DRILLER NAME: M Greer J Wolpert	
TOTAL DEPTH (ft): 6.5	RIG TYPE: Hand Auger	
LOGGED BY: M Greer		

<b>DRILLING INFORMATION</b>		
HAMMER TYPE: NA	CASING I.D./O.D.: NA / NA	CORE BARREL TYPE: NA
AUGER I.D./O.D.: 2.5 inch / 2.6 inch	DRILL ROD O.D.: NM	CORE BARREL I.D./O.D. NA / NA
DRILLING METHOD: Auger		
WATER LEVEL DEPTHS (ft): Not measured		

**ABBREVIATIONS:**

Pen = Penetration Length	S = Split Spoon Sample	Qp = Pocket Penetrometer Strength	NA NM = Not Applicable Not Measured
Rec = Recovery Length	C = Core Sample	Sv = Pocket orvane Shear Strength	Blows per 6 in 140-lb hammer alling
RQD = Rock Quality Designation	U = Undisturbed Sample	LL = Liquid Limit	30 inches to drive a 2-inch-O D
= Length o Sound Cores > 4 in / Pen %	SC = Sonic Core	P = Plasticity Index	split spoon sampler
WOR = Weight o Rods	DP = Direct Push Sample	P D = Photoionization Detector	
WOH = Weight o Hammer	HSA = Hollow-Stem Auger	D / O D = Inside Diameter/Outside Diameter	

Elev. (ft)	Depth (ft)	Sample Information				Drilling Remarks/ Field Test Data	Layer Name	Soil and Rock Description
		Sample No.	Depth (ft)	Pen./Rec. (n)	Blows per 6 in. or RQD			
		S1	1 to 2	12/12		OL	S1 (0 1'): ORGANIC SOIL (OL); ~85% low plasticity fines, ~15% fine sand, dark brown, roots in top 6 inches, wet.	
		S2	2 to 3	12/12		ML	S2 (1 1.5'): Same as S1(0 1'), no roots.	
		S3	3 to 4	12/12			S2(1.5 2'): SANDY SILT (ML); ~70% low plasticity fines, ~30% fine sand, gray, wet.	
		S4	4 to 5	12/12		CLAY	S3: Same as above.	
	5	S5	5 to 6	12/12			S4: LEAN CLAY (CL); ~95% medium plasticity fines, ~5% fine sand, gray, wet.	
		S6	6 to 6.5	12/12			S5: Same as S4, mottled orange, some roots.	
		S7	6.5 to 7	6/6			S6: Same as S4, mottled orange, some roots.	
			7 to 7				S7: Same as S4, mottled orange, some roots.	
	10						Bottom of boring at about 6.5 feet. Backfilled with cuttings.	
	15							
	20							

<b>NOTES:</b>	<b>PROJECT NAME:</b> Eversource New Hampshire Seacoast Reliability Project <b>CITY/STATE:</b> Newington NH <b>GEI PROJECT NUMBER:</b> 1607530
---------------	---



GEI WOBURN S D 14-LOCA ON-LAYER NAME EVS NH SRP GPJ 6/21/17

<b>BORING INFORMATION</b>		<b>BORING HA2 PAGE 1 of 1</b>
LOCATION: West side of tributary	DATE START/END: 4/7/2017 - 4/7/2017	
GROUND SURFACE EL. (ft): NM	DRILLING COMPANY: GE Consultants	
VERTICAL DATUM: NM	DRILLER NAME: M Greer J Wolpert	
TOTAL DEPTH (ft): 6.0	RIG TYPE: Hand Auger	
LOGGED BY: M Greer		

<b>DRILLING INFORMATION</b>		
HAMMER TYPE: NA	CASING I.D./O.D.: NA / NA	CORE BARREL TYPE: NA
AUGER I.D./O.D.: 2.5 inch / 2.6 inch	DRILL ROD O.D.: NM	CORE BARREL I.D./O.D. NA / NA
DRILLING METHOD: Auger		
WATER LEVEL DEPTHS (ft): Not measured		

**ABBREVIATIONS:**

Pen = Penetration Length	S = Split Spoon Sample	Qp = Pocket Penetrometer Strength	NA NM = Not Applicable Not Measured
Rec = Recovery Length	C = Core Sample	Sv = Pocket orvane Shear Strength	Blows per 6 in 140-lb hammer alling
RQD = Rock Quality Designation	U = Undisturbed Sample	LL = Liquid Limit	30 inches to drive a 2-inch-O D
= Length o Sound Cores > 4 in / Pen %	SC = Sonic Core	P = Plasticity Index	split spoon sampler
WOR = Weight o Rods	DP = Direct Push Sample	P D = Photoionization Detector	
WOH = Weight o Hammer	HSA = Hollow-Stem Auger	D / O D = Inside Diameter/Outside Diameter	

Elev. (ft)	Depth (ft)	Sample Information				Drilling Remarks/ Field Test Data	Layer Name	Soil and Rock Description
		Sample No.	Depth (ft)	Pen./Rec. (n)	Blows per 6 in. or RQD			
						OL	S1(0.0.5'): ORGANIC SOIL (OL); ~85% organic fines, ~15% fine sand, dark brown, roots, wet.	
		S1	1 to 2	12/12		SANDY SILT	S1(0.5 1'): SANDY SILT (ML); ~80% organic fines, ~20% fine sand, no roots, organic mottling, blue, wet.	
		S2	2 to 3	12/12			S2: same as S1(0.5 1').	
		S3	3 to 4	12/12			S3: same as S1(0.5 1').	
		S4	4 to 5	12/12		SAND	S4(3.3.5'): same as S1(0.5 1').	
	5	S5	5 to 6	12/12			S4(3.5 4'): NARROWLY GRADED SAND WITH SILT (SP SM); ~80% mostly fine sand, ~20% organic fines, gray, wet.	
		S6	6 to 7	12/12		CLAY	S5: same as S4(3.5 4').	
							S6: LEAN CLAY (CL); ~95% medium plastic fines, ~5% fine sand, gray, mottled, wet.	
							Bottom of boring at about 6 feet. Backfilled with cuttings.	
	10							
	15							
	20							

<b>NOTES:</b>	<b>PROJECT NAME:</b> Eversource New Hampshire Seacoast Reliability Project <b>CITY/STATE:</b> Newington NH <b>GEI PROJECT NUMBER:</b> 1607530
---------------	---



GEI WOBURN S D 14-LOCA ON-LAYER NAME EVS NH SRP GPJ 6/21/17

# BORING LOG NO. F107-109

**PROJECT:** Seacoast Reliability Project

**CLIENT:** Eversource Energy

**SITE:** Portsmouth, Newington,  
Durham, and Madbury, New Hampshire

GRAPHIC LOG	LOCATION See Exhibit A-2 Latitude 43 10076522° Longitude -70 83778978°  Surface Elev 43 284 (Ft) ELEVATION (Ft)	DEPTH (Ft)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	RECOVERY (n)	FIELD TEST RESULTS	ROD (%)	Core Rate (min/ft)
	3 nches of forest oam, roots 6 nches of subso	41.5			12	4 7 11 12 N=18		
2.0	<b>SILTY SAND (SM)</b> , ght brown to wh te, des ccated, med um dense	40			16	7 9 8 8 N=17		
3.5	<b>SILT WITH SAND (ML)</b> , o ve brown, des ccated				24	6 5 7 8 N=12		
9.0	<b>LEAN CLAY (CL)</b> , gray, very soft	34.5			24	woh 1 1 woh N=2		
24.0		19.5			24	wor/12" woh/12"		
25.0	<b>SILTY SAND (SM)</b> , w th fractured grave , brown, very dense, (GLACIAL TILL) Ro er b t to 29 feet	18.5			18	18 18 32 21 N=50		
29.0	Run 1 Hard, s ght y weathered, gray, aphan t c PHYLLITE, moderate y d pp ng, c ose jo nts EXETER DIORITE FORMATION	14.5			49		25	
	Run 2 Sm ar Note: Numerous mechan ca breaks due to jamm ng ns de the barre				41		13	

Stratification lines are approximate n-situ the transition may be gradual

Hammer Type Automatic

Advancement Method 3-inch casing	See Exhibit A-3 for description of field procedures See Appendix B for description of laboratory procedures and additional data (if any) See Appendix C for explanation of symbols and abbreviations	Notes	
Abandonment Method Boring backfilled with soil cuttings upon completion			
<b>WATER LEVEL OBSERVATIONS</b> No free water observed		77 Sundial Ave Ste 401W Manchester NH	
		Boring Started 8/26/2016 Drill Rig Diedrich D-50 turbo Project No J1165081	Boring Completed 8/26/2016 Driller Drilex Exhibit A-31

H.S.BORING LOG S NO VAL D F SEPARA ED FROM OR G NAL REPOR GEO SMAR LOG-NO WELL J1165081 GPJ

# BORING LOG NO. F107-109

**PROJECT:** Seacoast Reliability Project

**CLIENT:** Eversource Energy

**SITE:** Portsmouth, Newington,  
Durham, and Madbury, New Hampshire

GRAPHIC LOG	LOCATION See Exhibit A-2 Latitude 43 10076522° Longitude -70 83778978°  Surface Elev 43 284 (Ft )	DEPTH (Ft )	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	RECOVERY ( n )	FIELD TEST RESULTS	ROD (%)	Core Rate (min/ft)
DEPTH	ELEVATION (Ft )							
39.0	45				41			
<b>Boring Terminated at 39 Feet</b>								
Stratification lines are approximate n-situ the transition may be gradual					Hammer Type Automatic			

Advancement Method 3-inch casing	See Exhibit A-3 for description of field procedures See Appendix B for description of laboratory procedures and additional data (if any) See Appendix C for explanation of symbols and abbreviations	Notes						
Abandonment Method Boring backfilled with soil cuttings upon completion								
<b>WATER LEVEL OBSERVATIONS</b> No free water observed	 <p>77 Sundial Ave Ste 401W Manchester NH</p>	<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 50%; border-bottom: 1px solid black;">Boring Started 8/26/2016</td> <td style="width: 50%; border-bottom: 1px solid black;">Boring Completed 8/26/2016</td> </tr> <tr> <td style="border-bottom: 1px solid black;">Drill Rig Diedrich D-50 turbo</td> <td style="border-bottom: 1px solid black;">Driller Drilex</td> </tr> <tr> <td style="border-bottom: 1px solid black;">Project No J1165081</td> <td style="border-bottom: 1px solid black;">Exhibit A-31</td> </tr> </table>	Boring Started 8/26/2016	Boring Completed 8/26/2016	Drill Rig Diedrich D-50 turbo	Driller Drilex	Project No J1165081	Exhibit A-31
Boring Started 8/26/2016	Boring Completed 8/26/2016							
Drill Rig Diedrich D-50 turbo	Driller Drilex							
Project No J1165081	Exhibit A-31							

H.S.BORING LOG S.NO. VAL.D.F.SEPARATED FROM ORIGINAL REPORT GEO SMAR LOG-NO WELL J1165081 GPJ

# Groundwater Well Installation Log

## B101(MW)

**Project** Eversource New Hampshire Seacoast Reliability Project  
**City / Town** Newington, NH  
**Client** Eversource  
**Contractor** Drillex Environmental  
**Driller** J. Jalutkewicz **GEI Rep.** C. Conti

**GEI Proj. No.** 1607530  
**Location** East end of field at Frink Farm  
**Install Date** 8/26/2016


**Survey Datum:** \_\_\_\_\_

**Ground Elevation:**

Date	Time	Distance to ▼ below top of riser pipe

Silt

Clay



Length of Surface Casing above Ground	3.3'
Dist. Top of Surf. Casing to Top of Riser Pipe	0.18'
Type and Thickness of Seal around Surface Casing	NA
ID of Surface Casing	4"
Type of Surface Casing	
Depth Bottom of Surface Casing	1.7
ID and OD of Riser Pipe	2.0"/2.5"
Type of Riser Pipe	Sch. 40 PVC
Type of Backfill around Riser Pipe	NA
Diameter of Borehole	8"
Depth Top of Seal	NA
Type of Seal	Med. Bentonite Chips
Depth Bottom of Seal	1.5'
Depth Top of Screened Section	2'
Type of Screen	Sch. 40 PVC
Description of Screen Openings	0.010 Slotted
ID and OD of Screened Section	2.0"/2.5"
Type of Filter Material	Sand Type 0
Depth Bottom of Screened Section	7.7'
Depth Bottom of Silt Trap	8'
Depth Bottom of Filter Material	NA
Depth Top of Seal	NA
Type of Seal	NA
Depth Bottom of Seal	NA
Type of Backfill below Filter Material	NA
Bottom of Borehole	8'

**Notes:**





# Groundwater Well Installation Log

## B102(MW)


**Project** Eversource New Hampshire Seacoast Reliability Project  
**City / Town** Newington, NH  
**Client** Eversource  
**Contractor** Drillex Environmental  
**Driller** J. Jalutkewicz **GEI Rep.** C. Conti

**GEI Proj. No.** 1607530  
**Location** Middle of field at Frink Farm  
**Install Date** 8/26/2016

**Survey Datum:** \_\_\_\_\_

**Ground Elevation:**

Date		
Time		
Distance to ▼ below top of riser pipe		



Length of Surface Casing above Ground	3.1'
Dist. Top of Surf. Casing to Top of Riser Pipe	0.2'
Type and Thickness of Seal around Surface Casing	NA
ID of Surface Casing	4.25"
Type of Surface Casing	Steel guard pipe
Depth Bottom of Surface Casing	1.9
ID and OD of Riser Pipe	2.0"/2.5"
Type of Riser Pipe	Sch. 40 PVC
Type of Backfill around Riser Pipe	NA
Diameter of Borehole	8"
Depth Top of Seal	NA
Type of Seal	Med. Bentonite Chips
Depth Bottom of Seal	1.5'
Depth Top of Screened Section	2'
Type of Screen	Sch. 40 PVC
Description of Screen Openings	0.010 Slotted
ID and OD of Screened Section	2.0"/2.5"
Type of Filter Material	Sand Type 0
Depth Bottom of Screened Section	6.7'
Depth Bottom of Silt Trap	7'
Depth Bottom of Filter Material	NA
Depth Top of Seal	NA
Type of Seal	NA
Depth Bottom of Seal	NA
Type of Backfill below Filter Material	NA
Bottom of Borehole	7'

**Notes:**





# Groundwater Well Installation Log

## B103(MW)


**Project** Eversource New Hampshire Seacoast Reliability Project  
**City / Town** Newington, NH  
**Client** Eversource  
**Contractor** Drillex Environmental  
**Driller** J. Jalutkewicz **GEI Rep.** C. Conti

**GEI Proj. No.** 1607530  
**Location** West end of field at Frink Farm  
**Install Date** 8/26/2016

**Survey Datum:** \_\_\_\_\_

**Ground Elevation:**

Date	Time	Distance to ▼ below top of riser pipe



**Notes:**



# Appendix C

---

## Laboratory Data Reports



## ANALYTICAL REPORT

Lab Number:	L1627010
Client:	GEI Consultants 400 Unicorn Park Drive Woburn, MA 01801
ATTN:	Mike Sabulis
Phone:	(781) 721-4114
Project Name:	EVERSOURCE NH SRP
Project Number:	1607530
Report Date:	09/15/16

The original project report/data package is held by Alpha Analytical. This report/data package is paginated and should be reproduced only in its entirety. Alpha Analytical holds no responsibility for results and/or data that are not consistent with the original.

Certifications & Approvals: MA (M-MA086), NY (11148), CT (PH-0574), NH (2003), NJ NELAP (MA935), RI (LAO00065), ME (MA00086), PA (68-03671), VA (460195), MD (348), IL (200077), NC (666), TX (T104704476), DOD (L2217), USDA (Permit #P-330-11-00240).

---

Eight Walkup Drive, Westborough, MA 01581-1019  
508-898-9220 (Fax) 508-898-9193 800-624-9220 - [www.alphalab.com](http://www.alphalab.com)



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

<b>Alpha Sample ID</b>	<b>Client ID</b>	<b>Matrix</b>	<b>Sample Location</b>	<b>Collection Date/Time</b>	<b>Receive Date</b>
L1627010-01	1607530-B103(S1-S2)	SOIL	NEWINGTON, NH	08/26/16 09:25	08/29/16
L1627010-02	1607530-B103(S3-S4)	SOIL	NEWINGTON, NH	08/26/16 09:55	08/29/16
L1627010-03	1607530-B102(S1-S2)	SOIL	NEWINGTON, NH	08/26/16 10:45	08/29/16
L1627010-04	1607530-B102(S3-S4)	SOIL	NEWINGTON, NH	08/26/16 11:00	08/29/16
L1627010-05	1607530-B101(S1-S2)	SOIL	NEWINGTON, NH	08/26/16 11:45	08/29/16
L1627010-06	1607530-B101(S3-S4)	SOIL	NEWINGTON, NH	08/26/16 12:00	08/29/16

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

### Case Narrative

The samples were received in accordance with the Chain of Custody and no significant deviations were encountered during the preparation or analysis unless otherwise noted. Sample Receipt, Container Information, and the Chain of Custody are located at the back of the report.

Results contained within this report relate only to the samples submitted under this Alpha Lab Number and meet NELAP requirements for all NELAP accredited parameters unless otherwise noted in the following narrative. The data presented in this report is organized by parameter (i.e. VOC, SVOC, etc.). Sample specific Quality Control data (i.e. Surrogate Spike Recovery) is reported at the end of the target analyte list for each individual sample, followed by the Laboratory Batch Quality Control at the end of each parameter. Tentatively Identified Compounds (TICs), if requested, are reported for compounds identified to be present and are not part of the method/program Target Compound List, even if only a subset of the TCL are being reported. If a sample was re-analyzed or re-extracted due to a required quality control corrective action and if both sets of data are reported, the Laboratory ID of the re-analysis or re-extraction is designated with an "R" or "RE", respectively. When multiple Batch Quality Control elements are reported (e.g. more than one LCS), the associated samples for each element are noted in the grey shaded header line of each data table. Any Laboratory Batch, Sample Specific % recovery or RPD value that is outside the listed Acceptance Criteria is bolded in the report. All specific QC information is also incorporated in the Data Usability format of our Data Merger tool where it can be reviewed along with any associated usability implications. Soil/sediments, solids and tissues are reported on a dry weight basis unless otherwise noted. Definitions of all data qualifiers and acronyms used in this report are provided in the Glossary located at the back of the report.

In reference to questions H (CAM) or 4 (RCP) when "NO" is checked, the performance criteria for CAM and RCP methods allow for some quality control failures to occur and still be within method compliance. In these instances the specific failure is not narrated but noted in the associated QC table. The information is also incorporated in the Data Usability format of our Data Merger tool where it can be reviewed along with any associated usability implications.

Please see the associated ADEx data file for a comparison of laboratory reporting limits that were achieved with the regulatory Numerical Standards requested on the Chain of Custody.

#### HOLD POLICY

For samples submitted on hold, Alpha's policy is to hold samples (with the exception of Air canisters) free of charge for 21 calendar days from the date the project is completed. After 21 calendar days, we will dispose of all samples submitted including those put on hold unless you have contacted your Client Service Representative and made arrangements for Alpha to continue to hold the samples. Air canisters will be disposed after 3 business days from the date the project is completed.

Please contact Client Services at 800-624-9220 with any questions.

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

### Case Narrative (continued)


#### Report Submission

This final report replaces the partial report issued September 6, 2016 and includes the results of all requested analyses.

The analyses of PFOA and PFOS by Method 537 were subcontracted. A copy of the laboratory report is included as an addendum. Please note: This data is only available in PDF format and is not available on Data Merger.

I, the undersigned, attest under the pains and penalties of perjury that, to the best of my knowledge and belief and based upon my personal inquiry of those responsible for providing the information contained in this analytical report, such information is accurate and complete. This certificate of analysis is not complete unless this page accompanies any and all pages of this report.

Authorized Signature:

 Kelly Stenstrom

Title: Technical Director/Representative

Date: 09/15/16

# ORGANICS



# VOLATILES

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-01  
 Client ID: 1607530-B103(S1-S2)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8260C  
 Analytical Date: 09/05/16 12:20  
 Analyst: BN  
 Percent Solids: 93%

Date Collected: 08/26/16 09:25  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by EPA 5035 High - Westborough Lab</b>						
Methylene chloride	ND		ug/kg	610	--	1
1,1-Dichloroethane	ND		ug/kg	92	--	1
Chloroform	ND		ug/kg	92	--	1
Carbon tetrachloride	ND		ug/kg	61	--	1
1,2-Dichloropropane	ND		ug/kg	210	--	1
Dibromochloromethane	ND		ug/kg	61	--	1
1,1,2-Trichloroethane	ND		ug/kg	92	--	1
Tetrachloroethene	ND		ug/kg	61	--	1
Chlorobenzene	ND		ug/kg	61	--	1
Trichlorofluoromethane	ND		ug/kg	300	--	1
1,2-Dichloroethane	ND		ug/kg	61	--	1
1,1,1-Trichloroethane	ND		ug/kg	61	--	1
Bromodichloromethane	ND		ug/kg	61	--	1
trans-1,3-Dichloropropene	ND		ug/kg	61	--	1
cis-1,3-Dichloropropene	ND		ug/kg	61	--	1
1,3-Dichloropropene, Total	ND		ug/kg	61	--	1
1,1-Dichloropropene	ND		ug/kg	300	--	1
Bromoform	ND		ug/kg	240	--	1
1,1,2,2-Tetrachloroethane	ND		ug/kg	61	--	1
Benzene	ND		ug/kg	61	--	1
Toluene	ND		ug/kg	92	--	1
Ethylbenzene	ND		ug/kg	61	--	1
Chloromethane	ND		ug/kg	300	--	1
Bromomethane	ND		ug/kg	120	--	1
Vinyl chloride	ND		ug/kg	120	--	1
Chloroethane	ND		ug/kg	120	--	1
1,1-Dichloroethene	ND		ug/kg	61	--	1
trans-1,2-Dichloroethene	ND		ug/kg	92	--	1
Trichloroethene	ND		ug/kg	61	--	1
1,2-Dichlorobenzene	ND		ug/kg	300	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-01  
 Client ID: 1607530-B103(S1-S2)  
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 09:25  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by EPA 5035 High - Westborough Lab</b>						
1,3-Dichlorobenzene	ND		ug/kg	300	--	1
1,4-Dichlorobenzene	ND		ug/kg	300	--	1
Methyl tert butyl ether	ND		ug/kg	120	--	1
p/m-Xylene	ND		ug/kg	120	--	1
o-Xylene	ND		ug/kg	120	--	1
Xylenes, Total	ND		ug/kg	120	--	1
cis-1,2-Dichloroethene	ND		ug/kg	61	--	1
1,2-Dichloroethene, Total	ND		ug/kg	61	--	1
Dibromomethane	ND		ug/kg	610	--	1
1,4-Dichlorobutane	ND		ug/kg	610	--	1
1,2,3-Trichloropropane	ND		ug/kg	610	--	1
Styrene	ND		ug/kg	120	--	1
Dichlorodifluoromethane	ND		ug/kg	610	--	1
Acetone	ND		ug/kg	2200	--	1
Carbon disulfide	ND		ug/kg	610	--	1
2-Butanone	ND		ug/kg	610	--	1
Vinyl acetate	ND		ug/kg	610	--	1
4-Methyl-2-pentanone	ND		ug/kg	610	--	1
2-Hexanone	ND		ug/kg	610	--	1
Ethyl methacrylate	ND		ug/kg	610	--	1
Acrylonitrile	ND		ug/kg	240	--	1
Bromochloromethane	ND		ug/kg	300	--	1
Tetrahydrofuran	ND		ug/kg	1200	--	1
2,2-Dichloropropane	ND		ug/kg	300	--	1
1,2-Dibromoethane	ND		ug/kg	240	--	1
1,3-Dichloropropane	ND		ug/kg	300	--	1
1,1,1,2-Tetrachloroethane	ND		ug/kg	61	--	1
Bromobenzene	ND		ug/kg	300	--	1
n-Butylbenzene	ND		ug/kg	61	--	1
sec-Butylbenzene	ND		ug/kg	61	--	1
tert-Butylbenzene	ND		ug/kg	300	--	1
o-Chlorotoluene	ND		ug/kg	300	--	1
p-Chlorotoluene	ND		ug/kg	300	--	1
1,2-Dibromo-3-chloropropane	ND		ug/kg	300	--	1
Hexachlorobutadiene	ND		ug/kg	300	--	1
Isopropylbenzene	ND		ug/kg	61	--	1
p-Isopropyltoluene	ND		ug/kg	61	--	1
Naphthalene	ND		ug/kg	300	--	1
n-Propylbenzene	ND		ug/kg	61	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

**Lab ID:** L1627010-01  
**Client ID:** 1607530-B103(S1-S2)  
**Sample Location:** NEWINGTON, NH

**Date Collected:** 08/26/16 09:25  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Volatile Organics by EPA 5035 High - Westborough Lab						
1,2,3-Trichlorobenzene	ND		ug/kg	300	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	300	--	1
1,3,5-Trimethylbenzene	ND		ug/kg	300	--	1
1,2,4-Trimethylbenzene	ND		ug/kg	300	--	1
trans-1,4-Dichloro-2-butene	ND		ug/kg	300	--	1
Ethyl ether	ND		ug/kg	300	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	97		70-130
Toluene-d8	100		70-130
4-Bromofluorobenzene	98		70-130
Dibromofluoromethane	94		70-130

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-02  
 Client ID: 1607530-B103(S3-S4)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8260C  
 Analytical Date: 09/05/16 12:47  
 Analyst: BN  
 Percent Solids: 92%

Date Collected: 08/26/16 09:55  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by EPA 5035 High - Westborough Lab</b>						
Methylene chloride	ND		ug/kg	520	--	1
1,1-Dichloroethane	ND		ug/kg	77	--	1
Chloroform	ND		ug/kg	77	--	1
Carbon tetrachloride	ND		ug/kg	52	--	1
1,2-Dichloropropane	ND		ug/kg	180	--	1
Dibromochloromethane	ND		ug/kg	52	--	1
1,1,2-Trichloroethane	ND		ug/kg	77	--	1
Tetrachloroethene	ND		ug/kg	52	--	1
Chlorobenzene	ND		ug/kg	52	--	1
Trichlorofluoromethane	ND		ug/kg	260	--	1
1,2-Dichloroethane	ND		ug/kg	52	--	1
1,1,1-Trichloroethane	ND		ug/kg	52	--	1
Bromodichloromethane	ND		ug/kg	52	--	1
trans-1,3-Dichloropropene	ND		ug/kg	52	--	1
cis-1,3-Dichloropropene	ND		ug/kg	52	--	1
1,3-Dichloropropene, Total	ND		ug/kg	52	--	1
1,1-Dichloropropene	ND		ug/kg	260	--	1
Bromoform	ND		ug/kg	210	--	1
1,1,2,2-Tetrachloroethane	ND		ug/kg	52	--	1
Benzene	ND		ug/kg	52	--	1
Toluene	ND		ug/kg	77	--	1
Ethylbenzene	ND		ug/kg	52	--	1
Chloromethane	ND		ug/kg	260	--	1
Bromomethane	ND		ug/kg	100	--	1
Vinyl chloride	ND		ug/kg	100	--	1
Chloroethane	ND		ug/kg	100	--	1
1,1-Dichloroethene	ND		ug/kg	52	--	1
trans-1,2-Dichloroethene	ND		ug/kg	77	--	1
Trichloroethene	ND		ug/kg	52	--	1
1,2-Dichlorobenzene	ND		ug/kg	260	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

**Lab ID:** L1627010-02  
**Client ID:** 1607530-B103(S3-S4)  
**Sample Location:** NEWINGTON, NH

**Date Collected:** 08/26/16 09:55  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by EPA 5035 High - Westborough Lab</b>						
1,3-Dichlorobenzene	ND		ug/kg	260	--	1
1,4-Dichlorobenzene	ND		ug/kg	260	--	1
Methyl tert butyl ether	ND		ug/kg	100	--	1
p/m-Xylene	ND		ug/kg	100	--	1
o-Xylene	ND		ug/kg	100	--	1
Xylenes, Total	ND		ug/kg	100	--	1
cis-1,2-Dichloroethene	ND		ug/kg	52	--	1
1,2-Dichloroethene, Total	ND		ug/kg	52	--	1
Dibromomethane	ND		ug/kg	520	--	1
1,4-Dichlorobutane	ND		ug/kg	520	--	1
1,2,3-Trichloropropane	ND		ug/kg	520	--	1
Styrene	ND		ug/kg	100	--	1
Dichlorodifluoromethane	ND		ug/kg	520	--	1
Acetone	ND		ug/kg	1800	--	1
Carbon disulfide	ND		ug/kg	520	--	1
2-Butanone	ND		ug/kg	520	--	1
Vinyl acetate	ND		ug/kg	520	--	1
4-Methyl-2-pentanone	ND		ug/kg	520	--	1
2-Hexanone	ND		ug/kg	520	--	1
Ethyl methacrylate	ND		ug/kg	520	--	1
Acrylonitrile	ND		ug/kg	210	--	1
Bromochloromethane	ND		ug/kg	260	--	1
Tetrahydrofuran	ND		ug/kg	1000	--	1
2,2-Dichloropropane	ND		ug/kg	260	--	1
1,2-Dibromoethane	ND		ug/kg	210	--	1
1,3-Dichloropropane	ND		ug/kg	260	--	1
1,1,1,2-Tetrachloroethane	ND		ug/kg	52	--	1
Bromobenzene	ND		ug/kg	260	--	1
n-Butylbenzene	ND		ug/kg	52	--	1
sec-Butylbenzene	ND		ug/kg	52	--	1
tert-Butylbenzene	ND		ug/kg	260	--	1
o-Chlorotoluene	ND		ug/kg	260	--	1
p-Chlorotoluene	ND		ug/kg	260	--	1
1,2-Dibromo-3-chloropropane	ND		ug/kg	260	--	1
Hexachlorobutadiene	ND		ug/kg	260	--	1
Isopropylbenzene	ND		ug/kg	52	--	1
p-Isopropyltoluene	ND		ug/kg	52	--	1
Naphthalene	ND		ug/kg	260	--	1
n-Propylbenzene	ND		ug/kg	52	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-02  
 Client ID: 1607530-B103(S3-S4)  
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 09:55  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Volatile Organics by EPA 5035 High - Westborough Lab						
1,2,3-Trichlorobenzene	ND		ug/kg	260	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	260	--	1
1,3,5-Trimethylbenzene	ND		ug/kg	260	--	1
1,2,4-Trimethylbenzene	ND		ug/kg	260	--	1
trans-1,4-Dichloro-2-butene	ND		ug/kg	260	--	1
Ethyl ether	ND		ug/kg	260	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	99		70-130
Toluene-d8	100		70-130
4-Bromofluorobenzene	98		70-130
Dibromofluoromethane	94		70-130



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-03  
 Client ID: 1607530-B102(S1-S2)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8260C  
 Analytical Date: 09/05/16 13:13  
 Analyst: BN  
 Percent Solids: 84%

Date Collected: 08/26/16 10:45  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by EPA 5035 High - Westborough Lab</b>						
Methylene chloride	ND		ug/kg	650	--	1
1,1-Dichloroethane	ND		ug/kg	97	--	1
Chloroform	ND		ug/kg	97	--	1
Carbon tetrachloride	ND		ug/kg	65	--	1
1,2-Dichloropropane	ND		ug/kg	230	--	1
Dibromochloromethane	ND		ug/kg	65	--	1
1,1,2-Trichloroethane	ND		ug/kg	97	--	1
Tetrachloroethene	ND		ug/kg	65	--	1
Chlorobenzene	ND		ug/kg	65	--	1
Trichlorofluoromethane	ND		ug/kg	320	--	1
1,2-Dichloroethane	ND		ug/kg	65	--	1
1,1,1-Trichloroethane	ND		ug/kg	65	--	1
Bromodichloromethane	ND		ug/kg	65	--	1
trans-1,3-Dichloropropene	ND		ug/kg	65	--	1
cis-1,3-Dichloropropene	ND		ug/kg	65	--	1
1,3-Dichloropropene, Total	ND		ug/kg	65	--	1
1,1-Dichloropropene	ND		ug/kg	320	--	1
Bromoform	ND		ug/kg	260	--	1
1,1,2,2-Tetrachloroethane	ND		ug/kg	65	--	1
Benzene	ND		ug/kg	65	--	1
Toluene	ND		ug/kg	97	--	1
Ethylbenzene	ND		ug/kg	65	--	1
Chloromethane	ND		ug/kg	320	--	1
Bromomethane	ND		ug/kg	130	--	1
Vinyl chloride	ND		ug/kg	130	--	1
Chloroethane	ND		ug/kg	130	--	1
1,1-Dichloroethene	ND		ug/kg	65	--	1
trans-1,2-Dichloroethene	ND		ug/kg	97	--	1
Trichloroethene	ND		ug/kg	65	--	1
1,2-Dichlorobenzene	ND		ug/kg	320	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

**Lab ID:** L1627010-03  
**Client ID:** 1607530-B102(S1-S2)  
**Sample Location:** NEWINGTON, NH

**Date Collected:** 08/26/16 10:45  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by EPA 5035 High - Westborough Lab</b>						
1,3-Dichlorobenzene	ND		ug/kg	320	--	1
1,4-Dichlorobenzene	ND		ug/kg	320	--	1
Methyl tert butyl ether	ND		ug/kg	130	--	1
p/m-Xylene	ND		ug/kg	130	--	1
o-Xylene	ND		ug/kg	130	--	1
Xylenes, Total	ND		ug/kg	130	--	1
cis-1,2-Dichloroethene	ND		ug/kg	65	--	1
1,2-Dichloroethene, Total	ND		ug/kg	65	--	1
Dibromomethane	ND		ug/kg	650	--	1
1,4-Dichlorobutane	ND		ug/kg	650	--	1
1,2,3-Trichloropropane	ND		ug/kg	650	--	1
Styrene	ND		ug/kg	130	--	1
Dichlorodifluoromethane	ND		ug/kg	650	--	1
Acetone	ND		ug/kg	2300	--	1
Carbon disulfide	ND		ug/kg	650	--	1
2-Butanone	ND		ug/kg	650	--	1
Vinyl acetate	ND		ug/kg	650	--	1
4-Methyl-2-pentanone	ND		ug/kg	650	--	1
2-Hexanone	ND		ug/kg	650	--	1
Ethyl methacrylate	ND		ug/kg	650	--	1
Acrylonitrile	ND		ug/kg	260	--	1
Bromochloromethane	ND		ug/kg	320	--	1
Tetrahydrofuran	ND		ug/kg	1300	--	1
2,2-Dichloropropane	ND		ug/kg	320	--	1
1,2-Dibromoethane	ND		ug/kg	260	--	1
1,3-Dichloropropane	ND		ug/kg	320	--	1
1,1,1,2-Tetrachloroethane	ND		ug/kg	65	--	1
Bromobenzene	ND		ug/kg	320	--	1
n-Butylbenzene	ND		ug/kg	65	--	1
sec-Butylbenzene	ND		ug/kg	65	--	1
tert-Butylbenzene	ND		ug/kg	320	--	1
o-Chlorotoluene	ND		ug/kg	320	--	1
p-Chlorotoluene	ND		ug/kg	320	--	1
1,2-Dibromo-3-chloropropane	ND		ug/kg	320	--	1
Hexachlorobutadiene	ND		ug/kg	320	--	1
Isopropylbenzene	ND		ug/kg	65	--	1
p-Isopropyltoluene	ND		ug/kg	65	--	1
Naphthalene	ND		ug/kg	320	--	1
n-Propylbenzene	ND		ug/kg	65	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

**Lab ID:** L1627010-03  
**Client ID:** 1607530-B102(S1-S2)  
**Sample Location:** NEWINGTON, NH

**Date Collected:** 08/26/16 10:45  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Volatile Organics by EPA 5035 High - Westborough Lab						
1,2,3-Trichlorobenzene	ND		ug/kg	320	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	320	--	1
1,3,5-Trimethylbenzene	ND		ug/kg	320	--	1
1,2,4-Trimethylbenzene	ND		ug/kg	320	--	1
trans-1,4-Dichloro-2-butene	ND		ug/kg	320	--	1
Ethyl ether	ND		ug/kg	320	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	96		70-130
Toluene-d8	101		70-130
4-Bromofluorobenzene	98		70-130
Dibromofluoromethane	94		70-130

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-04  
 Client ID: 1607530-B102(S3-S4)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8260C  
 Analytical Date: 09/05/16 13:40  
 Analyst: BN  
 Percent Solids: 79%

Date Collected: 08/26/16 11:00  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by EPA 5035 High - Westborough Lab</b>						
Methylene chloride	ND		ug/kg	480	--	1
1,1-Dichloroethane	ND		ug/kg	73	--	1
Chloroform	ND		ug/kg	73	--	1
Carbon tetrachloride	ND		ug/kg	48	--	1
1,2-Dichloropropane	ND		ug/kg	170	--	1
Dibromochloromethane	ND		ug/kg	48	--	1
1,1,2-Trichloroethane	ND		ug/kg	73	--	1
Tetrachloroethene	ND		ug/kg	48	--	1
Chlorobenzene	ND		ug/kg	48	--	1
Trichlorofluoromethane	ND		ug/kg	240	--	1
1,2-Dichloroethane	ND		ug/kg	48	--	1
1,1,1-Trichloroethane	ND		ug/kg	48	--	1
Bromodichloromethane	ND		ug/kg	48	--	1
trans-1,3-Dichloropropene	ND		ug/kg	48	--	1
cis-1,3-Dichloropropene	ND		ug/kg	48	--	1
1,3-Dichloropropene, Total	ND		ug/kg	48	--	1
1,1-Dichloropropene	ND		ug/kg	240	--	1
Bromoform	ND		ug/kg	190	--	1
1,1,2,2-Tetrachloroethane	ND		ug/kg	48	--	1
Benzene	ND		ug/kg	48	--	1
Toluene	ND		ug/kg	73	--	1
Ethylbenzene	ND		ug/kg	48	--	1
Chloromethane	ND		ug/kg	240	--	1
Bromomethane	ND		ug/kg	97	--	1
Vinyl chloride	ND		ug/kg	97	--	1
Chloroethane	ND		ug/kg	97	--	1
1,1-Dichloroethene	ND		ug/kg	48	--	1
trans-1,2-Dichloroethene	ND		ug/kg	73	--	1
Trichloroethene	ND		ug/kg	48	--	1
1,2-Dichlorobenzene	ND		ug/kg	240	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

**Lab ID:** L1627010-04  
**Client ID:** 1607530-B102(S3-S4)  
**Sample Location:** NEWINGTON, NH

**Date Collected:** 08/26/16 11:00  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by EPA 5035 High - Westborough Lab</b>						
1,3-Dichlorobenzene	ND		ug/kg	240	--	1
1,4-Dichlorobenzene	ND		ug/kg	240	--	1
Methyl tert butyl ether	ND		ug/kg	97	--	1
p/m-Xylene	ND		ug/kg	97	--	1
o-Xylene	ND		ug/kg	97	--	1
Xylenes, Total	ND		ug/kg	97	--	1
cis-1,2-Dichloroethene	ND		ug/kg	48	--	1
1,2-Dichloroethene, Total	ND		ug/kg	48	--	1
Dibromomethane	ND		ug/kg	480	--	1
1,4-Dichlorobutane	ND		ug/kg	480	--	1
1,2,3-Trichloropropane	ND		ug/kg	480	--	1
Styrene	ND		ug/kg	97	--	1
Dichlorodifluoromethane	ND		ug/kg	480	--	1
Acetone	ND		ug/kg	1700	--	1
Carbon disulfide	ND		ug/kg	480	--	1
2-Butanone	ND		ug/kg	480	--	1
Vinyl acetate	ND		ug/kg	480	--	1
4-Methyl-2-pentanone	ND		ug/kg	480	--	1
2-Hexanone	ND		ug/kg	480	--	1
Ethyl methacrylate	ND		ug/kg	480	--	1
Acrylonitrile	ND		ug/kg	190	--	1
Bromochloromethane	ND		ug/kg	240	--	1
Tetrahydrofuran	ND		ug/kg	970	--	1
2,2-Dichloropropane	ND		ug/kg	240	--	1
1,2-Dibromoethane	ND		ug/kg	190	--	1
1,3-Dichloropropane	ND		ug/kg	240	--	1
1,1,1,2-Tetrachloroethane	ND		ug/kg	48	--	1
Bromobenzene	ND		ug/kg	240	--	1
n-Butylbenzene	ND		ug/kg	48	--	1
sec-Butylbenzene	ND		ug/kg	48	--	1
tert-Butylbenzene	ND		ug/kg	240	--	1
o-Chlorotoluene	ND		ug/kg	240	--	1
p-Chlorotoluene	ND		ug/kg	240	--	1
1,2-Dibromo-3-chloropropane	ND		ug/kg	240	--	1
Hexachlorobutadiene	ND		ug/kg	240	--	1
Isopropylbenzene	ND		ug/kg	48	--	1
p-Isopropyltoluene	ND		ug/kg	48	--	1
Naphthalene	ND		ug/kg	240	--	1
n-Propylbenzene	ND		ug/kg	48	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

**Lab ID:** L1627010-04  
**Client ID:** 1607530-B102(S3-S4)  
**Sample Location:** NEWINGTON, NH

**Date Collected:** 08/26/16 11:00  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Volatile Organics by EPA 5035 High - Westborough Lab						
1,2,3-Trichlorobenzene	ND		ug/kg	240	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	240	--	1
1,3,5-Trimethylbenzene	ND		ug/kg	240	--	1
1,2,4-Trimethylbenzene	ND		ug/kg	240	--	1
trans-1,4-Dichloro-2-butene	ND		ug/kg	240	--	1
Ethyl ether	ND		ug/kg	240	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	97		70-130
Toluene-d8	101		70-130
4-Bromofluorobenzene	98		70-130
Dibromofluoromethane	93		70-130

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-05  
 Client ID: 1607530-B101(S1-S2)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8260C  
 Analytical Date: 09/05/16 14:06  
 Analyst: BN  
 Percent Solids: 84%

Date Collected: 08/26/16 11:45  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by EPA 5035 High - Westborough Lab</b>						
Methylene chloride	ND		ug/kg	650	--	1
1,1-Dichloroethane	ND		ug/kg	98	--	1
Chloroform	ND		ug/kg	98	--	1
Carbon tetrachloride	ND		ug/kg	65	--	1
1,2-Dichloropropane	ND		ug/kg	230	--	1
Dibromochloromethane	ND		ug/kg	65	--	1
1,1,2-Trichloroethane	ND		ug/kg	98	--	1
Tetrachloroethene	ND		ug/kg	65	--	1
Chlorobenzene	ND		ug/kg	65	--	1
Trichlorofluoromethane	ND		ug/kg	320	--	1
1,2-Dichloroethane	ND		ug/kg	65	--	1
1,1,1-Trichloroethane	ND		ug/kg	65	--	1
Bromodichloromethane	ND		ug/kg	65	--	1
trans-1,3-Dichloropropene	ND		ug/kg	65	--	1
cis-1,3-Dichloropropene	ND		ug/kg	65	--	1
1,3-Dichloropropene, Total	ND		ug/kg	65	--	1
1,1-Dichloropropene	ND		ug/kg	320	--	1
Bromoform	ND		ug/kg	260	--	1
1,1,2,2-Tetrachloroethane	ND		ug/kg	65	--	1
Benzene	ND		ug/kg	65	--	1
Toluene	ND		ug/kg	98	--	1
Ethylbenzene	ND		ug/kg	65	--	1
Chloromethane	ND		ug/kg	320	--	1
Bromomethane	ND		ug/kg	130	--	1
Vinyl chloride	ND		ug/kg	130	--	1
Chloroethane	ND		ug/kg	130	--	1
1,1-Dichloroethene	ND		ug/kg	65	--	1
trans-1,2-Dichloroethene	ND		ug/kg	98	--	1
Trichloroethene	ND		ug/kg	65	--	1
1,2-Dichlorobenzene	ND		ug/kg	320	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

**Lab ID:** L1627010-05  
**Client ID:** 1607530-B101(S1-S2)  
**Sample Location:** NEWINGTON, NH

**Date Collected:** 08/26/16 11:45  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by EPA 5035 High - Westborough Lab</b>						
1,3-Dichlorobenzene	ND		ug/kg	320	--	1
1,4-Dichlorobenzene	ND		ug/kg	320	--	1
Methyl tert butyl ether	ND		ug/kg	130	--	1
p/m-Xylene	ND		ug/kg	130	--	1
o-Xylene	ND		ug/kg	130	--	1
Xylenes, Total	ND		ug/kg	130	--	1
cis-1,2-Dichloroethene	ND		ug/kg	65	--	1
1,2-Dichloroethene, Total	ND		ug/kg	65	--	1
Dibromomethane	ND		ug/kg	650	--	1
1,4-Dichlorobutane	ND		ug/kg	650	--	1
1,2,3-Trichloropropane	ND		ug/kg	650	--	1
Styrene	ND		ug/kg	130	--	1
Dichlorodifluoromethane	ND		ug/kg	650	--	1
Acetone	ND		ug/kg	2300	--	1
Carbon disulfide	ND		ug/kg	650	--	1
2-Butanone	ND		ug/kg	650	--	1
Vinyl acetate	ND		ug/kg	650	--	1
4-Methyl-2-pentanone	ND		ug/kg	650	--	1
2-Hexanone	ND		ug/kg	650	--	1
Ethyl methacrylate	ND		ug/kg	650	--	1
Acrylonitrile	ND		ug/kg	260	--	1
Bromochloromethane	ND		ug/kg	320	--	1
Tetrahydrofuran	ND		ug/kg	1300	--	1
2,2-Dichloropropane	ND		ug/kg	320	--	1
1,2-Dibromoethane	ND		ug/kg	260	--	1
1,3-Dichloropropane	ND		ug/kg	320	--	1
1,1,1,2-Tetrachloroethane	ND		ug/kg	65	--	1
Bromobenzene	ND		ug/kg	320	--	1
n-Butylbenzene	ND		ug/kg	65	--	1
sec-Butylbenzene	ND		ug/kg	65	--	1
tert-Butylbenzene	ND		ug/kg	320	--	1
o-Chlorotoluene	ND		ug/kg	320	--	1
p-Chlorotoluene	ND		ug/kg	320	--	1
1,2-Dibromo-3-chloropropane	ND		ug/kg	320	--	1
Hexachlorobutadiene	ND		ug/kg	320	--	1
Isopropylbenzene	ND		ug/kg	65	--	1
p-Isopropyltoluene	ND		ug/kg	65	--	1
Naphthalene	ND		ug/kg	320	--	1
n-Propylbenzene	ND		ug/kg	65	--	1



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

**Lab ID:** L1627010-05  
**Client ID:** 1607530-B101(S1-S2)  
**Sample Location:** NEWINGTON, NH

**Date Collected:** 08/26/16 11:45  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Volatile Organics by EPA 5035 High - Westborough Lab						
1,2,3-Trichlorobenzene	ND		ug/kg	320	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	320	--	1
1,3,5-Trimethylbenzene	ND		ug/kg	320	--	1
1,2,4-Trimethylbenzene	ND		ug/kg	320	--	1
trans-1,4-Dichloro-2-butene	ND		ug/kg	320	--	1
Ethyl ether	ND		ug/kg	320	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	98		70-130
Toluene-d8	101		70-130
4-Bromofluorobenzene	97		70-130
Dibromofluoromethane	94		70-130

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-06  
 Client ID: 1607530-B101(S3-S4)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8260C  
 Analytical Date: 09/05/16 14:33  
 Analyst: BN  
 Percent Solids: 81%

Date Collected: 08/26/16 12:00  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by EPA 5035 High - Westborough Lab</b>						
Methylene chloride	ND		ug/kg	480	--	1
1,1-Dichloroethane	ND		ug/kg	71	--	1
Chloroform	ND		ug/kg	71	--	1
Carbon tetrachloride	ND		ug/kg	48	--	1
1,2-Dichloropropane	ND		ug/kg	170	--	1
Dibromochloromethane	ND		ug/kg	48	--	1
1,1,2-Trichloroethane	ND		ug/kg	71	--	1
Tetrachloroethene	ND		ug/kg	48	--	1
Chlorobenzene	ND		ug/kg	48	--	1
Trichlorofluoromethane	ND		ug/kg	240	--	1
1,2-Dichloroethane	ND		ug/kg	48	--	1
1,1,1-Trichloroethane	ND		ug/kg	48	--	1
Bromodichloromethane	ND		ug/kg	48	--	1
trans-1,3-Dichloropropene	ND		ug/kg	48	--	1
cis-1,3-Dichloropropene	ND		ug/kg	48	--	1
1,3-Dichloropropene, Total	ND		ug/kg	48	--	1
1,1-Dichloropropene	ND		ug/kg	240	--	1
Bromoform	ND		ug/kg	190	--	1
1,1,2,2-Tetrachloroethane	ND		ug/kg	48	--	1
Benzene	ND		ug/kg	48	--	1
Toluene	ND		ug/kg	71	--	1
Ethylbenzene	ND		ug/kg	48	--	1
Chloromethane	ND		ug/kg	240	--	1
Bromomethane	ND		ug/kg	95	--	1
Vinyl chloride	ND		ug/kg	95	--	1
Chloroethane	ND		ug/kg	95	--	1
1,1-Dichloroethene	ND		ug/kg	48	--	1
trans-1,2-Dichloroethene	ND		ug/kg	71	--	1
Trichloroethene	ND		ug/kg	48	--	1
1,2-Dichlorobenzene	ND		ug/kg	240	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-06  
 Client ID: 1607530-B101(S3-S4)  
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 12:00  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Volatile Organics by EPA 5035 High - Westborough Lab</b>						
1,3-Dichlorobenzene	ND		ug/kg	240	--	1
1,4-Dichlorobenzene	ND		ug/kg	240	--	1
Methyl tert butyl ether	ND		ug/kg	95	--	1
p/m-Xylene	ND		ug/kg	95	--	1
o-Xylene	ND		ug/kg	95	--	1
Xylenes, Total	ND		ug/kg	95	--	1
cis-1,2-Dichloroethene	ND		ug/kg	48	--	1
1,2-Dichloroethene, Total	ND		ug/kg	48	--	1
Dibromomethane	ND		ug/kg	480	--	1
1,4-Dichlorobutane	ND		ug/kg	480	--	1
1,2,3-Trichloropropane	ND		ug/kg	480	--	1
Styrene	ND		ug/kg	95	--	1
Dichlorodifluoromethane	ND		ug/kg	480	--	1
Acetone	ND		ug/kg	1700	--	1
Carbon disulfide	ND		ug/kg	480	--	1
2-Butanone	ND		ug/kg	480	--	1
Vinyl acetate	ND		ug/kg	480	--	1
4-Methyl-2-pentanone	ND		ug/kg	480	--	1
2-Hexanone	ND		ug/kg	480	--	1
Ethyl methacrylate	ND		ug/kg	480	--	1
Acrylonitrile	ND		ug/kg	190	--	1
Bromochloromethane	ND		ug/kg	240	--	1
Tetrahydrofuran	ND		ug/kg	950	--	1
2,2-Dichloropropane	ND		ug/kg	240	--	1
1,2-Dibromoethane	ND		ug/kg	190	--	1
1,3-Dichloropropane	ND		ug/kg	240	--	1
1,1,1,2-Tetrachloroethane	ND		ug/kg	48	--	1
Bromobenzene	ND		ug/kg	240	--	1
n-Butylbenzene	ND		ug/kg	48	--	1
sec-Butylbenzene	ND		ug/kg	48	--	1
tert-Butylbenzene	ND		ug/kg	240	--	1
o-Chlorotoluene	ND		ug/kg	240	--	1
p-Chlorotoluene	ND		ug/kg	240	--	1
1,2-Dibromo-3-chloropropane	ND		ug/kg	240	--	1
Hexachlorobutadiene	ND		ug/kg	240	--	1
Isopropylbenzene	ND		ug/kg	48	--	1
p-Isopropyltoluene	ND		ug/kg	48	--	1
Naphthalene	ND		ug/kg	240	--	1
n-Propylbenzene	ND		ug/kg	48	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-06  
 Client ID: 1607530-B101(S3-S4)  
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 12:00  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Volatile Organics by EPA 5035 High - Westborough Lab						
1,2,3-Trichlorobenzene	ND		ug/kg	240	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	240	--	1
1,3,5-Trimethylbenzene	ND		ug/kg	240	--	1
1,2,4-Trimethylbenzene	ND		ug/kg	240	--	1
trans-1,4-Dichloro-2-butene	ND		ug/kg	240	--	1
Ethyl ether	ND		ug/kg	240	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	97		70-130
Toluene-d8	101		70-130
4-Bromofluorobenzene	98		70-130
Dibromofluoromethane	93		70-130

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**Method Blank Analysis**  
**Batch Quality Control**

Analytical Method: 1,8260C  
Analytical Date: 09/05/16 08:21  
Analyst: BN

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by EPA 5035 High - Westborough Lab for sample(s): 01-06 Batch: WG929175-5					
Methylene chloride	ND		ug/kg	500	--
1,1-Dichloroethane	ND		ug/kg	75	--
Chloroform	ND		ug/kg	75	--
Carbon tetrachloride	ND		ug/kg	50	--
1,2-Dichloropropane	ND		ug/kg	180	--
Dibromochloromethane	ND		ug/kg	50	--
1,1,2-Trichloroethane	ND		ug/kg	75	--
2-Chloroethylvinyl ether	ND		ug/kg	1000	--
Tetrachloroethene	ND		ug/kg	50	--
Chlorobenzene	ND		ug/kg	50	--
Trichlorofluoromethane	ND		ug/kg	250	--
1,2-Dichloroethane	ND		ug/kg	50	--
1,1,1-Trichloroethane	ND		ug/kg	50	--
Bromodichloromethane	ND		ug/kg	50	--
trans-1,3-Dichloropropene	ND		ug/kg	50	--
cis-1,3-Dichloropropene	ND		ug/kg	50	--
1,3-Dichloropropene, Total	ND		ug/kg	50	--
1,1-Dichloropropene	ND		ug/kg	250	--
Bromoform	ND		ug/kg	200	--
1,1,2,2-Tetrachloroethane	ND		ug/kg	50	--
Benzene	ND		ug/kg	50	--
Toluene	ND		ug/kg	75	--
Ethy benzene	ND		ug/kg	50	--
Chloromethane	ND		ug/kg	250	--
Bromomethane	ND		ug/kg	100	--
Vinyl chloride	ND		ug/kg	100	--
Chloroethane	ND		ug/kg	100	--
1,1-Dichloroethene	ND		ug/kg	50	--
trans-1,2-Dichloroethene	ND		ug/kg	75	--

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**Method Blank Analysis**  
**Batch Quality Control**

Analytical Method: 1,8260C  
Analytical Date: 09/05/16 08:21  
Analyst: BN

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by EPA 5035 High - Westborough Lab for sample(s): 01-06 Batch: WG929175-5					
Trichloroethene	ND		ug/kg	50	--
1,2-Dichlorobenzene	ND		ug/kg	250	--
1,3-Dichlorobenzene	ND		ug/kg	250	--
1,4-Dichlorobenzene	ND		ug/kg	250	--
Methyl tert butyl ether	ND		ug/kg	100	--
p/m-Xylene	ND		ug/kg	100	--
o-Xylene	ND		ug/kg	100	--
Xylenes, Total	ND		ug/kg	100	--
cis-1,2-Dichloroethene	ND		ug/kg	50	--
1,2-Dichloroethene, Total	ND		ug/kg	50	--
Dibromomethane	ND		ug/kg	500	--
1,4-Dichlorobutane	ND		ug/kg	500	--
1,2,3-Trichloropropane	ND		ug/kg	500	--
Styrene	ND		ug/kg	100	--
Dichlorodifluoromethane	ND		ug/kg	500	--
Acetone	ND		ug/kg	1800	--
Carbon disulfide	ND		ug/kg	500	--
2-Butanone	ND		ug/kg	500	--
Vinyl acetate	ND		ug/kg	500	--
4-Methyl-2-pentanone	ND		ug/kg	500	--
2-Hexanone	ND		ug/kg	500	--
Ethyl methacrylate	ND		ug/kg	500	--
Acrolein	ND		ug/kg	1200	--
Acrylonitrile	ND		ug/kg	200	--
Bromochloromethane	ND		ug/kg	250	--
Tetrahydrofuran	ND		ug/kg	1000	--
2,2-Dichloropropane	ND		ug/kg	250	--
1,2-Dibromoethane	ND		ug/kg	200	--
1,3-Dichloropropane	ND		ug/kg	250	--

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**Method Blank Analysis**  
**Batch Quality Control**

Analytical Method: 1,8260C  
 Analytical Date: 09/05/16 08:21  
 Analyst: BN

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by EPA 5035 High - Westborough Lab for sample(s): 01-06 Batch: WG929175-5					
1,1,1,2-Tetrachloroethane	ND		ug/kg	50	--
Bromobenzene	ND		ug/kg	250	--
n-Buty benzene	ND		ug/kg	50	--
sec-Buty benzene	ND		ug/kg	50	--
tert-Butylbenzene	ND		ug/kg	250	--
1,3,5-Trichlorobenzene	ND		ug/kg	200	--
o-Chlorotoluene	ND		ug/kg	250	--
p-Chlorotoluene	ND		ug/kg	250	--
1,2-Dibromo-3-chloropropane	ND		ug/kg	250	--
Hexachlorobutadiene	ND		ug/kg	250	--
Isopropylbenzene	ND		ug/kg	50	--
p-Isopropyltoluene	ND		ug/kg	50	--
Naphthalene	ND		ug/kg	250	--
n-Propy benzene	ND		ug/kg	50	--
1,2,3-Trichlorobenzene	ND		ug/kg	250	--
1,2,4-Trichlorobenzene	ND		ug/kg	250	--
1,3,5-Trimethylbenzene	ND		ug/kg	250	--
1,2,4-Trimethylbenzene	ND		ug/kg	250	--
trans-1,4-Dichloro-2-butene	ND		ug/kg	250	--
Halothane	ND		ug/kg	2000	--
Ethyl ether	ND		ug/kg	250	--
Methyl Acetate	ND		ug/kg	1000	--
Ethyl Acetate	ND		ug/kg	1000	--
Isopropyl Ether	ND		ug/kg	200	--
Cyclohexane	ND		ug/kg	1000	--
Tert-Butyl Alcohol	ND		ug/kg	5000	--
Ethyl-Tert-Butyl-Ether	ND		ug/kg	200	--
Tertiary-Amyl Methyl Ether	ND		ug/kg	200	--
1,4-Dioxane	ND		ug/kg	5000	--

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**Method Blank Analysis**  
**Batch Quality Control**

Analytical Method: 1,8260C  
 Analytical Date: 09/05/16 08:21  
 Analyst: BN

Parameter	Result	Qualifier	Units	RL	MDL
Volatile Organics by EPA 5035 High - Westborough Lab for sample(s): 01-06 Batch: WG929175-5					
Methyl cyclohexane	ND		ug/kg	200	--
1,1,2-Trichloro-1,2,2-Trifluoroethane	ND		ug/kg	1000	--
p-Diethylbenzene	ND		ug/kg	200	--
4-Ethyltoluene	ND		ug/kg	200	--
1,2,4,5-Tetramethylbenzene	ND		ug/kg	200	--

Surrogate	%Recovery	Qualifier	Acceptance Criteria
1,2-Dichloroethane-d4	98		70-130
Toluene-d8	99		70-130
4-Bromofluorobenzene	98		70-130
D bromofluoromethane	96		70-130



## Lab Control Sample Analysis

### Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by EPA 5035 High - Westborough Lab Associated sample(s): 01-06 Batch: WG929175-3 WG929175-4								
Methylene chloride	89		87		70-130	2		30
1,1-Dichloroethane	96		95		70-130	1		30
Chloroform	95		93		70-130	2		30
Carbon tetrachloride	93		91		70-130	2		30
1,2-Dichloropropane	94		92		70-130	2		30
Dibromochloromethane	92		92		70-130	0		30
1,1,2-Trichloroethane	94		93		70-130	1		30
2-Chloroethylvinyl ether	94		93		70-130	1		30
Tetrachloroethene	103		98		70-130	5		30
Chlorobenzene	96		94		70-130	2		30
Trichlorofluoromethane	112		107		70-139	5		30
1,2-Dichloroethane	93		92		70-130	1		30
1,1,1-Trichloroethane	95		93		70-130	2		30
Bromodichloromethane	92		89		70-130	3		30
trans-1,3-Dichloropropene	96		94		70-130	2		30
cis-1,3-Dichloropropene	95		95		70-130	0		30
1,1-Dichloropropene	107		104		70-130	3		30
Bromoform	83		83		70-130	0		30
1,1,2,2-Tetrachloroethane	94		93		70-130	1		30
Benzene	97		94		70-130	3		30
Toluene	97		94		70-130	3		30

## Lab Control Sample Analysis

### Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by EPA 5035 High - Westborough Lab Associated sample(s): 01-06 Batch: WG929175-3 WG929175-4								
Ethylbenzene	99		95		70-130	4		30
Chloromethane	115		111		52-130	4		30
Bromomethane	109		103		57-147	6		30
Vinyl chloride	104		99		67-130	5		30
Chloroethane	112		104		50-151	7		30
1,1-Dichloroethene	89		85		65-135	5		30
trans-1,2-Dichloroethene	99		95		70-130	4		30
Trichloroethene	98		94		70-130	4		30
1,2-Dichlorobenzene	99		98		70-130	1		30
1,3-Dichlorobenzene	100		98		70-130	2		30
1,4-Dichlorobenzene	99		97		70-130	2		30
Methyl tert butyl ether	92		91		66-130	1		30
p/m-Xylene	101		97		70-130	4		30
o-Xylene	101		98		70-130	3		30
cis-1,2-Dichloroethene	97		94		70-130	3		30
Dibromomethane	91		90		70-130	1		30
1,4-Dichlorobutane	94		92		70-130	2		30
1,2,3-Trichloropropane	94		94		68-130	0		30
Styrene	100		97		70-130	3		30
Dichlorodifluoromethane	118		112		30-146	5		30
Acetone	86		86		54-140	0		30

## Lab Control Sample Analysis

### Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by EPA 5035 High - Westborough Lab Associated sample(s): 01-06 Batch: WG929175-3 WG929175-4								
Carbon disulfide	73		72		59-130	1		30
2-Butanone	77		78		70-130	1		30
Vinyl acetate	95		96		70-130	1		30
4-Methyl-2-pentanone	89		88		70-130	1		30
2-Hexanone	86		86		70-130	0		30
Ethyl methacrylate	84		83		70-130	1		30
Acrolein	44	Q	47	Q	70-130	7		30
Acrylonitrile	84		83		70-130	1		30
Bromochloromethane	97		95		70-130	2		30
Tetrahydrofuran	84		85		66-130	1		30
2,2-Dichloropropane	97		94		70-130	3		30
1,2-Dibromoethane	94		92		70-130	2		30
1,3-Dichloropropane	96		94		69-130	2		30
1,1,1,2-Tetrachloroethane	95		93		70-130	2		30
Bromobenzene	100		97		70-130	3		30
n-Butylbenzene	109		106		70-130	3		30
sec-Butylbenzene	104		101		70-130	3		30
tert-Butylbenzene	103		100		70-130	3		30
1,3,5-Trichlorobenzene	104		102		70-139	2		30
o-Chlorotoluene	98		95		70-130	3		30
p-Chlorotoluene	98		97		70-130	1		30

## Lab Control Sample Analysis

### Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by EPA 5035 High - Westborough Lab Associated sample(s): 01-06 Batch: WG929175-3 WG929175-4								
1,2-Dibromo-3-chloropropane	84		87		68-130	4		30
Hexachlorobutadiene	107		104		67-130	3		30
Isopropylbenzene	102		98		70-130	4		30
p-Isopropyltoluene	106		103		70-130	3		30
Naphthalene	96		95		70-130	1		30
n-Propylbenzene	104		101		70-130	3		30
1,2,3-Trichlorobenzene	101		100		70-130	1		30
1,2,4-Trichlorobenzene	103		102		70-130	1		30
1,3,5-Trimethylbenzene	102		98		70-130	4		30
1,2,4-Trimethylbenzene	103		101		70-130	2		30
trans-1,4-Dichloro-2-butene	90		90		70-130	0		30
Halothane	107		105		70-130	2		20
Ethyl ether	105		102		67-130	3		30
Methyl Acetate	101		100		65-130	1		30
Ethyl Acetate	92		94		70-130	2		30
Isopropyl Ether	93		92		66-130	1		30
Cyclohexane	108		105		70-130	3		30
Tert-Butyl Alcohol	76		76		70-130	0		30
Ethyl-Tert-Butyl-Ether	94		93		70-130	1		30
Tertiary-Amyl Methyl Ether	91		90		70-130	1		30
1,4-Dioxane	78		75		65-136	4		30

## Lab Control Sample Analysis

### Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Volatile Organics by EPA 5035 High - Westborough Lab Associated sample(s): 01-06 Batch: WG929175-3 WG929175-4								
Methyl cyclohexane	114		109		70-130	4		30
1,1,2-Trichloro-1,2,2-Trifluoroethane	101		96		70-130	5		30
p-Diethylbenzene	107		104		70-130	3		30
4-Ethyltoluene	109		105		70-130	4		30
1,2,4,5-Tetramethylbenzene	105		103		70-130	2		30

Surrogate	LCS %Recovery	Qual	LCSD %Recovery	Qual	Acceptance Criteria
1,2-Dichloroethane-d4	95		97		70-130
Toluene-d8	101		100		70-130
4-Bromofluorobenzene	101		100		70-130
Dibromofluoromethane	100		100		70-130

# SEMIVOLATILES

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-01  
 Client ID: 1607530-B103(S1-S2)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8270D  
 Analytical Date: 09/02/16 04:52  
 Analyst: KV  
 Percent Solids: 93%

Date Collected: 08/26/16 09:25  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Semivolatile Organics by GC/MS - Westborough Lab</b>						
Acenaphthene	ND		ug/kg	140	--	1
Benzidine	ND		ug/kg	580	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	180	--	1
Hexachlorobenzene	ND		ug/kg	110	--	1
Bis(2-chloroethyl)ether	ND		ug/kg	160	--	1
2-Chloronaphthalene	ND		ug/kg	180	--	1
1,2-Dichlorobenzene	ND		ug/kg	180	--	1
1,3-Dichlorobenzene	ND		ug/kg	180	--	1
1,4-Dichlorobenzene	ND		ug/kg	180	--	1
3,3'-Dichlorobenzidine	ND		ug/kg	180	--	1
2,4-Dinitrotoluene	ND		ug/kg	180	--	1
2,6-Dinitrotoluene	ND		ug/kg	180	--	1
Azobenzene	ND		ug/kg	180	--	1
Fluoranthene	ND		ug/kg	110	--	1
4-Chlorophenyl phenyl ether	ND		ug/kg	180	--	1
4-Bromophenyl phenyl ether	ND		ug/kg	180	--	1
Bis(2-chloroisopropyl)ether	ND		ug/kg	210	--	1
Bis(2-chloroethoxy)methane	ND		ug/kg	190	--	1
Hexachlorobutadiene	ND		ug/kg	180	--	1
Hexachlorocyclopentadiene	ND		ug/kg	500	--	1
Hexachloroethane	ND		ug/kg	140	--	1
Isophorone	ND		ug/kg	160	--	1
Naphthalene	ND		ug/kg	180	--	1
Nitrobenzene	ND		ug/kg	160	--	1
NDPA/DPA	ND		ug/kg	140	--	1
n-Nitrosodi-n-propylamine	ND		ug/kg	180	--	1
Bis(2-ethylhexyl)phthalate	ND		ug/kg	180	--	1
Butyl benzyl phthalate	ND		ug/kg	180	--	1
Di-n-butylphthalate	ND		ug/kg	180	--	1
Di-n-octylphthalate	ND		ug/kg	180	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-01  
 Client ID: 1607530-B103(S1-S2)  
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 09:25  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Semivolatile Organics by GC/MS - Westborough Lab</b>						
Diethyl phthalate	ND		ug/kg	180	--	1
Dimethyl phthalate	ND		ug/kg	180	--	1
Benzo(a)anthracene	ND		ug/kg	110	--	1
Benzo(a)pyrene	ND		ug/kg	140	--	1
Benzo(b)fluoranthene	ND		ug/kg	110	--	1
Benzo(k)fluoranthene	ND		ug/kg	110	--	1
Chrysene	ND		ug/kg	110	--	1
Acenaphthylene	ND		ug/kg	140	--	1
Anthracene	ND		ug/kg	110	--	1
Benzo(ghi)perylene	ND		ug/kg	140	--	1
Fluorene	ND		ug/kg	180	--	1
Phenanthrene	ND		ug/kg	110	--	1
Dibenzo(a,h)anthracene	ND		ug/kg	110	--	1
Indeno(1,2,3-cd)pyrene	ND		ug/kg	140	--	1
Pyrene	ND		ug/kg	110	--	1
Biphenyl	ND		ug/kg	400	--	1
Aniline	ND		ug/kg	210	--	1
4-Chloroaniline	ND		ug/kg	180	--	1
1-Methylnaphthalene	ND		ug/kg	180	--	1
2-Nitroaniline	ND		ug/kg	180	--	1
3-Nitroaniline	ND		ug/kg	180	--	1
4-Nitroaniline	ND		ug/kg	180	--	1
Dibenzofuran	ND		ug/kg	180	--	1
2-Methylnaphthalene	ND		ug/kg	210	--	1
n-Nitrosodimethylamine	ND		ug/kg	350	--	1
2,4,6-Trichlorophenol	ND		ug/kg	110	--	1
p-Chloro-m-cresol	ND		ug/kg	180	--	1
2-Chlorophenol	ND		ug/kg	180	--	1
2,4-Dichlorophenol	ND		ug/kg	160	--	1
2,4-Dimethylphenol	ND		ug/kg	180	--	1
2-Nitrophenol	ND		ug/kg	380	--	1
4-Nitrophenol	ND		ug/kg	250	--	1
2,4-Dinitrophenol	ND		ug/kg	850	--	1
4,6-Dinitro-o-cresol	ND		ug/kg	460	--	1
Pentachlorophenol	ND		ug/kg	140	--	1
Phenol	ND		ug/kg	180	--	1
2-Methylphenol	ND		ug/kg	180	--	1
3-Methylphenol/4-Methylphenol	ND		ug/kg	250	--	1
2,4,5-Trichlorophenol	ND		ug/kg	180	--	1



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-01  
 Client ID: 1607530-B103(S1-S2)  
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 09:25  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

## Semivolatile Organics by GC/MS - Westborough Lab

Benzoic Acid	ND		ug/kg	570	--	1
Benzyl Alcohol	ND		ug/kg	180	--	1
Carbazole	ND		ug/kg	180	--	1
Pyridine	ND		ug/kg	710	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	98		25-120
Phenol-d6	101		10-120
Nitrobenzene-d5	103		23-120
2-Fluorobiphenyl	83		30-120
2,4,6-Tribromophenol	89		10-136
4-Terphenyl-d14	84		18-120

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-02  
 Client ID: 1607530-B103(S3-S4)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8270D  
 Analytical Date: 09/02/16 05:18  
 Analyst: KV  
 Percent Solids: 92%

Date Collected: 08/26/16 09:55  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Semivolatile Organics by GC/MS - Westborough Lab</b>						
Acenaphthene	ND		ug/kg	140	--	1
Benzidine	ND		ug/kg	580	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	180	--	1
Hexachlorobenzene	ND		ug/kg	100	--	1
Bis(2-chloroethyl)ether	ND		ug/kg	160	--	1
2-Chloronaphthalene	ND		ug/kg	180	--	1
1,2-Dichlorobenzene	ND		ug/kg	180	--	1
1,3-Dichlorobenzene	ND		ug/kg	180	--	1
1,4-Dichlorobenzene	ND		ug/kg	180	--	1
3,3'-Dichlorobenzidine	ND		ug/kg	180	--	1
2,4-Dinitrotoluene	ND		ug/kg	180	--	1
2,6-Dinitrotoluene	ND		ug/kg	180	--	1
Azobenzene	ND		ug/kg	180	--	1
Fluoranthene	ND		ug/kg	100	--	1
4-Chlorophenyl phenyl ether	ND		ug/kg	180	--	1
4-Bromophenyl phenyl ether	ND		ug/kg	180	--	1
Bis(2-chloroisopropyl)ether	ND		ug/kg	210	--	1
Bis(2-chloroethoxy)methane	ND		ug/kg	190	--	1
Hexachlorobutadiene	ND		ug/kg	180	--	1
Hexachlorocyclopentadiene	ND		ug/kg	500	--	1
Hexachloroethane	ND		ug/kg	140	--	1
Isophorone	ND		ug/kg	160	--	1
Naphthalene	ND		ug/kg	180	--	1
Nitrobenzene	ND		ug/kg	160	--	1
NDPA/DPA	ND		ug/kg	140	--	1
n-Nitrosodi-n-propylamine	ND		ug/kg	180	--	1
Bis(2-ethylhexyl)phthalate	ND		ug/kg	180	--	1
Butyl benzyl phthalate	ND		ug/kg	180	--	1
Di-n-butylphthalate	ND		ug/kg	180	--	1
Di-n-octylphthalate	ND		ug/kg	180	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-02  
 Client ID: 1607530-B103(S3-S4)  
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 09:55  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Semivolatile Organics by GC/MS - Westborough Lab</b>						
Diethyl phthalate	ND		ug/kg	180	--	1
Dimethyl phthalate	ND		ug/kg	180	--	1
Benzo(a)anthracene	ND		ug/kg	100	--	1
Benzo(a)pyrene	ND		ug/kg	140	--	1
Benzo(b)fluoranthene	ND		ug/kg	100	--	1
Benzo(k)fluoranthene	ND		ug/kg	100	--	1
Chrysene	ND		ug/kg	100	--	1
Acenaphthylene	ND		ug/kg	140	--	1
Anthracene	ND		ug/kg	100	--	1
Benzo(ghi)perylene	ND		ug/kg	140	--	1
Fluorene	ND		ug/kg	180	--	1
Phenanthrene	ND		ug/kg	100	--	1
Dibenzo(a,h)anthracene	ND		ug/kg	100	--	1
Indeno(1,2,3-cd)pyrene	ND		ug/kg	140	--	1
Pyrene	ND		ug/kg	100	--	1
Biphenyl	ND		ug/kg	400	--	1
Aniline	ND		ug/kg	210	--	1
4-Chloroaniline	ND		ug/kg	180	--	1
1-Methylnaphthalene	ND		ug/kg	180	--	1
2-Nitroaniline	ND		ug/kg	180	--	1
3-Nitroaniline	ND		ug/kg	180	--	1
4-Nitroaniline	ND		ug/kg	180	--	1
Dibenzofuran	ND		ug/kg	180	--	1
2-Methylnaphthalene	ND		ug/kg	210	--	1
n-Nitrosodimethylamine	ND		ug/kg	350	--	1
2,4,6-Trichlorophenol	ND		ug/kg	100	--	1
p-Chloro-m-cresol	ND		ug/kg	180	--	1
2-Chlorophenol	ND		ug/kg	180	--	1
2,4-Dichlorophenol	ND		ug/kg	160	--	1
2,4-Dimethylphenol	ND		ug/kg	180	--	1
2-Nitrophenol	ND		ug/kg	380	--	1
4-Nitrophenol	ND		ug/kg	250	--	1
2,4-Dinitrophenol	ND		ug/kg	840	--	1
4,6-Dinitro-o-cresol	ND		ug/kg	460	--	1
Pentachlorophenol	ND		ug/kg	140	--	1
Phenol	ND		ug/kg	180	--	1
2-Methylphenol	ND		ug/kg	180	--	1
3-Methylphenol/4-Methylphenol	ND		ug/kg	250	--	1
2,4,5-Trichlorophenol	ND		ug/kg	180	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-02  
 Client ID: 1607530-B103(S3-S4)  
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 09:55  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

## Semivolatile Organics by GC/MS - Westborough Lab

Benzoic Acid	ND		ug/kg	570	--	1
Benzyl Alcohol	ND		ug/kg	180	--	1
Carbazole	ND		ug/kg	180	--	1
Pyridine	ND		ug/kg	700	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	93		25-120
Phenol-d6	98		10-120
Nitrobenzene-d5	98		23-120
2-Fluorobiphenyl	85		30-120
2,4,6-Tribromophenol	92		10-136
4-Terphenyl-d14	93		18-120

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-03  
 Client ID: 1607530-B102(S1-S2)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8270D  
 Analytical Date: 09/02/16 05:43  
 Analyst: KV  
 Percent Solids: 84%

Date Collected: 08/26/16 10:45  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Semivolatile Organics by GC/MS - Westborough Lab</b>						
Acenaphthene	ND		ug/kg	150	--	1
Benzidine	ND		ug/kg	640	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	190	--	1
Hexachlorobenzene	ND		ug/kg	120	--	1
Bis(2-chloroethyl)ether	ND		ug/kg	170	--	1
2-Chloronaphthalene	ND		ug/kg	190	--	1
1,2-Dichlorobenzene	ND		ug/kg	190	--	1
1,3-Dichlorobenzene	ND		ug/kg	190	--	1
1,4-Dichlorobenzene	ND		ug/kg	190	--	1
3,3'-Dichlorobenzidine	ND		ug/kg	190	--	1
2,4-Dinitrotoluene	ND		ug/kg	190	--	1
2,6-Dinitrotoluene	ND		ug/kg	190	--	1
Azobenzene	ND		ug/kg	190	--	1
Fluoranthene	ND		ug/kg	120	--	1
4-Chlorophenyl phenyl ether	ND		ug/kg	190	--	1
4-Bromophenyl phenyl ether	ND		ug/kg	190	--	1
Bis(2-chloroisopropyl)ether	ND		ug/kg	230	--	1
Bis(2-chloroethoxy)methane	ND		ug/kg	210	--	1
Hexachlorobutadiene	ND		ug/kg	190	--	1
Hexachlorocyclopentadiene	ND		ug/kg	550	--	1
Hexachloroethane	ND		ug/kg	150	--	1
Isophorone	ND		ug/kg	170	--	1
Naphthalene	ND		ug/kg	190	--	1
Nitrobenzene	ND		ug/kg	170	--	1
NDPA/DPA	ND		ug/kg	150	--	1
n-Nitrosodi-n-propylamine	ND		ug/kg	190	--	1
Bis(2-ethylhexyl)phthalate	ND		ug/kg	190	--	1
Butyl benzyl phthalate	ND		ug/kg	190	--	1
Di-n-butylphthalate	ND		ug/kg	190	--	1
Di-n-octylphthalate	ND		ug/kg	190	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-03  
 Client ID: 1607530-B102(S1-S2)  
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 10:45  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Semivolatile Organics by GC/MS - Westborough Lab</b>						
Diethyl phthalate	ND		ug/kg	190	--	1
Dimethyl phthalate	ND		ug/kg	190	--	1
Benzo(a)anthracene	ND		ug/kg	120	--	1
Benzo(a)pyrene	ND		ug/kg	150	--	1
Benzo(b)fluoranthene	ND		ug/kg	120	--	1
Benzo(k)fluoranthene	ND		ug/kg	120	--	1
Chrysene	ND		ug/kg	120	--	1
Acenaphthylene	ND		ug/kg	150	--	1
Anthracene	ND		ug/kg	120	--	1
Benzo(ghi)perylene	ND		ug/kg	150	--	1
Fluorene	ND		ug/kg	190	--	1
Phenanthrene	ND		ug/kg	120	--	1
Dibenzo(a,h)anthracene	ND		ug/kg	120	--	1
Indeno(1,2,3-cd)pyrene	ND		ug/kg	150	--	1
Pyrene	ND		ug/kg	120	--	1
Biphenyl	ND		ug/kg	440	--	1
Aniline	ND		ug/kg	230	--	1
4-Chloroaniline	ND		ug/kg	190	--	1
1-Methylnaphthalene	ND		ug/kg	190	--	1
2-Nitroaniline	ND		ug/kg	190	--	1
3-Nitroaniline	ND		ug/kg	190	--	1
4-Nitroaniline	ND		ug/kg	190	--	1
Dibenzofuran	ND		ug/kg	190	--	1
2-Methylnaphthalene	ND		ug/kg	230	--	1
n-Nitrosodimethylamine	ND		ug/kg	390	--	1
2,4,6-Trichlorophenol	ND		ug/kg	120	--	1
p-Chloro-m-cresol	ND		ug/kg	190	--	1
2-Chlorophenol	ND		ug/kg	190	--	1
2,4-Dichlorophenol	ND		ug/kg	170	--	1
2,4-Dimethylphenol	ND		ug/kg	190	--	1
2-Nitrophenol	ND		ug/kg	420	--	1
4-Nitrophenol	ND		ug/kg	270	--	1
2,4-Dinitrophenol	ND		ug/kg	930	--	1
4,6-Dinitro-o-cresol	ND		ug/kg	500	--	1
Pentachlorophenol	ND		ug/kg	150	--	1
Phenol	ND		ug/kg	190	--	1
2-Methylphenol	ND		ug/kg	190	--	1
3-Methylphenol/4-Methylphenol	ND		ug/kg	280	--	1
2,4,5-Trichlorophenol	ND		ug/kg	190	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-03  
 Client ID: 1607530-B102(S1-S2)  
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 10:45  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

## Semivolatile Organics by GC/MS - Westborough Lab

Benzoic Acid	ND		ug/kg	630	--	1
Benzyl Alcohol	ND		ug/kg	190	--	1
Carbazole	ND		ug/kg	190	--	1
Pyridine	ND		ug/kg	770	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	89		25-120
Phenol-d6	93		10-120
Nitrobenzene-d5	96		23-120
2-Fluorobiphenyl	82		30-120
2,4,6-Tribromophenol	90		10-136
4-Terphenyl-d14	86		18-120



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-04  
 Client ID: 1607530-B102(S3-S4)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8270D  
 Analytical Date: 09/02/16 06:08  
 Analyst: KV  
 Percent Solids: 79%

Date Collected: 08/26/16 11:00  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Semivolatile Organics by GC/MS - Westborough Lab</b>						
Acenaphthene	ND		ug/kg	170	--	1
Benzidine	ND		ug/kg	690	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	210	--	1
Hexachlorobenzene	ND		ug/kg	120	--	1
Bis(2-chloroethyl)ether	ND		ug/kg	190	--	1
2-Chloronaphthalene	ND		ug/kg	210	--	1
1,2-Dichlorobenzene	ND		ug/kg	210	--	1
1,3-Dichlorobenzene	ND		ug/kg	210	--	1
1,4-Dichlorobenzene	ND		ug/kg	210	--	1
3,3'-Dichlorobenzidine	ND		ug/kg	210	--	1
2,4-Dinitrotoluene	ND		ug/kg	210	--	1
2,6-Dinitrotoluene	ND		ug/kg	210	--	1
Azobenzene	ND		ug/kg	210	--	1
Fluoranthene	ND		ug/kg	120	--	1
4-Chlorophenyl phenyl ether	ND		ug/kg	210	--	1
4-Bromophenyl phenyl ether	ND		ug/kg	210	--	1
Bis(2-chloroisopropyl)ether	ND		ug/kg	250	--	1
Bis(2-chloroethoxy)methane	ND		ug/kg	220	--	1
Hexachlorobutadiene	ND		ug/kg	210	--	1
Hexachlorocyclopentadiene	ND		ug/kg	600	--	1
Hexachloroethane	ND		ug/kg	170	--	1
Isophorone	ND		ug/kg	190	--	1
Naphthalene	ND		ug/kg	210	--	1
Nitrobenzene	ND		ug/kg	190	--	1
NDPA/DPA	ND		ug/kg	170	--	1
n-Nitrosodi-n-propylamine	ND		ug/kg	210	--	1
Bis(2-ethylhexyl)phthalate	ND		ug/kg	210	--	1
Butyl benzyl phthalate	ND		ug/kg	210	--	1
Di-n-butylphthalate	ND		ug/kg	210	--	1
Di-n-octylphthalate	ND		ug/kg	210	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-04  
 Client ID: 1607530-B102(S3-S4)  
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 11:00  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Semivolatile Organics by GC/MS - Westborough Lab</b>						
Diethyl phthalate	ND		ug/kg	210	--	1
Dimethyl phthalate	ND		ug/kg	210	--	1
Benzo(a)anthracene	ND		ug/kg	120	--	1
Benzo(a)pyrene	ND		ug/kg	170	--	1
Benzo(b)fluoranthene	ND		ug/kg	120	--	1
Benzo(k)fluoranthene	ND		ug/kg	120	--	1
Chrysene	ND		ug/kg	120	--	1
Acenaphthylene	ND		ug/kg	170	--	1
Anthracene	ND		ug/kg	120	--	1
Benzo(ghi)perylene	ND		ug/kg	170	--	1
Fluorene	ND		ug/kg	210	--	1
Phenanthrene	ND		ug/kg	120	--	1
Dibenzo(a,h)anthracene	ND		ug/kg	120	--	1
Indeno(1,2,3-cd)pyrene	ND		ug/kg	170	--	1
Pyrene	ND		ug/kg	120	--	1
Biphenyl	ND		ug/kg	480	--	1
Aniline	ND		ug/kg	250	--	1
4-Chloroaniline	ND		ug/kg	210	--	1
1-Methylnaphthalene	ND		ug/kg	210	--	1
2-Nitroaniline	ND		ug/kg	210	--	1
3-Nitroaniline	ND		ug/kg	210	--	1
4-Nitroaniline	ND		ug/kg	210	--	1
Dibenzofuran	ND		ug/kg	210	--	1
2-Methylnaphthalene	ND		ug/kg	250	--	1
n-Nitrosodimethylamine	ND		ug/kg	420	--	1
2,4,6-Trichlorophenol	ND		ug/kg	120	--	1
p-Chloro-m-cresol	ND		ug/kg	210	--	1
2-Chlorophenol	ND		ug/kg	210	--	1
2,4-Dichlorophenol	ND		ug/kg	190	--	1
2,4-Dimethylphenol	ND		ug/kg	210	--	1
2-Nitrophenol	ND		ug/kg	450	--	1
4-Nitrophenol	ND		ug/kg	290	--	1
2,4-Dinitrophenol	ND		ug/kg	1000	--	1
4,6-Dinitro-o-cresol	ND		ug/kg	540	--	1
Pentachlorophenol	ND		ug/kg	170	--	1
Phenol	ND		ug/kg	210	--	1
2-Methylphenol	ND		ug/kg	210	--	1
3-Methylphenol/4-Methylphenol	ND		ug/kg	300	--	1
2,4,5-Trichlorophenol	ND		ug/kg	210	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-04  
 Client ID: 1607530-B102(S3-S4)  
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 11:00  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

## Semivolatile Organics by GC/MS - Westborough Lab

Benzoic Acid	ND		ug/kg	680	--	1
Benzyl Alcohol	ND		ug/kg	210	--	1
Carbazole	ND		ug/kg	210	--	1
Pyridine	ND		ug/kg	830	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	91		25-120
Phenol-d6	94		10-120
Nitrobenzene-d5	97		23-120
2-Fluorobiphenyl	79		30-120
2,4,6-Tribromophenol	84		10-136
4-Terphenyl-d14	82		18-120

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-05  
 Client ID: 1607530-B101(S1-S2)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8270D  
 Analytical Date: 09/02/16 06:34  
 Analyst: KV  
 Percent Solids: 84%

Date Collected: 08/26/16 11:45  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Semivolatile Organics by GC/MS - Westborough Lab</b>						
Acenaphthene	ND		ug/kg	160	--	1
Benzidine	ND		ug/kg	640	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	200	--	1
Hexachlorobenzene	ND		ug/kg	120	--	1
Bis(2-chloroethyl)ether	ND		ug/kg	180	--	1
2-Chloronaphthalene	ND		ug/kg	200	--	1
1,2-Dichlorobenzene	ND		ug/kg	200	--	1
1,3-Dichlorobenzene	ND		ug/kg	200	--	1
1,4-Dichlorobenzene	ND		ug/kg	200	--	1
3,3'-Dichlorobenzidine	ND		ug/kg	200	--	1
2,4-Dinitrotoluene	ND		ug/kg	200	--	1
2,6-Dinitrotoluene	ND		ug/kg	200	--	1
Azobenzene	ND		ug/kg	200	--	1
Fluoranthene	ND		ug/kg	120	--	1
4-Chlorophenyl phenyl ether	ND		ug/kg	200	--	1
4-Bromophenyl phenyl ether	ND		ug/kg	200	--	1
Bis(2-chloroisopropyl)ether	ND		ug/kg	230	--	1
Bis(2-chloroethoxy)methane	ND		ug/kg	210	--	1
Hexachlorobutadiene	ND		ug/kg	200	--	1
Hexachlorocyclopentadiene	ND		ug/kg	560	--	1
Hexachloroethane	ND		ug/kg	160	--	1
Isophorone	ND		ug/kg	180	--	1
Naphthalene	ND		ug/kg	200	--	1
Nitrobenzene	ND		ug/kg	180	--	1
NDPA/DPA	ND		ug/kg	160	--	1
n-Nitrosodi-n-propylamine	ND		ug/kg	200	--	1
Bis(2-ethylhexyl)phthalate	ND		ug/kg	200	--	1
Butyl benzyl phthalate	ND		ug/kg	200	--	1
Di-n-butylphthalate	ND		ug/kg	200	--	1
Di-n-octylphthalate	ND		ug/kg	200	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-05  
 Client ID: 1607530-B101(S1-S2)  
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 11:45  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Semivolatile Organics by GC/MS - Westborough Lab</b>						
Diethyl phthalate	ND		ug/kg	200	--	1
Dimethyl phthalate	ND		ug/kg	200	--	1
Benzo(a)anthracene	ND		ug/kg	120	--	1
Benzo(a)pyrene	ND		ug/kg	160	--	1
Benzo(b)fluoranthene	ND		ug/kg	120	--	1
Benzo(k)fluoranthene	ND		ug/kg	120	--	1
Chrysene	ND		ug/kg	120	--	1
Acenaphthylene	ND		ug/kg	160	--	1
Anthracene	ND		ug/kg	120	--	1
Benzo(ghi)perylene	ND		ug/kg	160	--	1
Fluorene	ND		ug/kg	200	--	1
Phenanthrene	ND		ug/kg	120	--	1
Dibenzo(a,h)anthracene	ND		ug/kg	120	--	1
Indeno(1,2,3-cd)pyrene	ND		ug/kg	160	--	1
Pyrene	ND		ug/kg	120	--	1
Biphenyl	ND		ug/kg	440	--	1
Aniline	ND		ug/kg	230	--	1
4-Chloroaniline	ND		ug/kg	200	--	1
1-Methylnaphthalene	ND		ug/kg	200	--	1
2-Nitroaniline	ND		ug/kg	200	--	1
3-Nitroaniline	ND		ug/kg	200	--	1
4-Nitroaniline	ND		ug/kg	200	--	1
Dibenzofuran	ND		ug/kg	200	--	1
2-Methylnaphthalene	ND		ug/kg	230	--	1
n-Nitrosodimethylamine	ND		ug/kg	390	--	1
2,4,6-Trichlorophenol	ND		ug/kg	120	--	1
p-Chloro-m-cresol	ND		ug/kg	200	--	1
2-Chlorophenol	ND		ug/kg	200	--	1
2,4-Dichlorophenol	ND		ug/kg	180	--	1
2,4-Dimethylphenol	ND		ug/kg	200	--	1
2-Nitrophenol	ND		ug/kg	420	--	1
4-Nitrophenol	ND		ug/kg	270	--	1
2,4-Dinitrophenol	ND		ug/kg	940	--	1
4,6-Dinitro-o-cresol	ND		ug/kg	510	--	1
Pentachlorophenol	ND		ug/kg	160	--	1
Phenol	ND		ug/kg	200	--	1
2-Methylphenol	ND		ug/kg	200	--	1
3-Methylphenol/4-Methylphenol	ND		ug/kg	280	--	1
2,4,5-Trichlorophenol	ND		ug/kg	200	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-05  
 Client ID: 1607530-B101(S1-S2)  
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 11:45  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

## Semivolatile Organics by GC/MS - Westborough Lab

Benzoic Acid	ND		ug/kg	630	--	1
Benzyl Alcohol	ND		ug/kg	200	--	1
Carbazole	ND		ug/kg	200	--	1
Pyridine	ND		ug/kg	780	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	86		25-120
Phenol-d6	89		10-120
Nitrobenzene-d5	95		23-120
2-Fluorobiphenyl	78		30-120
2,4,6-Tribromophenol	90		10-136
4-Terphenyl-d14	87		18-120

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-06  
 Client ID: 1607530-B101(S3-S4)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8270D  
 Analytical Date: 09/02/16 07:00  
 Analyst: KV  
 Percent Solids: 81%

Date Collected: 08/26/16 12:00  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Semivolatile Organics by GC/MS - Westborough Lab</b>						
Acenaphthene	ND		ug/kg	160	--	1
Benzidine	ND		ug/kg	660	--	1
1,2,4-Trichlorobenzene	ND		ug/kg	200	--	1
Hexachlorobenzene	ND		ug/kg	120	--	1
Bis(2-chloroethyl)ether	ND		ug/kg	180	--	1
2-Chloronaphthalene	ND		ug/kg	200	--	1
1,2-Dichlorobenzene	ND		ug/kg	200	--	1
1,3-Dichlorobenzene	ND		ug/kg	200	--	1
1,4-Dichlorobenzene	ND		ug/kg	200	--	1
3,3'-Dichlorobenzidine	ND		ug/kg	200	--	1
2,4-Dinitrotoluene	ND		ug/kg	200	--	1
2,6-Dinitrotoluene	ND		ug/kg	200	--	1
Azobenzene	ND		ug/kg	200	--	1
Fluoranthene	ND		ug/kg	120	--	1
4-Chlorophenyl phenyl ether	ND		ug/kg	200	--	1
4-Bromophenyl phenyl ether	ND		ug/kg	200	--	1
Bis(2-chloroisopropyl)ether	ND		ug/kg	240	--	1
Bis(2-chloroethoxy)methane	ND		ug/kg	220	--	1
Hexachlorobutadiene	ND		ug/kg	200	--	1
Hexachlorocyclopentadiene	ND		ug/kg	580	--	1
Hexachloroethane	ND		ug/kg	160	--	1
Isophorone	ND		ug/kg	180	--	1
Naphthalene	ND		ug/kg	200	--	1
Nitrobenzene	ND		ug/kg	180	--	1
NDPA/DPA	ND		ug/kg	160	--	1
n-Nitrosodi-n-propylamine	ND		ug/kg	200	--	1
Bis(2-ethylhexyl)phthalate	ND		ug/kg	200	--	1
Butyl benzyl phthalate	ND		ug/kg	200	--	1
Di-n-butylphthalate	ND		ug/kg	200	--	1
Di-n-octylphthalate	ND		ug/kg	200	--	1

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-06  
 Client ID: 1607530-B101(S3-S4)  
 Sample Location: NEWINGTON, NH

Date Collected: 08/26/16 12:00  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Semivolatile Organics by GC/MS - Westborough Lab</b>						
Diethyl phthalate	ND		ug/kg	200	--	1
Dimethyl phthalate	ND		ug/kg	200	--	1
Benzo(a)anthracene	ND		ug/kg	120	--	1
Benzo(a)pyrene	ND		ug/kg	160	--	1
Benzo(b)fluoranthene	ND		ug/kg	120	--	1
Benzo(k)fluoranthene	ND		ug/kg	120	--	1
Chrysene	ND		ug/kg	120	--	1
Acenaphthylene	ND		ug/kg	160	--	1
Anthracene	ND		ug/kg	120	--	1
Benzo(ghi)perylene	ND		ug/kg	160	--	1
Fluorene	ND		ug/kg	200	--	1
Phenanthrene	ND		ug/kg	120	--	1
Dibenzo(a,h)anthracene	ND		ug/kg	120	--	1
Indeno(1,2,3-cd)pyrene	ND		ug/kg	160	--	1
Pyrene	ND		ug/kg	120	--	1
Biphenyl	ND		ug/kg	460	--	1
Aniline	ND		ug/kg	240	--	1
4-Chloroaniline	ND		ug/kg	200	--	1
1-Methylnaphthalene	ND		ug/kg	200	--	1
2-Nitroaniline	ND		ug/kg	200	--	1
3-Nitroaniline	ND		ug/kg	200	--	1
4-Nitroaniline	ND		ug/kg	200	--	1
Dibenzofuran	ND		ug/kg	200	--	1
2-Methylnaphthalene	ND		ug/kg	240	--	1
n-Nitrosodimethylamine	ND		ug/kg	400	--	1
2,4,6-Trichlorophenol	ND		ug/kg	120	--	1
p-Chloro-m-cresol	ND		ug/kg	200	--	1
2-Chlorophenol	ND		ug/kg	200	--	1
2,4-Dichlorophenol	ND		ug/kg	180	--	1
2,4-Dimethylphenol	ND		ug/kg	200	--	1
2-Nitrophenol	ND		ug/kg	440	--	1
4-Nitrophenol	ND		ug/kg	280	--	1
2,4-Dinitrophenol	ND		ug/kg	970	--	1
4,6-Dinitro-o-cresol	ND		ug/kg	520	--	1
Pentachlorophenol	ND		ug/kg	160	--	1
Phenol	ND		ug/kg	200	--	1
2-Methylphenol	ND		ug/kg	200	--	1
3-Methylphenol/4-Methylphenol	ND		ug/kg	290	--	1
2,4,5-Trichlorophenol	ND		ug/kg	200	--	1



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

**Lab ID:** L1627010-06  
**Client ID:** 1607530-B101(S3-S4)  
**Sample Location:** NEWINGTON, NH

**Date Collected:** 08/26/16 12:00  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

## Semivolatile Organics by GC/MS - Westborough Lab

Benzoic Acid	ND		ug/kg	650	--	1
Benzyl Alcohol	ND		ug/kg	200	--	1
Carbazole	ND		ug/kg	200	--	1
Pyridine	ND		ug/kg	810	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	111		25-120
Phenol-d6	115		10-120
Nitrobenzene-d5	120		23-120
2-Fluorobiphenyl	92		30-120
2,4,6-Tribromophenol	92		10-136
4-Terphenyl-d14	90		18-120

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**Method Blank Analysis**  
**Batch Quality Control**

**Analytical Method:** 1,8270D  
**Analytical Date:** 09/02/16 03:36  
**Analyst:** KV

**Extraction Method:** EPA 3546  
**Extraction Date:** 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL
Semivolatile Organics by GC/MS - Westborough Lab for sample(s): 01-06 Batch: WG927494-1					
Acenaphthene	ND		ug/kg	130	--
Benzidine	ND		ug/kg	540	--
1,2,4-Trichlorobenzene	ND		ug/kg	160	--
Hexachlorobenzene	ND		ug/kg	98	--
Bis(2-chloroethyl)ether	ND		ug/kg	150	--
2-Chloronaphthalene	ND		ug/kg	160	--
1,2-Dichlorobenzene	ND		ug/kg	160	--
1,3-Dichlorobenzene	ND		ug/kg	160	--
1,4-Dichlorobenzene	ND		ug/kg	160	--
3,3'-Dichlorobenzidine	ND		ug/kg	160	--
2,4-Dinitrotoluene	ND		ug/kg	160	--
2,6-Dinitrotoluene	ND		ug/kg	160	--
Azobenzene	ND		ug/kg	160	--
Fluoranthene	ND		ug/kg	98	--
4-Chlorophenyl phenyl ether	ND		ug/kg	160	--
4-Bromophenyl phenyl ether	ND		ug/kg	160	--
Bis(2-chloroisopropyl)ether	ND		ug/kg	200	--
Bis(2-chloroethoxy)methane	ND		ug/kg	180	--
Hexachlorobutadiene	ND		ug/kg	160	--
Hexachlorocyclopentadiene	ND		ug/kg	470	--
Hexachloroethane	ND		ug/kg	130	--
Isophorone	ND		ug/kg	150	--
Naphthalene	ND		ug/kg	160	--
Nitrobenzene	ND		ug/kg	150	--
NDPA/DPA	ND		ug/kg	130	--
n-Nitrosodi-n-propylamine	ND		ug/kg	160	--
Bis(2-ethylhexyl)phthalate	ND		ug/kg	160	--
Butyl benzyl phthalate	ND		ug/kg	160	--
Di-n-butylphthalate	ND		ug/kg	160	--

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**Method Blank Analysis**  
**Batch Quality Control**

Analytical Method: 1,8270D  
Analytical Date: 09/02/16 03:36  
Analyst: KV

Extraction Method: EPA 3546  
Extraction Date: 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL
Semivolatile Organics by GC/MS - Westborough Lab for sample(s): 01-06 Batch: WG927494-1					
Di-n-octylphthalate	ND		ug/kg	160	--
Diethyl phthalate	ND		ug/kg	160	--
Dimethyl phthalate	ND		ug/kg	160	--
Benzo(a)anthracene	ND		ug/kg	98	--
Benzo(a)pyrene	ND		ug/kg	130	--
Benzo(b)fluoranthene	ND		ug/kg	98	--
Benzo(k)fluoranthene	ND		ug/kg	98	--
Chrysene	ND		ug/kg	98	--
Acenaphthylene	ND		ug/kg	130	--
Anthracene	ND		ug/kg	98	--
Benzo(ghi)perylene	ND		ug/kg	130	--
Fluorene	ND		ug/kg	160	--
Phenanthrene	ND		ug/kg	98	--
Dibenzo(a,h)anthracene	ND		ug/kg	98	--
Indeno(1,2,3-cd)pyrene	ND		ug/kg	130	--
Pyrene	ND		ug/kg	98	--
Biphenyl	ND		ug/kg	370	--
Aniline	ND		ug/kg	200	--
4-Chloroaniline	ND		ug/kg	160	--
1-Methylnaphthalene	ND		ug/kg	160	--
2-Nitroaniline	ND		ug/kg	160	--
3-Nitroaniline	ND		ug/kg	160	--
4-Nitroaniline	ND		ug/kg	160	--
Dibenzofuran	ND		ug/kg	160	--
2-Methylnaphthalene	ND		ug/kg	200	--
n-Nitrosodimethylamine	ND		ug/kg	330	--
2,4,6-Trichlorophenol	ND		ug/kg	98	--
p-Chloro-m-cresol	ND		ug/kg	160	--
2-Chlorophenol	ND		ug/kg	160	--

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**Method Blank Analysis**  
**Batch Quality Control**

**Analytical Method:** 1,8270D  
**Analytical Date:** 09/02/16 03:36  
**Analyst:** KV

**Extraction Method:** EPA 3546  
**Extraction Date:** 08/31/16 00:26

Parameter	Result	Qualifier	Units	RL	MDL
Semivolatile Organics by GC/MS - Westborough Lab for sample(s): 01-06 Batch: WG927494-1					
2,4-Dichlorophenol	ND		ug/kg	150	--
2,4-Dimethylphenol	ND		ug/kg	160	--
2-Nitrophenol	ND		ug/kg	350	--
4-Nitrophenol	ND		ug/kg	230	--
2,4-Dinitrophenol	ND		ug/kg	780	--
4,6-Dinitro-o-cresol	ND		ug/kg	420	--
Pentachlorophenol	ND		ug/kg	130	--
Phenol	ND		ug/kg	160	--
2-Methylphenol	ND		ug/kg	160	--
3-Methylphenol/4-Methylphenol	ND		ug/kg	240	--
2,4,5-Trichlorophenol	ND		ug/kg	160	--
Benzoic Acid	ND		ug/kg	530	--
Benzyl Alcohol	ND		ug/kg	160	--
Carbazole	ND		ug/kg	160	--
Pyridine	ND		ug/kg	650	--

Surrogate	%Recovery	Qualifier	Acceptance Criteria
2-Fluorophenol	71		25-120
Phenol-d6	71		10-120
Nitrobenzene-d5	74		23-120
2-Fluorobiphenyl	61		30-120
2,4,6-Tribromophenol	64		10-136
4-Terphenyl-d14	67		18-120

## Lab Control Sample Analysis

### Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Semivolatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-06 Batch: WG927494-2 WG927494-3								
Acenaphthene	74		75		31-137	1		50
Benzidine	52		47		10-66	10		50
1,2,4-Trichlorobenzene	73		82		38-107	12		50
Hexachlorobenzene	74		74		40-140	0		50
Bis(2-chloroethyl)ether	75		85		40-140	13		50
2-Chloronaphthalene	74		75		40-140	1		50
1,2-Dichlorobenzene	69		83		40-140	18		50
1,3-Dichlorobenzene	67		80		40-140	18		50
1,4-Dichlorobenzene	68		82		28-104	19		50
3,3'-Dichlorobenzidine	82		76		40-140	8		50
2,4-Dinitrotoluene	96	Q	93	Q	28-89	3		50
2,6-Dinitrotoluene	83		84		40-140	1		50
Azobenzene	76		77		40-140	1		50
Fluoranthene	80		77		40-140	4		50
4-Chlorophenyl phenyl ether	75		75		40-140	0		50
4-Bromophenyl phenyl ether	74		75		40-140	1		50
Bis(2-chloroisopropyl)ether	73		80		40-140	9		50
Bis(2-chloroethoxy)methane	77		84		40-117	9		50
Hexachlorobutadiene	71		77		40-140	8		50
Hexachlorocyclopentadiene	89		93		40-140	4		50
Hexachloroethane	73		88		40-140	19		50

## Lab Control Sample Analysis

### Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Semivolatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-06 Batch: WG927494-2 WG927494-3								
Isophorone	82		89		40-140	8		50
Naphthalene	73		79		40-140	8		50
Nitrobenzene	89		100		40-140	12		50
NDPA/DPA	76		77		36-157	1		50
n-Nitrosodi-n-propylamine	86		92		32-121	7		50
Bis(2-ethylhexyl)phthalate	88		84		40-140	5		50
Butyl benzyl phthalate	95		91		40-140	4		50
Di-n-butylphthalate	89		85		40-140	5		50
Di-n-octylphthalate	98		95		40-140	3		50
Diethyl phthalate	82		79		40-140	4		50
Dimethyl phthalate	83		81		40-140	2		50
Benzo(a)anthracene	79		77		40-140	3		50
Benzo(a)pyrene	86		84		40-140	2		50
Benzo(b)fluoranthene	81		80		40-140	1		50
Benzo(k)fluoranthene	81		75		40-140	8		50
Chrysene	76		74		40-140	3		50
Acenaphthylene	80		81		40-140	1		50
Anthracene	81		80		40-140	1		50
Benzo(ghi)perylene	82		80		40-140	2		50
Fluorene	77		77		40-140	0		50
Phenanthrene	72		72		40-140	0		50

## Lab Control Sample Analysis

### Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Semivolatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-06 Batch: WG927494-2 WG927494-3								
Dibenzo(a,h)anthracene	84		83		40-140	1		50
Indeno(1,2,3-cd)pyrene	84		83		40-140	1		50
Pyrene	77		74		35-142	4		50
Biphenyl	80		81		54-104	1		50
Aniline	64		69		40-140	8		50
4-Chloroaniline	66		74		40-140	11		50
1-Methylnaphthalene	72		78		26-130	8		50
2-Nitroaniline	91		91		47-134	0		50
3-Nitroaniline	84		79		26-129	6		50
4-Nitroaniline	86		83		41-125	4		50
Dibenzofuran	75		76		40-140	1		50
2-Methylnaphthalene	74		78		40-140	5		50
1,2,4,5-Tetrachlorobenzene	75		80		40-117	6		50
Acetophenone	83		91		14-144	9		50
n-Nitrosodimethylamine	69		83		22-100	18		50
2,4,6-Trichlorophenol	84		83		30-130	1		50
p-Chloro-m-cresol	90		91		26-103	1		50
2-Chlorophenol	87		99		25-102	13		50
2,4-Dichlorophenol	94		97		30-130	3		50
2,4-Dimethylphenol	95		105		30-130	10		50
2-Nitrophenol	113		123		30-130	8		50

## Lab Control Sample Analysis

### Batch Quality Control

**Project Name:** EVERSOURCE NH SRP

**Lab Number:** L1627010

**Project Number:** 1607530

**Report Date:** 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Semivolatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-06 Batch: WG927494-2 WG927494-3								
4-Nitrophenol	85		83		11-114	2		50
2,4-Dinitrophenol	118		109		4-130	8		50
4,6-Dinitro-o-cresol	126		120		10-130	5		50
Pentachlorophenol	76		76		17-109	0		50
Phenol	81		90		26-90	11		50
2-Methylphenol	88		95		30-130.	8		50
3-Methylphenol/4-Methylphenol	86		91		30-130	6		50
2,4,5-Trichlorophenol	92		93		30-130	1		50
Benzoic Acid	45		45		10-110	0		50
Benzyl Alcohol	85		94		40-140	10		50
Carbazole	79		76		54-128	4		50
Pyridine	54		72		10-93	29		50
Parathion, ethyl	135		131		40-140	3		50
Atrazine	97		97		40-140	0		50
Benzaldehyde	63		75		40-140	17		50
Caprolactam	90		89		15-130	1		50
2,3,4,6-Tetrachlorophenol	88		86		40-140	2		50



## Lab Control Sample Analysis

### Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
-----------	------------------	------	-------------------	------	---------------------	-----	------	---------------

Semivolatile Organics by GC/MS - Westborough Lab Associated sample(s): 01-06 Batch: WG927494-2 WG927494-3

Surrogate	LCS %Recovery	Qual	LCSD %Recovery	Qual	Acceptance Criteria
2-Fluorophenol	86		97		25-120
Phenol-d6	87		97		10-120
Nitrobenzene-d5	95		102		23-120
2-Fluorobiphenyl	75		76		30-120
2,4,6-Tribromophenol	80		81		10-136
4-Terphenyl-d14	77		74		18-120

# PETROLEUM HYDROCARBONS

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-01  
 Client ID: 1607530-B103(S1-S2)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8015C(M)  
 Analytical Date: 09/01/16 20:20  
 Analyst: DV  
 Percent Solids: 93%

Date Collected: 08/26/16 09:25  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 08/31/16 20:59

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Petroleum Hydrocarbon Quantitation - Westborough Lab						
--	--	--	--	--	--	--

TPH	ND		ug/kg	35500	--	1
-----	----	--	-------	-------	----	---

Surrogate	% Recovery	Qualifier	Acceptance Criteria
o-Terphenyl	54		40-140

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-02  
 Client ID: 1607530-B103(S3-S4)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8015C(M)  
 Analytical Date: 09/01/16 20:53  
 Analyst: DV  
 Percent Solids: 92%

Date Collected: 08/26/16 09:55  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 08/31/16 20:59

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Petroleum Hydrocarbon Quantitation - Westborough Lab						
--	--	--	--	--	--	--

TPH	ND		ug/kg	34100	--	1
-----	----	--	-------	-------	----	---

Surrogate	% Recovery	Qualifier	Acceptance Criteria
o-Terphenyl	81		40-140

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-03  
 Client ID: 1607530-B102(S1-S2)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8015C(M)  
 Analytical Date: 09/01/16 21:25  
 Analyst: DV  
 Percent Solids: 84%

Date Collected: 08/26/16 10:45  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 08/31/16 20:59

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Petroleum Hydrocarbon Quantitation - Westborough Lab						
--	--	--	--	--	--	--

TPH	ND		ug/kg	39500	--	1
-----	----	--	-------	-------	----	---

Surrogate	% Recovery	Qualifier	Acceptance Criteria
o-Terphenyl	83		40-140

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-04  
 Client ID: 1607530-B102(S3-S4)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8015C(M)  
 Analytical Date: 09/01/16 21:57  
 Analyst: DV  
 Percent Solids: 79%

Date Collected: 08/26/16 11:00  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 08/31/16 20:59

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Petroleum Hydrocarbon Quantitation - Westborough Lab						
--	--	--	--	--	--	--

TPH	ND		ug/kg	39900	--	1
-----	----	--	-------	-------	----	---

Surrogate	% Recovery	Qualifier	Acceptance Criteria
o-Terphenyl	78		40-140

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-05  
 Client ID: 1607530-B101(S1-S2)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8015C(M)  
 Analytical Date: 09/01/16 22:29  
 Analyst: DV  
 Percent Solids: 84%

Date Collected: 08/26/16 11:45  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 08/31/16 20:59

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Petroleum Hydrocarbon Quantitation - Westborough Lab						
--	--	--	--	--	--	--

TPH	39000		ug/kg	37500	--	1
-----	-------	--	-------	-------	----	---

Surrogate	% Recovery	Qualifier	Acceptance Criteria
o-Terphenyl	82		40-140

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-06  
 Client ID: 1607530-B101(S3-S4)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8015C(M)  
 Analytical Date: 09/01/16 23:01  
 Analyst: DV  
 Percent Solids: 81%

Date Collected: 08/26/16 12:00  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 08/31/16 20:59

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
-----------	--------	-----------	-------	----	-----	-----------------

Petroleum Hydrocarbon Quantitation - Westborough Lab						
--	--	--	--	--	--	--

TPH	ND		ug/kg	39800	--	1
-----	----	--	-------	-------	----	---

Surrogate	% Recovery	Qualifier	Acceptance Criteria
o-Terphenyl	79		40-140



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**Method Blank Analysis**  
**Batch Quality Control**

**Analytical Method:** 1,8015C(M)  
**Analytical Date:** 09/01/16 17:08  
**Analyst:** SR

**Extraction Method:** EPA 3546  
**Extraction Date:** 08/31/16 19:47

Parameter	Result	Qualifier	Units	RL	MDL
Petroleum Hydrocarbon Quantitation - Westborough Lab for sample(s): 01-06 Batch: WG927867-1					
TPH	ND		ug/kg	33000	--

Surrogate	%Recovery	Qualifier	Acceptance Criteria
o-Terphenyl	85		40-140

### Lab Control Sample Analysis Batch Quality Control

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

<b>Parameter</b>	<b>LCS %Recovery</b>	<b>Qual</b>	<b>LCSD %Recovery</b>	<b>Qual</b>	<b>%Recovery Limits</b>	<b>RPD</b>	<b>Qual</b>	<b>RPD Limits</b>
Petroleum Hydrocarbon Quantitation - Westborough Lab Associated sample(s): 01-06 Batch: WG927867-2								
TPH	92		-		40-140	-		40

<b>Surrogate</b>	<b>LCS %Recovery</b>	<b>Qual</b>	<b>LCSD %Recovery</b>	<b>Qual</b>	<b>Acceptance Criteria</b>
o-Terphenyl	89				40-140



# PCBS

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-01  
 Client ID: 1607530-B103(S1-S2)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8082A  
 Analytical Date: 09/02/16 22:16  
 Analyst: JA  
 Percent Solids: 93%

Date Collected: 08/26/16 09:25  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 08/31/16 18:23  
 Cleanup Method: EPA 3665A  
 Cleanup Date: 09/01/16  
 Cleanup Method: EPA 3660B  
 Cleanup Date: 09/01/16

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Column
<b>PCB by GC - Westborough Lab</b>							
Aroclor 1016	ND		ug/kg	33.9	--	1	A
Aroclor 1221	ND		ug/kg	33.9	--	1	A
Aroclor 1232	ND		ug/kg	33.9	--	1	A
Aroclor 1242	ND		ug/kg	33.9	--	1	A
Aroclor 1248	ND		ug/kg	33.9	--	1	A
Aroclor 1254	ND		ug/kg	33.9	--	1	A
Aroclor 1260	ND		ug/kg	33.9	--	1	A
Aroclor 1262	ND		ug/kg	33.9	--	1	A
Aroclor 1268	ND		ug/kg	33.9	--	1	A
PCBs, Total	ND		ug/kg	33.9	--	1	A

Surrogate	% Recovery	Qualifier	Acceptance Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	67		30-150	A
Decachlorobiphenyl	67		30-150	A
2,4,5,6-Tetrachloro-m-xylene	72		30-150	B
Decachlorobiphenyl	75		30-150	B

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-02  
 Client ID: 1607530-B103(S3-S4)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8082A  
 Analytical Date: 09/02/16 22:31  
 Analyst: JA  
 Percent Solids: 92%

Date Collected: 08/26/16 09:55  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 08/31/16 18:23  
 Cleanup Method: EPA 3665A  
 Cleanup Date: 09/01/16  
 Cleanup Method: EPA 3660B  
 Cleanup Date: 09/01/16

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Column
<b>PCB by GC - Westborough Lab</b>							
Aroclor 1016	ND		ug/kg	34.4	--	1	A
Aroclor 1221	ND		ug/kg	34.4	--	1	A
Aroclor 1232	ND		ug/kg	34.4	--	1	A
Aroclor 1242	ND		ug/kg	34.4	--	1	A
Aroclor 1248	ND		ug/kg	34.4	--	1	A
Aroclor 1254	ND		ug/kg	34.4	--	1	A
Aroclor 1260	ND		ug/kg	34.4	--	1	A
Aroclor 1262	ND		ug/kg	34.4	--	1	A
Aroclor 1268	ND		ug/kg	34.4	--	1	A
PCBs, Total	ND		ug/kg	34.4	--	1	A

Surrogate	% Recovery	Qualifier	Acceptance Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	78		30-150	A
Decachlorobiphenyl	82		30-150	A
2,4,5,6-Tetrachloro-m-xylene	82		30-150	B
Decachlorobiphenyl	85		30-150	B

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-03  
 Client ID: 1607530-B102(S1-S2)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8082A  
 Analytical Date: 09/02/16 22:45  
 Analyst: JA  
 Percent Solids: 84%

Date Collected: 08/26/16 10:45  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 08/31/16 18:23  
 Cleanup Method: EPA 3665A  
 Cleanup Date: 09/01/16  
 Cleanup Method: EPA 3660B  
 Cleanup Date: 09/01/16

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Column
<b>PCB by GC - Westborough Lab</b>							
Aroclor 1016	ND		ug/kg	39.1	--	1	A
Aroclor 1221	ND		ug/kg	39.1	--	1	A
Aroclor 1232	ND		ug/kg	39.1	--	1	A
Aroclor 1242	ND		ug/kg	39.1	--	1	A
Aroclor 1248	ND		ug/kg	39.1	--	1	A
Aroclor 1254	ND		ug/kg	39.1	--	1	A
Aroclor 1260	ND		ug/kg	39.1	--	1	A
Aroclor 1262	ND		ug/kg	39.1	--	1	A
Aroclor 1268	ND		ug/kg	39.1	--	1	A
PCBs, Total	ND		ug/kg	39.1	--	1	A

Surrogate	% Recovery	Qualifier	Acceptance Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	77		30-150	A
Decachlorobiphenyl	84		30-150	A
2,4,5,6-Tetrachloro-m-xylene	78		30-150	B
Decachlorobiphenyl	93		30-150	B

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-04  
 Client ID: 1607530-B102(S3-S4)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8082A  
 Analytical Date: 09/04/16 16:48  
 Analyst: KEG  
 Percent Solids: 79%

Date Collected: 08/26/16 11:00  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 09/04/16 06:18  
 Cleanup Method: EPA 3665A  
 Cleanup Date: 09/04/16  
 Cleanup Method: EPA 3660B  
 Cleanup Date: 09/04/16

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Column
<b>PCB by GC - Westborough Lab</b>							
Aroclor 1016	ND		ug/kg	41.5	--	1	A
Aroclor 1221	ND		ug/kg	41.5	--	1	A
Aroclor 1232	ND		ug/kg	41.5	--	1	A
Aroclor 1242	ND		ug/kg	41.5	--	1	A
Aroclor 1248	ND		ug/kg	41.5	--	1	A
Aroclor 1254	ND		ug/kg	41.5	--	1	A
Aroclor 1260	ND		ug/kg	41.5	--	1	A
Aroclor 1262	ND		ug/kg	41.5	--	1	A
Aroclor 1268	ND		ug/kg	41.5	--	1	A
PCBs, Total	ND		ug/kg	41.5	--	1	A

Surrogate	% Recovery	Qualifier	Acceptance Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	54		30-150	A
Decachlorobiphenyl	49		30-150	A
2,4,5,6-Tetrachloro-m-xylene	56		30-150	B
Decachlorobiphenyl	62		30-150	B

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-05  
 Client ID: 1607530-B101(S1-S2)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8082A  
 Analytical Date: 09/02/16 23:14  
 Analyst: JA  
 Percent Solids: 84%

Date Collected: 08/26/16 11:45  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 08/31/16 18:23  
 Cleanup Method: EPA 3665A  
 Cleanup Date: 09/01/16  
 Cleanup Method: EPA 3660B  
 Cleanup Date: 09/01/16

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Column
<b>PCB by GC - Westborough Lab</b>							
Aroclor 1016	ND		ug/kg	39.2	--	1	A
Aroclor 1221	ND		ug/kg	39.2	--	1	A
Aroclor 1232	ND		ug/kg	39.2	--	1	A
Aroclor 1242	ND		ug/kg	39.2	--	1	A
Aroclor 1248	ND		ug/kg	39.2	--	1	A
Aroclor 1254	ND		ug/kg	39.2	--	1	A
Aroclor 1260	ND		ug/kg	39.2	--	1	A
Aroclor 1262	ND		ug/kg	39.2	--	1	A
Aroclor 1268	ND		ug/kg	39.2	--	1	A
PCBs, Total	ND		ug/kg	39.2	--	1	A

Surrogate	% Recovery	Qualifier	Acceptance Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	89		30-150	A
Decachlorobiphenyl	92		30-150	A
2,4,5,6-Tetrachloro-m-xylene	96		30-150	B
Decachlorobiphenyl	113		30-150	B



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-06  
 Client ID: 1607530-B101(S3-S4)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Analytical Method: 1,8082A  
 Analytical Date: 09/04/16 17:04  
 Analyst: KEG  
 Percent Solids: 81%

Date Collected: 08/26/16 12:00  
 Date Received: 08/29/16  
 Field Prep: Not Specified  
 Extraction Method: EPA 3546  
 Extraction Date: 09/04/16 06:18  
 Cleanup Method: EPA 3665A  
 Cleanup Date: 09/04/16  
 Cleanup Method: EPA 3660B  
 Cleanup Date: 09/04/16

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Column
<b>PCB by GC - Westborough Lab</b>							
Aroclor 1016	ND		ug/kg	40.0	--	1	A
Aroclor 1221	ND		ug/kg	40.0	--	1	A
Aroclor 1232	ND		ug/kg	40.0	--	1	A
Aroclor 1242	ND		ug/kg	40.0	--	1	A
Aroclor 1248	ND		ug/kg	40.0	--	1	A
Aroclor 1254	ND		ug/kg	40.0	--	1	A
Aroclor 1260	ND		ug/kg	40.0	--	1	A
Aroclor 1262	ND		ug/kg	40.0	--	1	A
Aroclor 1268	ND		ug/kg	40.0	--	1	A
PCBs, Total	ND		ug/kg	40.0	--	1	A

Surrogate	% Recovery	Qualifier	Acceptance Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	39		30-150	A
Decachlorobiphenyl	32		30-150	A
2,4,5,6-Tetrachloro-m-xylene	38		30-150	B
Decachlorobiphenyl	43		30-150	B

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**Method Blank Analysis  
Batch Quality Control**

Analytical Method: 1,8082A  
Analytical Date: 09/02/16 21:33  
Analyst: JA

Extraction Method: EPA 3546  
Extraction Date: 08/31/16 18:23  
Cleanup Method: EPA 3665A  
Cleanup Date: 09/01/16  
Cleanup Method: EPA 3660B  
Cleanup Date: 09/01/16

Parameter	Result	Qualifier	Units	RL	MDL	Column
PCB by GC - Westborough Lab for sample(s): 01-03,05 Batch: WG927841-1						
Aroclor 1016	ND		ug/kg	32.6	--	A
Aroclor 1221	ND		ug/kg	32.6	--	A
Aroclor 1232	ND		ug/kg	32.6	--	A
Aroclor 1242	ND		ug/kg	32.6	--	A
Aroclor 1248	ND		ug/kg	32.6	--	A
Aroclor 1254	ND		ug/kg	32.6	--	A
Aroclor 1260	ND		ug/kg	32.6	--	A
Aroclor 1262	ND		ug/kg	32.6	--	A
Aroclor 1268	ND		ug/kg	32.6	--	A
PCBs, Total	ND		ug/kg	32.6	--	A

Surrogate	%Recovery	Qualifier	Acceptance	
			Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	82		30-150	A
Decachlorobiphenyl	85		30-150	A
2,4,5,6-Tetrachloro-m-xylene	89		30-150	B
Decachlorobiphenyl	93		30-150	B

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**Method Blank Analysis**  
**Batch Quality Control**

Analytical Method: 1,8082A  
Analytical Date: 09/04/16 19:10  
Analyst: JA

Extraction Method: EPA 3546  
Extraction Date: 09/04/16 02:28  
Cleanup Method: EPA 3665A  
Cleanup Date: 09/04/16  
Cleanup Method: EPA 3660B  
Cleanup Date: 09/04/16

Parameter	Result	Qualifier	Units	RL	MDL	Column
PCB by GC - Westborough Lab for sample(s): 04,06 Batch: WG928866-1						
Aroclor 1016	ND		ug/kg	31.9	--	A
Aroclor 1221	ND		ug/kg	31.9	--	A
Aroclor 1232	ND		ug/kg	31.9	--	A
Aroclor 1242	ND		ug/kg	31.9	--	A
Aroclor 1248	ND		ug/kg	31.9	--	A
Aroclor 1254	ND		ug/kg	31.9	--	A
Aroclor 1260	ND		ug/kg	31.9	--	A
Aroclor 1262	ND		ug/kg	31.9	--	A
Aroclor 1268	ND		ug/kg	31.9	--	A
PCBs, Total	ND		ug/kg	31.9	--	A

Surrogate	%Recovery	Qualifier	Acceptance	
			Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	78		30-150	A
Decachlorobiphenyl	74		30-150	A
2,4,5,6-Tetrachloro-m-xylene	74		30-150	B
Decachlorobiphenyl	71		30-150	B

## Lab Control Sample Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits	Column
PCB by GC - Westborough Lab Associated sample(s): 01-03,05 Batch: WG927841-2 WG927841-3									
Aroclor 1016	102		98		40-140	4		50	A
Aroclor 1260	88		87		40-140	1		50	A

Surrogate	LCS %Recovery	Qual	LCSD %Recovery	Qual	Acceptance Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	94		89		30-150	A
Decachlorobiphenyl	86		88		30-150	A
2,4,5,6-Tetrachloro-m-xylene	94		95		30-150	B
Decachlorobiphenyl	93		99		30-150	B

## Lab Control Sample Analysis

### Batch Quality Control

Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits	Column
PCB by GC - Westborough Lab Associated sample(s): 04,06 Batch: WG928866-2 WG928866-3									
Aroclor 1016	72		75		40-140	4		50	A
Aroclor 1260	70		62		40-140	12		50	A

Surrogate	LCS %Recovery	Qual	LCSD %Recovery	Qual	Acceptance Criteria	Column
2,4,5,6-Tetrachloro-m-xylene	72		76		30-150	A
Decachlorobiphenyl	71		73		30-150	A
2,4,5,6-Tetrachloro-m-xylene	71		71		30-150	B
Decachlorobiphenyl	69		69		30-150	B

## METALS

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-01  
 Client ID: 1607530-B103(S1-S2)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Percent Solids: 93%

Date Collected: 08/26/16 09:25  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
<b>Total Metals - Mansfield Lab</b>											
Arsenic, Total	9.0		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 13:28	EPA 3050B	1,6010C	PS
Barium, Total	30		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 13:28	EPA 3050B	1,6010C	PS
Cadmium, Total	ND		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 13:28	EPA 3050B	1,6010C	PS
Chromium, Total	30		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 13:28	EPA 3050B	1,6010C	PS
Lead, Total	7.2		mg/kg	2.1	--	1	08/31/16 06:40	08/31/16 13:28	EPA 3050B	1,6010C	PS
Mercury, Total	ND		mg/kg	0.07	--	1	08/30/16 09:00	08/30/16 15:06	EPA 7471B	1,7471B	BV
Selenium, Total	ND		mg/kg	0.85	--	1	08/31/16 06:40	08/31/16 13:28	EPA 3050B	1,6010C	PS
Silver, Total	ND		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 13:28	EPA 3050B	1,6010C	PS



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-02  
 Client ID: 1607530-B103(S3-S4)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Percent Solids: 92%

Date Collected: 08/26/16 09:55  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
<b>Total Metals - Mansfield Lab</b>											
Arsenic, Total	7.1		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 14:39	EPA 3050B	1,6010C	PS
Barium, Total	18		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 14:39	EPA 3050B	1,6010C	PS
Cadmium, Total	ND		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 14:39	EPA 3050B	1,6010C	PS
Chromium, Total	26		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 14:39	EPA 3050B	1,6010C	PS
Lead, Total	8.6		mg/kg	2.1	--	1	08/31/16 06:40	08/31/16 14:39	EPA 3050B	1,6010C	PS
Mercury, Total	ND		mg/kg	0.07	--	1	08/30/16 09:00	08/30/16 15:08	EPA 7471B	1,7471B	BV
Selenium, Total	ND		mg/kg	0.84	--	1	08/31/16 06:40	08/31/16 14:39	EPA 3050B	1,6010C	PS
Silver, Total	ND		mg/kg	0.42	--	1	08/31/16 06:40	08/31/16 14:39	EPA 3050B	1,6010C	PS





**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-03  
 Client ID: 1607530-B102(S1-S2)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Percent Solids: 84%

Date Collected: 08/26/16 10:45  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
<b>Total Metals - Mansfield Lab</b>											
Arsenic, Total	12		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 14:43	EPA 3050B	1,6010C	PS
Barium, Total	44		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 14:43	EPA 3050B	1,6010C	PS
Cadmium, Total	ND		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 14:43	EPA 3050B	1,6010C	PS
Chromium, Total	19		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 14:43	EPA 3050B	1,6010C	PS
Lead, Total	6.8		mg/kg	2.3	--	1	08/31/16 06:40	08/31/16 14:43	EPA 3050B	1,6010C	PS
Mercury, Total	ND		mg/kg	0.08	--	1	08/30/16 09:00	08/30/16 15:10	EPA 7471B	1,7471B	BV
Selenium, Total	ND		mg/kg	0.94	--	1	08/31/16 06:40	08/31/16 14:43	EPA 3050B	1,6010C	PS
Silver, Total	ND		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 14:43	EPA 3050B	1,6010C	PS



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-04  
 Client ID: 1607530-B102(S3-S4)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Percent Solids: 79%

Date Collected: 08/26/16 11:00  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
<b>Total Metals - Mansfield Lab</b>											
Arsenic, Total	12		mg/kg	0.49	--	1	08/31/16 06:40	08/31/16 14:47	EPA 3050B	1,6010C	PS
Barium, Total	31		mg/kg	0.49	--	1	08/31/16 06:40	08/31/16 14:47	EPA 3050B	1,6010C	PS
Cadmium, Total	ND		mg/kg	0.49	--	1	08/31/16 06:40	08/31/16 14:47	EPA 3050B	1,6010C	PS
Chromium, Total	18		mg/kg	0.49	--	1	08/31/16 06:40	08/31/16 14:47	EPA 3050B	1,6010C	PS
Lead, Total	8.9		mg/kg	2.4	--	1	08/31/16 06:40	08/31/16 14:47	EPA 3050B	1,6010C	PS
Mercury, Total	ND		mg/kg	0.08	--	1	08/30/16 09:00	08/30/16 15:12	EPA 7471B	1,7471B	BV
Selenium, Total	ND		mg/kg	0.98	--	1	08/31/16 06:40	08/31/16 14:47	EPA 3050B	1,6010C	PS
Silver, Total	ND		mg/kg	0.49	--	1	08/31/16 06:40	08/31/16 14:47	EPA 3050B	1,6010C	PS



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-05  
 Client ID: 1607530-B101(S1-S2)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Percent Solids: 84%

Date Collected: 08/26/16 11:45  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
<b>Total Metals - Mansfield Lab</b>											
Arsenic, Total	7.4		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 15:48	EPA 3050B	1,6010C	PS
Barium, Total	28		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 15:48	EPA 3050B	1,6010C	PS
Cadmium, Total	ND		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 15:48	EPA 3050B	1,6010C	PS
Chromium, Total	14		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 15:48	EPA 3050B	1,6010C	PS
Lead, Total	5.7		mg/kg	2.4	--	1	08/31/16 06:40	08/31/16 15:48	EPA 3050B	1,6010C	PS
Mercury, Total	ND		mg/kg	0.08	--	1	08/30/16 09:00	08/30/16 15:19	EPA 7471B	1,7471B	BV
Selenium, Total	ND		mg/kg	0.94	--	1	08/31/16 06:40	08/31/16 15:48	EPA 3050B	1,6010C	PS
Silver, Total	ND		mg/kg	0.47	--	1	08/31/16 06:40	08/31/16 15:48	EPA 3050B	1,6010C	PS



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

Lab ID: L1627010-06  
 Client ID: 1607530-B101(S3-S4)  
 Sample Location: NEWINGTON, NH  
 Matrix: Soil  
 Percent Solids: 81%

Date Collected: 08/26/16 12:00  
 Date Received: 08/29/16  
 Field Prep: Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
<b>Total Metals - Mansfield Lab</b>											
Arsenic, Total	5.6		mg/kg	0.48	--	1	08/31/16 06:40	08/31/16 15:51	EPA 3050B	1,6010C	PS
Barium, Total	33		mg/kg	0.48	--	1	08/31/16 06:40	08/31/16 15:51	EPA 3050B	1,6010C	PS
Cadmium, Total	ND		mg/kg	0.48	--	1	08/31/16 06:40	08/31/16 15:51	EPA 3050B	1,6010C	PS
Chromium, Total	16		mg/kg	0.48	--	1	08/31/16 06:40	08/31/16 15:51	EPA 3050B	1,6010C	PS
Lead, Total	4.6		mg/kg	2.4	--	1	08/31/16 06:40	08/31/16 15:51	EPA 3050B	1,6010C	PS
Mercury, Total	ND		mg/kg	0.08	--	1	08/30/16 09:00	08/30/16 15:21	EPA 7471B	1,7471B	BV
Selenium, Total	ND		mg/kg	0.96	--	1	08/31/16 06:40	08/31/16 15:51	EPA 3050B	1,6010C	PS
Silver, Total	ND		mg/kg	0.48	--	1	08/31/16 06:40	08/31/16 15:51	EPA 3050B	1,6010C	PS



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

### Method Blank Analysis Batch Quality Control

Parameter	Result Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
Total Metals - Mansfield Lab for sample(s): 01-06 Batch: WG927131-1									
Mercury, Total	ND	mg/kg	0.08	--	1	08/30/16 09:00	08/30/16 14:37	1,7471B	BV

#### Prep Information

Digestion Method: EPA 7471B

Parameter	Result Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
Total Metals - Mansfield Lab for sample(s): 01-06 Batch: WG927532-1									
Arsenic, Total	ND	mg/kg	0.40	--	1	08/31/16 06:40	08/31/16 14:15	1,6010C	PS
Barium, Total	ND	mg/kg	0.40	--	1	08/31/16 06:40	08/31/16 14:15	1,6010C	PS
Cadmium, Total	ND	mg/kg	0.40	--	1	08/31/16 06:40	08/31/16 14:15	1,6010C	PS
Chromium, Total	ND	mg/kg	0.40	--	1	08/31/16 06:40	08/31/16 14:15	1,6010C	PS
Lead, Total	ND	mg/kg	2.0	--	1	08/31/16 06:40	08/31/16 14:15	1,6010C	PS
Selenium, Total	ND	mg/kg	0.80	--	1	08/31/16 06:40	08/31/16 14:15	1,6010C	PS
Silver, Total	ND	mg/kg	0.40	--	1	08/31/16 06:40	08/31/16 14:15	1,6010C	PS

#### Prep Information

Digestion Method: EPA 3050B

## Lab Control Sample Analysis

### Batch Quality Control

**Project Name:** EVERSOURCE NH SRP

**Project Number:** 1607530

**Lab Number:** L1627010

**Report Date:** 09/15/16

Parameter	LCS		LCSD		%Recovery Limits	RPD	Qual	RPD Limits
	%Recovery	Qual	%Recovery	Qual				
Total Metals - Mansfield Lab Associated sample(s): 01-06 Batch: WG927131-2 SRM Lot Number: D089-540								
Mercury, Total	101		-		57-143	-		
Total Metals - Mansfield Lab Associated sample(s): 01-06 Batch: WG927532-2 SRM Lot Number: D089-540								
Arsenic, Total	100		-		80-120	-		
Barium, Total	93		-		83-117	-		
Cadmium, Total	95		-		82-117	-		
Chromium, Total	96		-		79-121	-		
Lead, Total	95		-		81-119	-		
Selenium, Total	90		-		78-121	-		
Silver, Total	97		-		75-125	-		

### Matrix Spike Analysis Batch Quality Control

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

Parameter	Native Sample	MS Added	MS Found	MS %Recovery	Qual	MSD Found	MSD %Recovery	Qual	Recovery Limits	RPD	Qual	RPD Limits
Total Metals - Mansfield Lab Associated sample(s): 01-06    QC Batch ID: WG927131-4    QC Sample: L1626498-01    Client ID: MS Sample												
Mercury, Total	ND	0.144	0.18	125	Q	-	-		80-120	-		20
Total Metals - Mansfield Lab Associated sample(s): 01-06    QC Batch ID: WG927532-4    QC Sample: L1627089-01    Client ID: MS Sample												
Arsenic, Total	1.7	9.93	10	84		-	-		75-125	-		20
Barium, Total	25	165	150	76		-	-		75-125	-		20
Cadmium, Total	ND	4.22	2.8	66	Q	-	-		75-125	-		20
Chromium, Total	3.5	16.5	14	63	Q	-	-		75-125	-		20
Lead, Total	3.3	42.2	30	63	Q	-	-		75-125	-		20
Selenium, Total	ND	9.93	7.8	78		-	-		75-125	-		20
Silver, Total	ND	24.8	21	85		-	-		75-125	-		20

## Lab Duplicate Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Project Number: 1607530

Lab Number: L1627010

Report Date: 09/15/16

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
Total Metals - Mansfield Lab Associated sample(s): 01-06 QC Batch ID: WG927131-3 QC Sample: L1626498-01 Client ID: DUP Sample						
Mercury, Total	ND	ND	mg/kg	NC		20
Total Metals - Mansfield Lab Associated sample(s): 01-06 QC Batch ID: WG927532-3 QC Sample: L1627089-01 Client ID: DUP Sample						
Arsenic, Total	1.7	2.0	mg/kg	16		20
Barium, Total	25	29	mg/kg	15		20
Cadmium, Total	ND	ND	mg/kg	NC		20
Chromium, Total	3.5	4.4	mg/kg	23	Q	20
Lead, Total	3.3	3.6	mg/kg	9		20
Selenium, Total	ND	ND	mg/kg	NC		20
Silver, Total	ND	ND	mg/kg	NC		20



# **INORGANICS & MISCELLANEOUS**

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

### SAMPLE RESULTS

**Lab ID:** L1627010-01  
**Client ID:** 1607530-B103(S1-S2)  
**Sample Location:** NEWINGTON, NH  
**Matrix:** Soil

**Date Collected:** 08/26/16 09:25  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

### Test Material Information

**Source of Material:** Unknown  
**Description of Material:** Non-Metallic - Dry Soil  
**Particle Size:** Fine  
**Preliminary Burning Time (sec):** 120

Parameter	Result	Date Analyzed	Analytical Method	Analyst
Ignitability of Solids - Westborough Lab				
Ignitability	NI	08/30/16 15:55	1,1030	AB



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

### SAMPLE RESULTS

**Lab ID:** L1627010-02  
**Client ID:** 1607530-B103(S3-S4)  
**Sample Location:** NEWINGTON, NH  
**Matrix:** Soil

**Date Collected:** 08/26/16 09:55  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

### Test Material Information

**Source of Material:** Unknown  
**Description of Material:** Non-Metallic - Damp Soil  
**Particle Size:** Medium  
**Preliminary Burning Time (sec):** 120

Parameter	Result	Date Analyzed	Analytical Method	Analyst
Ignitability of Solids - Westborough Lab				
Ignitability	NI	08/30/16 15:55	1,1030	AB



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

### SAMPLE RESULTS

**Lab ID:** L1627010-03  
**Client ID:** 1607530-B102(S1-S2)  
**Sample Location:** NEWINGTON, NH  
**Matrix:** Soil

**Date Collected:** 08/26/16 10:45  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

### Test Material Information

**Source of Material:** Unknown  
**Description of Material:** Non-Metallic - Dry Clay  
**Particle Size:** Medium  
**Preliminary Burning Time (sec):** 120

Parameter	Result	Date Analyzed	Analytical Method	Analyst
Ignitability of Solids - Westborough Lab				
Ignitability	NI	08/30/16 15:55	1,1030	AB



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

### SAMPLE RESULTS

**Lab ID:** L1627010-04  
**Client ID:** 1607530-B102(S3-S4)  
**Sample Location:** NEWINGTON, NH  
**Matrix:** Soil

**Date Collected:** 08/26/16 11:00  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

### Test Material Information

**Source of Material:** Unknown  
**Description of Material:** Non-Metallic - Wet Clay  
**Particle Size:** Medium  
**Preliminary Burning Time (sec):** 120

Parameter	Result	Date Analyzed	Analytical Method	Analyst
Ignitability of Solids - Westborough Lab				
Ignitability	NI	08/30/16 15:55	1,1030	AB



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

### SAMPLE RESULTS

**Lab ID:** L1627010-05  
**Client ID:** 1607530-B101(S1-S2)  
**Sample Location:** NEWINGTON, NH  
**Matrix:** Soil

**Date Collected:** 08/26/16 11:45  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

### Test Material Information

**Source of Material:** Unknown  
**Description of Material:** Non-Metallic - Damp Soil  
**Particle Size:** Medium  
**Preliminary Burning Time (sec):** 120

Parameter	Result	Date Analyzed	Analytical Method	Analyst
Ignitability of Solids - Westborough Lab				
Ignitability	NI	08/30/16 23:45	1,1030	SB



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

### SAMPLE RESULTS

**Lab ID:** L1627010-06  
**Client ID:** 1607530-B101(S3-S4)  
**Sample Location:** NEWINGTON, NH  
**Matrix:** Soil

**Date Collected:** 08/26/16 12:00  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

### Test Material Information

**Source of Material:** Unknown  
**Description of Material:** Non-Metallic - Damp Soil  
**Particle Size:** Medium  
**Preliminary Burning Time (sec):** 120

Parameter	Result	Date Analyzed	Analytical Method	Analyst
Ignitability of Solids - Westborough Lab				
Ignitability	NI	08/30/16 23:45	1,1030	SB



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

**Lab ID:** L1627010-01  
**Client ID:** 1607530-B103(S1-S2)  
**Sample Location:** NEWINGTON, NH  
**Matrix:** Soil

**Date Collected:** 08/26/16 09:25  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
<b>General Chemistry - Westborough Lab</b>										
Specific Conductance @ 25 C	ND		umhos/cm	10	--	1	-	08/30/16 19:35	1,9050A	AS
Solids, Total	93.3		%	0.100	NA	1	-	08/30/16 16:09	121,2540G	RI
pH (H)	5.7		SU	-	NA	1	-	08/30/16 01:30	1,9045D	MC
Cyanide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 23:01	1,7.3	TL
Sulfide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 22:53	1,7.3	TL
Oxidation/Reduction Potential	170		mv	-	NA	1	-	08/30/16 02:19	68,1498	MC





**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

**Lab ID:** L1627010-02  
**Client ID:** 1607530-B103(S3-S4)  
**Sample Location:** NEWINGTON, NH  
**Matrix:** Soil

**Date Collected:** 08/26/16 09:55  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
<b>General Chemistry - Westborough Lab</b>										
Specific Conductance @ 25 C	44		umhos/cm	10	--	1	-	08/30/16 19:35	1,9050A	AS
Solids, Total	92.4		%	0.100	NA	1	-	08/30/16 16:09	121,2540G	RI
pH (H)	7.0		SU	-	NA	1	-	08/30/16 01:30	1,9045D	MC
Cyanide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 23:01	1,7.3	TL
Sulfide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 22:53	1,7.3	TL
Oxidation/Reduction Potential	150		mv	-	NA	1	-	08/30/16 02:19	68,1498	MC



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

**Lab ID:** L1627010-03  
**Client ID:** 1607530-B102(S1-S2)  
**Sample Location:** NEWINGTON, NH  
**Matrix:** Soil

**Date Collected:** 08/26/16 10:45  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
<b>General Chemistry - Westborough Lab</b>										
Specific Conductance @ 25 C	ND		umhos/cm	10	--	1	-	08/30/16 19:35	1,9050A	AS
Solids, Total	83.6		%	0.100	NA	1	-	08/30/16 16:09	121,2540G	RI
pH (H)	6.3		SU	-	NA	1	-	08/30/16 01:30	1,9045D	MC
Cyanide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 23:01	1,7.3	TL
Sulfide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 22:53	1,7.3	TL
Oxidation/Reduction Potential	170		mv	-	NA	1	-	08/30/16 02:19	68,1498	MC



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

**Lab ID:** L1627010-04  
**Client ID:** 1607530-B102(S3-S4)  
**Sample Location:** NEWINGTON, NH  
**Matrix:** Soil

**Date Collected:** 08/26/16 11:00  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
<b>General Chemistry - Westborough Lab</b>										
Specific Conductance @ 25 C	28		umhos/cm	10	--	1	-	08/30/16 19:35	1,9050A	AS
Solids, Total	79.2		%	0.100	NA	1	-	08/30/16 16:09	121,2540G	RI
pH (H)	7.4		SU	-	NA	1	-	08/30/16 01:30	1,9045D	MC
Cyanide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 23:01	1,7.3	TL
Sulfide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 22:53	1,7.3	TL
Oxidation/Reduction Potential	190		mv	-	NA	1	-	08/30/16 02:19	68,1498	MC



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

**Lab ID:** L1627010-05  
**Client ID:** 1607530-B101(S1-S2)  
**Sample Location:** NEWINGTON, NH  
**Matrix:** Soil

**Date Collected:** 08/26/16 11:45  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
<b>General Chemistry - Westborough Lab</b>										
Specific Conductance @ 25 C	ND		umhos/cm	10	--	1	-	08/30/16 19:35	1,9050A	AS
Solids, Total	84.2		%	0.100	NA	1	-	08/30/16 16:09	121,2540G	RI
pH (H)	6.2		SU	-	NA	1	-	08/30/16 01:30	1,9045D	MC
Cyanide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 23:02	1,7.3	TL
Sulfide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 22:54	1,7.3	TL
Oxidation/Reduction Potential	180		mv	-	NA	1	-	08/30/16 02:19	68,1498	MC



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**SAMPLE RESULTS**

**Lab ID:** L1627010-06  
**Client ID:** 1607530-B101(S3-S4)  
**Sample Location:** NEWINGTON, NH  
**Matrix:** Soil

**Date Collected:** 08/26/16 12:00  
**Date Received:** 08/29/16  
**Field Prep:** Not Specified

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
<b>General Chemistry - Westborough Lab</b>										
Specific Conductance @ 25 C	ND		umhos/cm	10	--	1	-	08/30/16 19:35	1,9050A	AS
Solids, Total	80.9		%	0.100	NA	1	-	08/30/16 16:09	121,2540G	RI
pH (H)	6.4		SU	-	NA	1	-	08/30/16 01:30	1,9045D	MC
Cyanide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 23:02	1,7.3	TL
Sulfide, Reactive	ND		mg/kg	10	--	1	08/30/16 22:05	08/30/16 22:54	1,7.3	TL
Oxidation/Reduction Potential	170		mv	-	NA	1	-	08/30/16 02:19	68,1498	MC



Project Name: EVERSOURCE NH SRP

Lab Number: L1627010

Project Number: 1607530

Report Date: 09/15/16

**Method Blank Analysis**  
**Batch Quality Control**

Parameter	Result Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
General Chemistry - Westborough Lab for sample(s): 01-06 Batch: WG927398-1									
Cyanide, Reactive	ND	mg/kg	10	--	1	08/30/16 22:05	08/30/16 23:00	1,7.3	TL
General Chemistry - Westborough Lab for sample(s): 01-06 Batch: WG927400-1									
Sulfide, Reactive	ND	mg/kg	10	--	1	08/30/16 22:05	08/30/16 22:52	1,7.3	TL

## Lab Control Sample Analysis

### Batch Quality Control

**Project Name:** EVERSOURCE NH SRP

**Project Number:** 1607530

**Lab Number:** L1627010

**Report Date:** 09/15/16

Parameter	LCS		LCSD		%Recovery Limits	RPD	Qual	RPD Limits
	%Recovery	Qual	%Recovery	Qual				
General Chemistry - Westborough Lab Associated sample(s): 01-06 Batch: WG927110-1								
pH	100		-		99-101	-		
General Chemistry - Westborough Lab Associated sample(s): 01-06 Batch: WG927111-1								
Oxidation/Reduction Potential	98		-		90-110	-		20
General Chemistry - Westborough Lab Associated sample(s): 01-06 Batch: WG927398-2								
Cyanide, Reactive	48		-		30-125	-		40
General Chemistry - Westborough Lab Associated sample(s): 01-06 Batch: WG927400-2								
Sulfide, Reactive	98		-		60-125	-		40
General Chemistry - Westborough Lab Associated sample(s): 01-06 Batch: WG927422-1								
Specific Conductance	100		-		99-101	-		

## Lab Duplicate Analysis

Batch Quality Control

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
General Chemistry - Westborough Lab Associated sample(s): 01-06 QC Batch ID: WG927110-2 QC Sample: L1627010-01 Client ID: 1607530-B103(S1-S2)						
pH (H)	5.7	5.7	SU	0		5
General Chemistry - Westborough Lab Associated sample(s): 01-06 QC Batch ID: WG927111-2 QC Sample: L1627010-01 Client ID: 1607530-B103(S1-S2)						
Oxidation/Reduction Potential	170	170	mv	0		20
General Chemistry - Westborough Lab Associated sample(s): 01-06 QC Batch ID: WG927364-1 QC Sample: L1627010-01 Client ID: 1607530-B103(S1-S2)						
Solids, Total	93.3	92.4	%	1		20
General Chemistry - Westborough Lab Associated sample(s): 01-06 QC Batch ID: WG927398-3 QC Sample: L1627028-01 Client ID: DUP Sample						
Cyanide, Reactive	ND	ND	mg/kg	NC		40
General Chemistry - Westborough Lab Associated sample(s): 01-06 QC Batch ID: WG927400-3 QC Sample: L1627028-01 Client ID: DUP Sample						
Sulfide, Reactive	ND	ND	mg/kg	NC		40
General Chemistry - Westborough Lab Associated sample(s): 01-06 QC Batch ID: WG927422-2 QC Sample: L1627026-01 Client ID: DUP Sample						
Specific Conductance	74	97	umhos/cm	27	Q	20



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

### Sample Receipt and Container Information

Were project specific reporting limits specified? YES

**Reagent H2O Preserved Vials Frozen on:** 08/29/2016 22:27

#### Cooler Information Custody Seal

##### Cooler

A Absent  
 B Absent

#### Container Information

Container ID	Container Type	Cooler	pH	Temp deg C	Pres	Seal	Analysis(*)
L1627010-01A	Vial MeOH preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-01B	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-01C	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-01D	Metals Only - Glass 60mL/2oz unp	A	N/A	2.4	Y	Absent	AS-TI(180),BA-TI(180),AG-TI(180),CR-TI(180),PB-TI(180),SE-TI(180),HG-T(28),CD-TI(180)
L1627010-01E	Glass 60mL/2oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-01F	Glass 120ml/4oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-01G	Glass 500ml/16oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-01H	Plastic 250ml unpreserved	B	N/A	3.1	Y	Absent	SUB-537()
L1627010-01X	Glass 120ml/4oz unpreserved/No H	A	N/A	2.4	Y	Absent	HEXCR-RELOG()
L1627010-02A	Vial MeOH preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-02B	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-02C	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-02D	Metals Only - Glass 60mL/2oz unp	A	N/A	2.4	Y	Absent	AS-TI(180),BA-TI(180),AG-TI(180),CR-TI(180),PB-TI(180),SE-TI(180),HG-T(28),CD-TI(180)

\*Values in parentheses indicate holding time in days

Project Name: EVERSOURCE NH SRP

Project Number: 1607530

Lab Number: L1627010

Report Date: 09/15/16

## Container Information

Container ID	Container Type	Cooler	pH	Temp deg C	Pres	Seal	Analysis(*)
L1627010-02E	Glass 60mL/2oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-02F	Glass 120ml/4oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-02G	Glass 500ml/16oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-02H	Plastic 250ml unpreserved	B	N/A	3.1	Y	Absent	SUB-537()
L1627010-02X	Glass 120ml/4oz unpreserved/No H	A	N/A	2.4	Y	Absent	HEXCR-RELOG()
L1627010-03A	Vial MeOH preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-03B	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-03C	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-03D	Metals Only - Glass 60mL/2oz unp	A	N/A	2.4	Y	Absent	AS-TI(180),BA-TI(180),AG-TI(180),CR-TI(180),PB-TI(180),SE-TI(180),HG-T(28),CD-TI(180)
L1627010-03E	Glass 60mL/2oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-03F	Glass 120ml/4oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-03G	Glass 500ml/16oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-03H	Plastic 250ml unpreserved	B	N/A	3.1	Y	Absent	SUB-537()
L1627010-03X	Glass 120ml/4oz unpreserved/No H	A	N/A	2.4	Y	Absent	HEXCR-RELOG()
L1627010-04A	Vial MeOH preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-04B	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-04C	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)

\*Values in parentheses indicate holding time in days



Project Name: EVERSOURCE NH SRP

Project Number: 1607530

Lab Number: L1627010

Report Date: 09/15/16

## Container Information

Container ID	Container Type	Cooler	pH	Temp deg C	Pres	Seal	Analysis(*)
L1627010-04D	Metals Only - Glass 60mL/2oz unp	A	N/A	2.4	Y	Absent	AS-TI(180),BA-TI(180),AG-TI(180),CR-TI(180),PB-TI(180),SE-TI(180),HG-T(28),CD-TI(180)
L1627010-04E	Glass 60mL/2oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-04F	Glass 120ml/4oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-04G	Glass 500ml/16oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-04H	Plastic 250ml unpreserved	B	N/A	3.1	Y	Absent	SUB-537()
L1627010-04X	Glass 120ml/4oz unpreserved/No H	A	N/A	2.4	Y	Absent	HEXCR-RELOG()
L1627010-05A	Vial MeOH preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-05B	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-05C	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-05D	Metals Only - Glass 60mL/2oz unp	A	N/A	2.4	Y	Absent	AS-TI(180),BA-TI(180),AG-TI(180),CR-TI(180),PB-TI(180),SE-TI(180),HG-T(28),CD-TI(180)
L1627010-05E	Glass 60mL/2oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-05F	Glass 120ml/4oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-05G	Glass 500ml/16oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-05H	Plastic 250ml unpreserved	B	N/A	3.1	Y	Absent	SUB-537()
L1627010-05X	Glass 120ml/4oz unpreserved/No H	A	N/A	2.4	Y	Absent	HEXCR-RELOG()
L1627010-06A	Vial MeOH preserved	A	N/A	2.4	Y	Absent	8260H(14)

\*Values in parentheses indicate holding time in days



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

**Container Information**

Container ID	Container Type	Cooler	pH	Temp deg C	Pres	Seal	Analysis(*)
L1627010-06B	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-06C	Vial water preserved	A	N/A	2.4	Y	Absent	8260H(14)
L1627010-06D	Metals Only - Glass 60mL/2oz unp	A	N/A	2.4	Y	Absent	AS-TI(180),BA-TI(180),AG-TI(180),CR-TI(180),PB-TI(180),SE-TI(180),HG-T(28),CD-TI(180)
L1627010-06E	Glass 60mL/2oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-06F	Glass 120ml/4oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-06G	Glass 500ml/16oz unpreserved	A	N/A	2.4	Y	Absent	8270TCL(14),IGNIT-1030(14),ORP-9045(1),REACTS(14),PCB-8082(14),TS(7),PH-9045(1),REACTCN(14),TPH-DRO-D(14),COND-9050(28)
L1627010-06H	Plastic 250ml unpreserved	B	N/A	3.1	Y	Absent	SUB-537()
L1627010-06X	Glass 120ml/4oz unpreserved/No H	A	N/A	2.4	Y	Absent	HEXCR-RELOG()

\*Values in parentheses indicate holding time in days



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

## GLOSSARY

### Acronyms

EDL	- Estimated Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The EDL includes any adjustments from dilutions, concentrations or moisture content, where applicable. The use of EDLs is specific to the analysis of PAHs using Solid-Phase Microextraction (SPME).
EPA	- Environmental Protection Agency.
LCS	- Laboratory Control Sample: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
LCSD	- Laboratory Control Sample Duplicate: Refer to LCS.
LFB	- Laboratory Fortified Blank: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
MDL	- Method Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The MDL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
MS	- Matrix Spike Sample: A sample prepared by adding a known mass of target analyte to a specified amount of matrix sample for which an independent estimate of target analyte concentration is available.
MSD	- Matrix Spike Sample Duplicate: Refer to MS.
NA	- Not Applicable.
NC	- Not Calculated: Term is utilized when one or more of the results utilized in the calculation are non-detect at the parameter's reporting unit.
NDPA/DPA	- N-Nitrosodiphenylamine/Diphenylamine.
NI	- Not Ignitable.
NP	- Non-Plastic: Term is utilized for the analysis of Atterberg Limits in soil.
RL	- Reporting Limit: The value at which an instrument can accurately measure an analyte at a specific concentration. The RL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
RPD	- Relative Percent Difference: The results from matrix and/or matrix spike duplicates are primarily designed to assess the precision of analytical results in a given matrix and are expressed as relative percent difference (RPD). Values which are less than five times the reporting limit for any individual parameter are evaluated by utilizing the absolute difference between the values; although the RPD value will be provided in the report.
SRM	- Standard Reference Material: A reference sample of a known or certified value that is of the same or similar matrix as the associated field samples.
STLP	- Semi-dynamic Tank Leaching Procedure per EPA Method 1315.
TIC	- Tentatively Identified Compound: A compound that has been identified to be present and is not part of the target compound list (TCL) for the method and/or program. All TICs are qualitatively identified and reported as estimated concentrations.

### Footnotes

- 1 - The reference for this analyte should be considered modified since this analyte is absent from the target analyte list of the original method.

### Terms

**Total:** With respect to Organic analyses, a 'Total' result is defined as the summation of results for individual isomers or Aroclors. If a 'Total' result is requested, the results of its individual components will also be reported. This is applicable to 'Total' results for methods 8260, 8081 and 8082.

**Analytical Method:** Both the document from which the method originates and the analytical reference method. (Example: EPA 8260B is shown as 1,8260B.) The codes for the reference method documents are provided in the References section of the Addendum.

### Data Qualifiers

- A** - Spectra identified as "Aldol Condensation Product".
- B** - The analyte was detected above the reporting limit in the associated method blank. Flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For MCP-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For DOD-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank AND the analyte was detected above one-half the reporting limit (or above the reporting limit for common lab contaminants) in the associated method blank. For NJ-Air-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte above the reporting limit. For NJ-related projects (excluding Air), flag only applies to associated field samples that have detectable concentrations of the analyte, which was detected above the reporting limit in the associated method blank or above five times the

**Report Format:** Data Usability Report



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

#### Data Qualifiers

- reporting limit for common lab contaminants (Phthalates, Acetone, Methylene Chloride, 2-Butanone).
- C** - Co-elution: The target analyte co-elutes with a known lab standard (i.e. surrogate, internal standards, etc.) for co-extracted analyses.
  - D** - Concentration of analyte was quantified from diluted analysis. Flag only applies to field samples that have detectable concentrations of the analyte.
  - E** - Concentration of analyte exceeds the range of the calibration curve and/or linear range of the instrument.
  - G** - The concentration may be biased high due to matrix interferences (i.e. co-elution) with non-target compound(s). The result should be considered estimated.
  - H** - The analysis of pH was performed beyond the regulatory-required holding time of 15 minutes from the time of sample collection.
  - I** - The lower value for the two columns has been reported due to obvious interference.
  - M** - Reporting Limit (RL) exceeds the MCP CAM Reporting Limit for this analyte.
  - NJ** - Presumptive evidence of compound. This represents an estimated concentration for Tentatively Identified Compounds (TICs), where the identification is based on a mass spectral library search.
  - P** - The RPD between the results for the two columns exceeds the method-specified criteria.
  - Q** - The quality control sample exceeds the associated acceptance criteria. For DOD-related projects, LCS and/or Continuing Calibration Standard exceedences are also qualified on all associated sample results. Note: This flag is not applicable for matrix spike recoveries when the sample concentration is greater than 4x the spike added or for batch duplicate RPD when the sample concentrations are less than 5x the RL. (Metals only.)
  - R** - Analytical results are from sample re-analysis.
  - RE** - Analytical results are from sample re-extraction.
  - S** - Analytical results are from modified screening analysis.
  - J** - Estimated value. This represents an estimated concentration for Tentatively Identified Compounds (TICs).
  - ND** - Not detected at the reporting limit (RL) for the sample.

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1627010  
**Report Date:** 09/15/16

## REFERENCES

- 1 Test Methods for Evaluating Solid Waste: Physical/Chemical Methods. EPA SW-846. Third Edition. Updates I - IV, 2007.
- 68 Annual Book of ASTM (American Society for Testing and Materials) Standards following extraction by SW-846 EPA Method 9045C under the requirements of MADEP BWSC, WSC-CAM-VIB. August 2004.
- 121 Standard Methods for the Examination of Water and Wastewater. APHA-AWWA-WEF. Standard Methods Online.

## LIMITATION OF LIABILITIES

Alpha Analytical performs services with reasonable care and diligence normal to the analytical testing laboratory industry. In the event of an error, the sole and exclusive responsibility of Alpha Analytical shall be to re-perform the work at it's own expense. In no event shall Alpha Analytical be held liable for any incidental, consequential or special damages, including but not limited to, damages in any way connected with the use of, interpretation of, information or analysis provided by Alpha Analytical.

We strongly urge our clients to comply with EPA protocol regarding sample volume, preservation, cooling, containers, sampling procedures, holding time and splitting of samples in the field.



## Certification Information

---

The following analytes are not included in our Primary NELAP Scope of Accreditation:

### Westborough Facility

**EPA 624:** m/p-xylene, o-xylene

**EPA 8260C:** NPW: 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene, Azobenzene; SCM: Iodomethane (methyl iodide), Methyl methacrylate, 1,2,4,5-Tetramethyl benzene; 4-Ethyltoluene.

**EPA 8270D:** NPW: Dimethylnaphthalene,1,4-Diphenylhydrazine; SCM: Dimethylnaphthalene,1,4-Diphenylhydrazine.

**EPA 300:** DW: Bromide

**EPA 6860:** NPW and SCM: Perchlorate

**EPA 9010:** NPW and SCM: Amenable Cyanide Distillation

**EPA 9012B:** NPW: Total Cyanide

**EPA 9050A:** NPW: Specific Conductance

**SM3500:** NPW: Ferrous Iron

**SM4500:** NPW: Amenable Cyanide, Dissolved Oxygen; SCM: Total Phosphorus, TKN, NO<sub>2</sub>, NO<sub>3</sub>.

**SM5310C:** DW: Dissolved Organic Carbon

### Mansfield Facility

**SM 2540D:** TSS

**EPA 3005A** NPW

**EPA 8082A:** NPW: PCB: 1, 5, 31, 87,101, 110, 141, 151, 153, 180, 183, 187.

**EPA TO-15:** Halothane, 2,4,4-Trimethyl-2-pentene, 2,4,4-Trimethyl-1-pentene, Thiophene, 2-Methylthiophene,

3-Methylthiophene, 2-Ethylthiophene, 1,2,3-Trimethylbenzene, Indan, Indene, 1,2,4,5-Tetramethylbenzene, Benzothiophene, 1-Methylnaphthalene.

**Biological Tissue Matrix:** **EPA 3050B**

---

The following analytes are included in our Massachusetts DEP Scope of Accreditation

### Westborough Facility:

#### Drinking Water

**EPA 300.0:** Nitrate-N, Fluoride, Sulfate; **EPA 353.2:** Nitrate-N, Nitrite-N; **SM4500NO3-F:** Nitrate-N, Nitrite-N; **SM4500F-C, SM4500CN-CE, EPA 180.1, SM2130B, SM4500CI-D, SM2320B, SM2540C, SM4500H-B**

**EPA 332:** Perchlorate; **EPA 524.2:** THMs and VOCs; **EPA 504.1:** EDB, DBCP.

**Microbiology:** **SM9215B; SM9223-P/A, SM9223B-Colilert-QT, SM9222D.**

#### Non-Potable Water

**SM4500H,B, EPA 120.1, SM2510B, SM2540C, SM2320B, SM4500CL-E, SM4500F-BC, SM4500NH3-BH, EPA 350.1:** Ammonia-N, **LACHAT 10-107-06-1-B:** Ammonia-N, **SM4500NO3-F, EPA 353.2:** Nitrate-N, **EPA 351.1, SM4500P-E, SM4500P-B, E, SM4500SO4-E, SM5220D, EPA 410.4, SM5210B, SM5310C, SM4500CL-D, EPA 1664, EPA 420.1, SM4500-CN-CE, SM2540D.**

**EPA 624:** Volatile Halocarbons & Aromatics,

**EPA 608:** Chlordane, Toxaphene, Aldrin, alpha-BHC, beta-BHC, gamma-BHC, delta-BHC, Dieldrin, DDD, DDE, DDT, Endosulfan I, Endosulfan II, Endosulfan sulfate, Endrin, Endrin Aldehyde, Heptachlor, Heptachlor Epoxide, PCBs

**EPA 625:** SVOC (Acid/Base/Neutral Extractables), **EPA 600/4-81-045:** PCB-Oil.

**Microbiology:** **SM9223B-Colilert-QT; Enterolert-QT, SM9222D-MF.**

### Mansfield Facility:

#### Drinking Water

**EPA 200.7:** Ba, Be, Cd, Cr, Cu, Ni, Na, Ca. **EPA 200.8:** Sb, As, Ba, Be, Cd, Cr, Cu, Pb, Ni, Se, TL. **EPA 245.1 Hg.**

#### Non-Potable Water

**EPA 200.7:** Al, Sb, As, Be, Cd, Ca, Cr, Co, Cu, Fe, Pb, Mg, Mn, Mo, Ni, K, Se, Ag, Na, Sr, TL, Ti, V, Zn.

**EPA 200.8:** Al, Sb, As, Be, Cd, Cr, Cu, Pb, Mn, Ni, Se, Ag, TL, Zn.

**EPA 245.1 Hg.**

**SM2340B**

---

For a complete listing of analytes and methods, please contact your Alpha Project Manager.



08/29/16

L1627010

<b>Chain-of-Custody Record</b>	<b>Laboratory:</b> Alpha	<b>Laboratory Job #</b> (Lab use only)
--------------------------------	--------------------------	---



**GEI**  
Consultants

400 Unicorn Park Drive  
Woburn, MA 01801  
PH: 781.721.4000  
FX: 781.721.4073

Project Information	
Project Name: Eversource NH SRP	Project Location: Newington, NH
Project Number: 1607530	Project Manager: Mike Sabulis (office: 781-721-4114) (cell: 508-633-9544)

Page 1 of 1

Send Report to: Jess Englehart	<b>Preservative</b>								
Send EDD to: labdata@geiconsultants.com	<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td style="width:5%;">MeOH</td> <td style="width:10%; text-align: center;">-</td> <td style="width:10%; text-align: center;">-</td> <td style="width:10%; text-align: center;">-</td> <td style="width:10%; text-align: center;">-</td> <td style="width:10%; text-align: center;">-</td> <td style="width:10%; text-align: center;">-</td> <td style="width:10%; text-align: center;">-</td> </tr> </table>	MeOH	-	-	-	-	-	-	-
MeOH	-	-	-	-	-	-	-		
<b>Analysis</b>									

Sample Handling

**MCP PRESUMPTIVE CERTAINTY REQUIRED -- YES NO**

If Yes, Are MCP Analytical Methods Required?	YES	NO	NA
If Yes, Are Drinking Water Samples Submitted?	YES	NO	NA
If Yes, Have You Met Minimum Field QC Requirements?	YES	NO	NA

Samples Field Filtered  
YES NO NA

Sampled Shipped  
With Ice  
YES NO

Lab Sample Number	GEI Sample ID	Collection		Matrix	No. of Bottles	Sampler(s) Initials	VOC	SVOCs	TPH (8100M)	PCBs	RCRA 8Metals + TCLP (if necessary)*	Cond/Corr/Ignitability	Sulfide-Cyanide Reactivity	Hex Cr w/ pH and redox (if necessary)**	Sample Specific Remarks
		Date	Time												
	1607530-B103(S1-S2)	8/26/16	0925	SO	8	MEG	X	X	X	X	X	X	X	X	
	- B103(S3-S4)		0953												
	B102(S1-S2)		1045												
	B102(S3-S4)		1100												
	B101(S1-S2)		1145												
	B101(S3-S4)		1200												

**MCP Level Needed:** GEI requires the most stringent Method 1 MCP standard be met for all analytes whenever possible.

**Turnaround Time (Business days):**

Normal  X  Other    

10-Day      7-Day    

5-Day      3-Day    

Before submitting rush turnaround samples, you **must** notify the laboratory to confirm that the TAT can be achieved.

Relinquished by: (signature)	Date:	Time:	Received by: (signature)
1. Molly Green	8/27/16	14:50	1. GEI fridge
Relinquished by: (signature)	Date:	Time:	Received by: (signature)
2. GEI Fridge	8/29/16	1120	2. J. Englehart
Relinquished by: (signature)	Date:	Time:	Received by: (signature)
3. J. Englehart	8/29/16	1120	3. Charles Floyd
Relinquished by: (signature)	Date:	Time:	Received by: (signature)
4. Charles Floyd	8/29/16	17:20	4. Andrew Smith

Additional Requirements/Comments/Remarks:

\*Please run TCLP on analyses that exceed 20x rule.

\*\*Please run Hex Cr if total Cr exceeds 100ppm. Please run ORP ASAP as it has a 24-hr hold time.



08/29/16

L1627010

<b>Chain-of-Custody Record</b>	<b>Laboratory:</b> Alpha	<b>Laboratory Job #</b> (Lab use only)
--------------------------------	--------------------------	---



**GEI**  
Consultants

400 Unicorn Park Drive  
Woburn, MA 01801  
PH: 781.721.4000  
FX: 781.721.4073

Project Information	
Project Name: Eversource NH SRP	Project Location: Newington, NH
Project Number: 1607530	Project Manager: Mike Sabulis (office: 781-721-4114) (cell: 508-633-9544)
Send Report to: Jess Englehart	Preservative - -
Send EDD to: labdata@geiconsultants.com	
Analysis	

Page 1 of 1

**MCP PRESUMPTIVE CERTAINTY REQUIRED -- YES NO**

If Yes, Are MCP Analytical Methods Required?	YES	NO	NA
If Yes, Are Drinking Water Samples Submitted?	YES	NO	NA
If Yes, Have You Met Minimum Field QC Requirements?	YES	NO	NA

Sample Handling		
Samples Field Filtered	YES	NO
Sampled Shipped With Ice	YES	NO

Lab Sample Number	GEI Sample ID	Collection		Matrix	No. of Bottles	Sampler(s) Initials	PFOS	PFOA											Sample Specific Remarks			
		Date	Time																			
	1607530-B103(S1-S2)	8/26/16	09:25	SO	1	MEG	X	X														
	B103(S3-S4)	↓	09:55	↓	↓	↓	↓	↓														
	B102(S1-S2)	↓	10:45	↓	↓	↓	↓	↓														
	B102(S3-S4)	↓	11:00	↓	↓	↓	↓	↓														
	B101(S1-S2)	↓	11:45	↓	↓	↓	↓	↓														
	B101(S3-S4)	↓	12:00	↓	↓	↓	↓	↓														

**MCP Level Needed:** GEI requires the most stringent Method 1 MCP standard be met for all analytes whenever possible.

Turnaround Time (Business days):
Normal <u>X</u> Other <u>    </u>
10-Day <u>    </u> 7-Day <u>    </u>
5-Day <u>    </u> 3-Day <u>    </u>

Before submitting rush turnaround samples, you **must** notify the laboratory to confirm that the TAT can be achieved.

Relinquished by: (signature)	Date:	Time:	Received by: (signature)
1. Molly Owen	8/27/16	14:50	1. GEI Fridge
Relinquished by: (signature)	Date:	Time:	Received by: (signature)
2. GEI Fridge	8/29/16	11:20	2. J. Englehart
Relinquished by: (signature)	Date:	Time:	Received by: (signature)
3. J. Englehart	8/29/16	11:20	3. [Signature]
Relinquished by: (signature)	Date:	Time:	Received by: (signature)
4. [Signature]	8/29/16	17:20	4. [Signature]

**Additional Requirements/Comments/Remarks:**



September 15, 2016

**Vista Work Order No. 1601099**

Ms. Karyn Raymond  
Alpha Analytical Laboratory  
8 Walkup Drive  
Westborough, MA 01581

Dear Ms. Raymond,

Enclosed are the amended results for the sample set received at Vista Analytical Laboratory on August 31, 2016. This sample set was analyzed on a rush turn-around time. The SDG Number is L1627010.

Vista Analytical Laboratory is committed to serving you effectively. If you require additional information, please contact me at 916-673-1520 or by email at [mmaier@vista-analytical.com](mailto:mmaier@vista-analytical.com).

Thank you for choosing Vista as part of your analytical support team.

Sincerely,

A handwritten signature in black ink that reads "Karen Lopez" followed by the word "for" in a smaller, cursive font.

Martha Maier  
Laboratory Director



*Vista Analytical Laboratory certifies that the report herein meets all the requirements set forth by NELAP for those applicable test methods. Results relate only to the samples as received by the laboratory. This report should not be reproduced except in full without the written approval of Vista.*

**SDG Number L1627010**

**Vista Work Order No. 1601099**

**Case Narrative**

**Sample Condition on Receipt:**

Six soil samples were received in good condition and within the method temperature requirements. The samples were received and stored securely in accordance with Vista standard operating procedures and EPA methodology. This report was amended to reflect Alpha job number L1627010 rather than L1626010.

**Analytical Notes:**

**Modified EPA Method 537**

The samples were extracted and analyzed for PFOA and PFOS using Modified EPA Method 537. The results include both linear and branched isomers.

**Holding Times**

The samples were extracted and analyzed within the method hold times.

**Quality Control**

The Initial Calibration and Continuing Calibration Verifications met the acceptance criteria.

A Method Blank and Ongoing Precision and Recovery (OPR) sample were extracted and analyzed with the preparation batch. No analytes were detected in the Method Blank above the Reporting Limit. The OPR recoveries were within the method acceptance criteria.

The recoveries of all internal standards in the QC and field samples were within the acceptance criteria.

TABLE OF CONTENTS

Case Narrative.....	1
Table of Contents.....	3
Sample Inventory.....	4
Analytical Results.....	5
Qualifiers.....	14
Certifications.....	15
Sample Receipt.....	18

# Sample Inventory Report

<b>Vista Sample ID</b>	<b>Client Sample ID</b>	<b>Sampled</b>	<b>Received</b>	<b>Components/Containers</b>
1601099-01	1607530-B103(S1-S2)	26-Aug-16 09:25	31-Aug-16 09:33	HDPE Jar, 4 oz
1601099-02	1607530-B103(S3-S4)	26-Aug-16 09:55	31-Aug-16 09:33	HDPE Jar, 4 oz
1601099-03	1607530-B102(S1-S2)	26-Aug-16 10:45	31-Aug-16 09:33	HDPE Jar, 4 oz
1601099-04	1607530-B102(S3-S4)	26-Aug-16 11:00	31-Aug-16 09:33	HDPE Jar, 4 oz
1601099-05	1607530-B101(S1-S2)	26-Aug-16 11:45	31-Aug-16 09:33	HDPE Jar, 4 oz
1601099-06	1607530-B101(S3-S4)	26-Aug-16 12:00	31-Aug-16 09:33	HDPE Jar, 4 oz

Vista Project: 1601099

## **ANALYTICAL RESULTS**

Sample ID: Method Blank				VAL - PFAS			
Matrix: Solid		QC Batch: B6I0041		Lab Sample: B6I0041-BLK1			
Sample Size: 1.00 g		Date Extracted: 08-Sep-2016 14:54		Date Analyzed: 12-Sep-16 19:47	Column: BEH C18	Analyst: AC	
Analyte	Conc. (ng/g)	RL	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	2.00		IS 13C2-PFOA	124	60 - 150	
PFOS	ND	2.00		IS 13C8-PFOS	109	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

The results are reported in dry weight

The sample size is reported in wet weight

Results reported to RL

When reported, PFBS, PFHxS and PFOS include both linear and branched isomers Only the linear isomer is reported for all other analytes



Sample ID: OPR					VAL - PFAS		
Matrix: Solid	QC Batch: B6I0041		Lab Sample: B6I0041-BS1				
Sample Size: 1.00 g	Date Extracted: 08-Sep-2016 14:54		Date Analyzed: 12-Sep-16 18:56 Column: BEH C18 Analyst: AC				
Analyte	Amt Found (ng/g)	Spike Amt	%R	Limits	Labeled Standard	%R	LCL-UCL
PFOA	9.89	10.0	98.9	70 - 130	IS 13C2-PFOA	123	60 - 150
PFOS	10.7	10.0	107	70 - 130	IS 13C8-PFOS	105	60 - 150

LCL-UCL - Lower control limit - upper control limit

**Sample ID: 1607530-B103(S1-S2)****VAL - PFAS**

Client Data			Sample Data		Laboratory Data			
Name:	Alpha Analytical Laboratory		Matrix:	Soil	Lab Sample:	1601099-01	Date Received:	31-Aug-2016 9:33
Project:			Sample Size:	1.46 g	QC Batch:	B6I0041	Date Extracted:	08-Sep-2016 14:54
Date Collected:	26-Aug-2016 9:25		% Solids:	71.0	Date Analyzed:	13-Sep-16 02:56 Column: BEH C18 Analyst: AC		
Analyte	Conc. (ng/g)	RL	Qualifiers		Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	1.93			IS 13C2-PFOA	137	60 - 150	
PFOS	ND	1.93			IS 13C8-PFOS	76.3	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

The results are reported in dry weight

The sample size is reported in wet weight

Results reported to RL

When reported, PFBS, PFHxS and PFOS include both linear and branched isomers Only the linear isomer is reported for all other analytes

**Sample ID: 1607530-B103(S3-S4)****VAL - PFAS**

Client Data			Sample Data		Laboratory Data			
Name:	Alpha Analytical Laboratory		Matrix:	Soil	Lab Sample:	1601099-02	Date Received:	31-Aug-2016 9:33
Project:			Sample Size:	1.23 g	QC Batch:	B6I0041	Date Extracted:	08-Sep-2016 14:54
Date Collected:	26-Aug-2016 9:55		% Solids:	80.4	Date Analyzed:	13-Sep-16 03:09 Column: BEH C18 Analyst: AC		
Analyte	Conc. (ng/g)	RL	Qualifiers		Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	2.02			IS 13C2-PFOA	130	60 - 150	
PFOS	ND	2.02			IS 13C8-PFOS	81.7	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

The results are reported in dry weight

The sample size is reported in wet weight

Results reported to RL

When reported, PFBS, PFHxS and PFOS include both linear and branched isomers Only the linear isomer is reported for all other analytes

**Sample ID: 1607530-B102(S1-S2)****VAL - PFAS**

Client Data			Sample Data		Laboratory Data			
Name:	Alpha Analytical Laboratory		Matrix:	Soil	Lab Sample:	1601099-03	Date Received:	31-Aug-2016 9:33
Project:			Sample Size:	1.37 g	QC Batch:	B6I0041	Date Extracted:	08-Sep-2016 14:54
Date Collected:	26-Aug-2016 10:45		% Solids:	75.0	Date Analyzed:	13-Sep-16 03:21 Column: BEH C18 Analyst: AC		
Analyte	Conc. (ng/g)	RL	Qualifiers		Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	1.95			IS 13C2-PFOA	150	60 - 150	
PFOS	ND	1.95			IS 13C8-PFOS	99.6	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

The results are reported in dry weight

The sample size is reported in wet weight

Results reported to RL

When reported, PFBS, PFHxS and PFOS include both linear and branched isomers Only the linear isomer is reported for all other analytes

**Sample ID: 1607530-B102(S3-S4)****VAL - PFAS**

Client Data			Sample Data		Laboratory Data			
Name:	Alpha Analytical Laboratory		Matrix:	Soil	Lab Sample:	1601099-04	Date Received:	31-Aug-2016 9:33
Project:			Sample Size:	1.36 g	QC Batch:	B6I0041	Date Extracted:	08-Sep-2016 14:54
Date Collected:	26-Aug-2016 11:00		% Solids:	75.3	Date Analyzed:	13-Sep-16 03:34 Column: BEH C18 Analyst: AC		
Analyte	Conc. (ng/g)	RL	Qualifiers		Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	1.95			IS 13C2-PFOA	141	60 - 150	
PFOS	ND	1.95			IS 13C8-PFOS	108	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

The results are reported in dry weight

The sample size is reported in wet weight

Results reported to RL

When reported, PFBS, PFHxS and PFOS include both linear and branched isomers Only the linear isomer is reported for all other analytes

**Sample ID: 1607530-B101(S1-S2)****VAL - PFAS**

Client Data			Sample Data		Laboratory Data			
Name:	Alpha Analytical Laboratory		Matrix:	Soil	Lab Sample:	1601099-05	Date Received:	31-Aug-2016 9:33
Project:			Sample Size:	1.38 g	QC Batch:	B6I0041	Date Extracted:	08-Sep-2016 14:54
Date Collected:	26-Aug-2016 11:45		% Solids:	74.1	Date Analyzed:	13-Sep-16 03:47 Column: BEH C18 Analyst: AC		

Analyte	Conc. (ng/g)	RL	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	1.96		IS 13C2-PFOA	135	60 - 150	
PFOS	ND	1.96		IS 13C8-PFOS	103	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

The results are reported in dry weight

The sample size is reported in wet weight

Results reported to RL

When reported, PFBS, PFHxS and PFOS include both linear and branched isomers Only the linear isomer is reported for all other analytes

**Sample ID: 1607530-B101(S3-S4)****VAL - PFAS**

Client Data			Sample Data		Laboratory Data			
Name:	Alpha Analytical Laboratory		Matrix:	Soil	Lab Sample:	1601099-06	Date Received:	31-Aug-2016 9:33
Project:			Sample Size:	1.30 g	QC Batch:	B6I0041	Date Extracted:	08-Sep-2016 14:54
Date Collected:	26-Aug-2016 12:00		% Solids:	78.5	Date Analyzed:	13-Sep-16 03:59 Column: BEH C18 Analyst: AC		
Analyte	Conc. (ng/g)	RL	Qualifiers		Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	1.96			IS 13C2-PFOA	148	60 - 150	
PFOS	ND	1.96			IS 13C8-PFOS	98.0	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

The results are reported in dry weight

The sample size is reported in wet weight

Results reported to RL

When reported, PFBS, PFHxS and PFOS include both linear and branched isomers Only the linear isomer is reported for all other analytes

## DATA QUALIFIERS & ABBREVIATIONS

<b>B</b>	<b>This compound was also detected in the method blank.</b>
<b>D</b>	<b>Dilution</b>
<b>E</b>	<b>The associated compound concentration exceeded the calibration range of the instrument.</b>
<b>H</b>	<b>Recovery and/or RPD was outside laboratory acceptance limits.</b>
<b>I</b>	<b>Chemical Interference</b>
<b>J</b>	<b>The amount detected is below the Reporting Limit/LOQ.</b>
<b>*</b>	<b>See Cover Letter</b>
<b>Conc.</b>	<b>Concentration</b>
<b>NA</b>	<b>Not applicable</b>
<b>ND</b>	<b>Not Detected</b>
<b>TEQ</b>	<b>Toxic Equivalency</b>

**Unless otherwise noted, solid sample results are reported in dry weight. Tissue samples are reported in wet weight.**



**CERTIFICATIONS**

<b>Accrediting Authority</b>	<b>Certificate Number</b>
California Department of Health – ELAP	2892
DoD ELAP - A2LA Accredited - ISO/IEC 17025:2005	3091.01
Florida Department of Health	E87777
Hawaii Department of Health	N/A
Louisiana Department of Environmental Quality	01977
Maine Department of Health	2014022
Nevada Division of Environmental Protection	CA004132015-1
New Jersey Department of Environmental Protection	CA003
New York Department of Health	11411
Oregon Laboratory Accreditation Program	4042-004
Pennsylvania Department of Environmental Protection	012
South Carolina Department of Health	87002001
Texas Commission on Environmental Quality	T104704189-15-6
Virginia Department of General Services	7923
Washington Department of Ecology	C584
Wisconsin Department of Natural Resources	998036160

*Current certificates and lists of licensed parameters are located in the Quality Assurance office and are available upon request*

**NELAP Accredited Test Methods**

MATRIX: Air	
Description of Test	Method
Determination of Polychlorinated p-Dioxins & Polychlorinated Dibenzofurans	EPA 23

MATRIX: Biological Tissue	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Drinking Water	
Description of Test	Method
2,3,7,8-Tetrachlorodibenzo- p-dioxin (2,3,7,8-TCDD) GC/HRMS	EPA 1613
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537

MATRIX: Non-Potable Water	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Dioxin by GC/HRMS	EPA 613
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Solids	
Description of Test	Method
Tetra-Octa Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope	EPA 1613B

Dilution GC/HRMS	
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

# CHAIN OF CUSTODY

PAGE OF

11601099 1.6°C  
 9/1/16 8:30-9:16



Westborough, MA Mansfield, MA  
 TEL: 508-898-9220 TEL: 508-822-9300  
 FAX: 508-898-9193 FAX: 508-822-3288

**Client Information**  
 Client: Alpha Analytical Lab  
 Address: 8 Walkup Drive  
 Westborough, Ma 01581  
 Phone: 508-898-9220  
 Fax: [ ] These samples have been Previously analyzed by Alpha  
 Email: subreports@alphalab.com

**Project Information**  
 Project Name:  
 Project Location: NH  
 Project #:  
 Project Manager: Karyn Raymond  
 ALPHA Quote #: 380  
**Turn-Around Time**  
 Standard  Rush (ONLY IF PRE-APPROVED)  
 14 Day TAT  
 Due Date: Time:

Other Project Specific Requirements/Comments/Detection Limits:  
 Please reference Alpha Job #L1627010 on this report.  
**537-PFOA and PFOS only**

Date Rec'd in Lab: **ALPHA Job #: L1627010**  
**Report Information Data Deliverables Billing Information**  
 FAX  EMAIL  Same as Client info PO #:  
 ADEx  Add'l Deliverables

**Regulatory Requirements/Report Limits**  
 State/Fed Program Criteria

**MCP PRESUMPTIVE CERTAINTY-CT REASONABLE CONFIDENCE PROTOCOLS**  
 Yes  No Are MCP Analytical Methods Required?  
 Yes  No Are CT RCP (Reasonable Confidence Protocols) Required?

ALPHA Lab ID (Lab Use Only)	Sample ID	Collection		Sample Matrix	Sampler's Initials
		Date	Time		
	1607530-B103(S1-S2)	8/26/16	09:25	Soil	
	1607530-B103(S3-S4)	8/26/16	09:55	Soil	X
	1607530-B102(S1-S2)	8/26/16	10:45	Soil	X
	1607530-B102(S3-S4)	8/26/16	11:00	Soil	X
	1607530-B101(S1-S2)	8/26/16	11:45	Soil	X
	1607530-B101(S3-S4)	8/26/16	12:00	Soil	X

ANALYSIS											
537											

**TOTAL # BOTTLES**

**SAMPLE HANDLING**  
**Filtration**  
 Done  
 Not Needed  
 Lab to do  
**Preservation**  
 Lab to do  
 (Please specify below)

Sample Specific Comments

PLEASE ANSWER QUESTIONS ABOVE!

Container Type P - - - - -  
 Preservative A - - - - -

**IS YOUR PROJECT MA MCP or CT RCP?**

Relinquished By: *[Signature]* AAK Date/Time: 8/30/16  
 Received By: *[Signature]* Date/Time: 9/1/16 09:31

Please print clearly, legibly and completely. Samples can not be logged in and turnaround time clock will not start until any ambiguities are resolved. All samples submitted are subject to Alpha's Payment Terms.

SAMPLE LOG-IN CHECKLIST



Vista Project #: 1601099

TAT

Samples Arrival:	Date/Time	Initials:	Location:
	08/31/16 0933	BSB	WR-2
Logged In:	Date/Time	Initials:	Location:
	09/01/16 1235	BSB	WR-2
Delivered By:	FedEx	UPS	On Trac
			DHL
Preservation:	Ice	Blue Ice	Dry Ice
			None
Temp °C:	1.9 (uncorrected)	Time:	Thermometer ID: IR-1
Temp °C:	1.6 (corrected)	Probe used: Yes <input type="checkbox"/> No <input type="checkbox"/>	

	YES	NO	NA
Adequate Sample Volume Received?			
Holding Time Acceptable?			
Shipping Container(s) Intact?	✓		
Shipping Custody Seals Intact?			✓
Shipping Documentation Present?	✓		
Airbill	✓		
Trk #	1Z E30654019384 2982		
Sample Container Intact?			
Sample Custody Seals Intact?	✓		
Chain of Custody / Sample Documentation Present?	✓		
COC Anomaly/Sample Acceptance Form completed?			
If Chlorinated or Drinking Water Samples, Acceptable Preservation?			
Na <sub>2</sub> S <sub>2</sub> O <sub>3</sub> Preservation Documented?			
	COC	Sample Container	None
Shipping Container	Vista	Client	Retain
		Return	Dispose

Comments:





September 15, 2016

**Vista Work Order No. 1601114**

Ms. Karyn Raymond  
Alpha Analytical Laboratory  
8 Walkup Drive  
Westborough, MA 01581

Dear Ms. Raymond,

Enclosed are the results for the sample set received at Vista Analytical Laboratory on September 03, 2016. This sample set was analyzed on a rush turn-around time. The SDG Number is L1627653.

Vista Analytical Laboratory is committed to serving you effectively. If you require additional information, please contact me at 916-673-1520 or by email at [mmaier@vista-analytical.com](mailto:mmaier@vista-analytical.com).

Thank you for choosing Vista as part of your analytical support team.

Sincerely,

A handwritten signature in black ink that reads "Martha Maier".

Martha Maier  
Laboratory Director



*Vista Analytical Laboratory certifies that the report herein meets all the requirements set forth by NELAP for those applicable test methods. Results relate only to the samples as received by the laboratory. This report should not be reproduced except in full without the written approval of Vista.*

Vista Analytical Laboratory 1104 Windfeld Way El Dorado Hills, CA 95762 ph: 916-673-1520 fx: 916-673-0106 [www.vista-analytical.com](http://www.vista-analytical.com)

**SDG Number L1627653**

**Vista Work Order No. 1601114**

**Case Narrative**

**Sample Condition on Receipt:**

Three water samples were received in good condition and within the method temperature requirements. The samples were received and stored securely in accordance with Vista standard operating procedures and EPA methodology.

**Analytical Notes:**

**Modified EPA Method 537**

The samples were extracted and analyzed for PFOA and PFOS using Modified EPA Method 537. The results include both linear and branched isomers.

**Holding Times**

The samples were extracted and analyzed within the method hold times.

**Quality Control**

The Initial Calibration and Continuing Calibration Verifications met the acceptance criteria.

A Method Blank and Ongoing Precision and Recovery (OPR) sample were extracted and analyzed with the preparation batch. No analytes were detected in the Method Blank above the Reporting Limit. The OPR recoveries were within the method acceptance criteria.

The recoveries of all internal standards in the QC and field samples were within the acceptance criteria.

## TABLE OF CONTENTS

Case Narrative.....	1
Table of Contents.....	3
Sample Inventory.....	4
Analytical Results.....	5
Qualifiers.....	11
Certifications.....	12
Sample Receipt.....	15



# Sample Inventory Report

<b>Vista Sample ID</b>	<b>Client Sample ID</b>	<b>Sampled</b>	<b>Received</b>	<b>Components/Containers</b>
1601114-01	1607530-B101 (MW)	01-Sep-16 10:00	03-Sep-16 09:45	HDPE Bottle, 125 mL HDPE Bottle, 125 mL
1601114-02	1607530-B102 (MW)	01-Sep-16 10:10	03-Sep-16 09:45	HDPE Bottle, 125 mL HDPE Bottle, 125 mL
1601114-03	1607530-SW1	01-Sep-16 10:35	03-Sep-16 09:45	HDPE Bottle, 125 mL HDPE Bottle, 125 mL

## **ANALYTICAL RESULTS**

Sample ID: Method Blank				Modified EPA Method 537			
Matrix: Aqueous Sample Size: 0.125 L		QC Batch: B6I0058 Date Extracted: 13-Sep-2016 7:28		Lab Sample: B6I0058-BLK1 Date Analyzed: 13-Sep-16 17:52 Column: BEH C18 Analyst: AC			
Analyte	Conc. (ng/L)	RL	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	8.00		IS 13C2-PFOA	92.7	60 - 150	
PFOS	ND	8.00		IS 13C8-PFOS	88.3	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit  
 Results reported to RL  
 When reported, PFBS, PFHxS, PFOA and PFOS include both linear and branched isomers. Only the linear isomer is reported for all other analytes

Sample ID: OPR					Modified EPA Method 537		
Matrix: Aqueous	QC Batch: B6I0058	Lab Sample: B6I0058-BS1		Date Analyzed: 13-Sep-16 17:14 Column: BEH C18 Analyst: AC			
Sample Size: 0.125 L	Date Extracted: 13-Sep-2016 7:28						
Analyte	Amt Found (ng/L)	Spike Amt	%R	Limits	Labeled Standard	%R	LCL-UCL
PFOA	73.9	80.0	92.4	70 - 130	IS 13C2-PFOA	104	60 - 150
PFOS	79.1	80.0	98.9	70 - 130	IS 13C8-PFOS	90.7	60 - 150

LCL-UCL - Lower control limit - upper control limit

**Sample ID: 1607530-B101 (MW)****Modified EPA Method 537**

<b>Client Data</b>		<b>Sample Data</b>		<b>Laboratory Data</b>	
Name:	Alpha Analytical Laboratory	Matrix:	Water	Lab Sample:	1601114-01
Project:		Sample Size:	0.127 L	Date Received:	03-Sep-2016 9:45
Date Collected:	01-Sep-2016 10:00			QC Batch:	B6I0058
				Date Analyzed:	13-Sep-16 18:18
				Column:	BEH C18
				Analyst:	AC

Analyte	Conc. (ng/L)	RL	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	ND	7.86		IS 13C2-PFOA	117	60 - 150	
PFOS	ND	7.86		IS 13C8-PFOS	68.2	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

Results reported to RL

When reported, PFBS, PFHxS, PFOA and PFOS include both linear and branched isomers

Only the linear isomer is reported for all other analytes

**Sample ID: 1607530-B102 (MW)**

**Modified EPA Method 537**

Client Data		Sample Data		Laboratory Data					
Name:	Alpha Analytical Laboratory	Matrix:	Water	Lab Sample:	1601114-02	Date Received:	03-Sep-2016 9:45		
Project:		Sample Size:	0.125 L	QC Batch:	B6I0058	Date Extracted:	13-Sep-2016 7:28		
Date Collected:	01-Sep-2016 10:10			Date Analyzed:	13-Sep-16 18:30	Column:	BEH C18	Analyst:	AC

Analyte	Conc. (ng/L)	RL	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	11.2	8.01		IS 13C2-PFOA	101	60 - 150	
PFOS	16.1	8.01		IS 13C8-PFOS	88.9	60 - 150	

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

Results reported to RL

When reported, PFBS, PFHxS, PFOA and PFOS include both linear and branched isomers

Only the linear isomer is reported for all other analytes

**Sample ID: 1607530-SW1****Modified EPA Method 537**

<b>Client Data</b>		<b>Sample Data</b>		<b>Laboratory Data</b>			
Name:	Alpha Analytical Laboratory	Matrix:	Water	Lab Sample:	1601114-03	Date Received:	03-Sep-2016 9:45
Project:		Sample Size:	0.123 L	QC Batch:	B6I0058	Date Extracted:	13-Sep-2016 7:28
Date Collected:	01-Sep-2016 10:35			Date Analyzed:	13-Sep-16 18:43	Column:	BEH C18 Analyst: AC
					14-Sep-16 10:33	Column:	BEH C18 Analyst: AC

Analyte	Conc. (ng/L)	RL	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
PFOA	842	8.12		IS 13C2-PFOA	101	60 - 150	
PFOS	2910	40.6	D	IS 13C8-PFOS	95.4	60 - 150	D

RL - Reporting limit

LCL-UCL - Lower control limit - upper control limit

Results reported to RL

When reported, PFBS, PFHxS, PFOA and PFOS include both linear and branched isomers

Only the linear isomer is reported for all other analytes

## **DATA QUALIFIERS & ABBREVIATIONS**

<b>B</b>	<b>This compound was also detected in the method blank.</b>
<b>D</b>	<b>Dilution</b>
<b>E</b>	<b>The associated compound concentration exceeded the calibration range of the instrument.</b>
<b>H</b>	<b>Recovery and/or RPD was outside laboratory acceptance limits.</b>
<b>I</b>	<b>Chemical Interference</b>
<b>J</b>	<b>The amount detected is below the Reporting Limit/LOQ.</b>
<b>*</b>	<b>See Cover Letter</b>
<b>Conc.</b>	<b>Concentration</b>
<b>NA</b>	<b>Not applicable</b>
<b>ND</b>	<b>Not Detected</b>
<b>TEQ</b>	<b>Toxic Equivalency</b>

**Unless otherwise noted, solid sample results are reported in dry weight. Tissue samples are reported in wet weight.**



### CERTIFICATIONS

<b>Accrediting Authority</b>	<b>Certificate Number</b>
California Department of Health – ELAP	2892
DoD ELAP - A2LA Accredited - ISO/IEC 17025:2005	3091.01
Florida Department of Health	E87777
Hawaii Department of Health	N/A
Louisiana Department of Environmental Quality	01977
Maine Department of Health	2014022
Nevada Division of Environmental Protection	CA004132015-1
New Jersey Department of Environmental Protection	CA003
New York Department of Health	11411
Oregon Laboratory Accreditation Program	4042-004
Pennsylvania Department of Environmental Protection	012
South Carolina Department of Health	87002001
Texas Commission on Environmental Quality	T104704189-15-6
Virginia Department of General Services	7923
Washington Department of Ecology	C584
Wisconsin Department of Natural Resources	998036160

*Current certificates and lists of licensed parameters are located in the Quality Assurance office and are available upon request*

## NELAP Accredited Test Methods

MATRIX: Air	
Description of Test	Method
Determination of Polychlorinated p-Dioxins & Polychlorinated Dibenzofurans	EPA 23

MATRIX: Biological Tissue	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Drinking Water	
Description of Test	Method
2,3,7,8-Tetrachlorodibenzo- p-dioxin (2,3,7,8-TCDD) GC/HRMS	EPA 1613
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537

MATRIX: Non-Potable Water	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Dioxin by GC/HRMS	EPA 613
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Solids	
Description of Test	Method
Tetra-Octa Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope	EPA 1613B

Dilution GC/HRMS	
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A





**SAMPLE LOG-IN CHECKLIST**



Vista Project #: 1601114 TAT 14

<b>Samples Arrival:</b>	<b>Date/Time:</b> 9/3/16 09:45	<b>Initials:</b> WL	<b>Location:</b> WR2
			<b>Shelf/Rack:</b> NA
<b>Logged In:</b>	<b>Date/Time:</b> 09/06/16 1325	<b>Initials:</b> RAB	<b>Location:</b> WR-2
			<b>Shelf/Rack:</b> F6
<b>Delivered By:</b>	FedEx	<u>UPS</u>	On Trac
			DHL
			Hand Delivered
			Other
<b>Preservation:</b>	<u>Ice</u>	Blue Ice	Dry Ice
			None
<b>Temp °C:</b> 0.90 (uncorrected)	<b>Time:</b> 09:50		<b>Thermometer ID:</b> IR-1
<b>Temp °C:</b> 0.5 (corrected)	<b>Probe used:</b> Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		

	YES	NO	NA
Adequate Sample Volume Received?	✓		
Holding Time Acceptable?	✓		
Shipping Container(s) Intact?	✓		
Shipping Custody Seals Intact?			✓
Shipping Documentation Present?			✓
Airbill			
Trk #	1ZE30654449471588		
Sample Container Intact?	✓		
Sample Custody Seals Intact?			✓
Chain of Custody / Sample Documentation Present?	✓		
COC Anomaly/Sample Acceptance Form completed?		✓	
If Chlorinated or Drinking Water Samples, Acceptable Preservation?			✓
Na <sub>2</sub> S <sub>2</sub> O <sub>3</sub> Preservation Documented?	COC	Sample Container	<u>None</u>
Shipping Container	Vista	<u>Client</u>	Retain
			Return
			Dispose

Comments:

# Chain-of-Custody Record

Laboratory:

Alpha

Laboratory Job #

(Lab use only)

21627653



400 Unicorn Park Drive  
Woburn, MA 01801  
PH: 781.721.4000  
FX: 781.721.4073

## Project Information

Project Name: Eversource NH SRP

Project Location: Newington, NH

Project Number: 1607530

Project Manager: Mike Sabulis  
(office: 781-721-4114) (cell: 508-633-9544)

Send Report to: Jess Englehart

Send EDD to: labdata@geiconsultants.com

Page 1 of 1

Sample Handling

Samples Field Filtered  
YES NO NA

Sampled Shipped  
With Ice

YES NO

Sample Specific Remarks

MCP PRESUMPTIVE CERTAINTY REQUIRED -- YES NO

If Yes, Are MCP Analytical Methods Required? YES NO NA

If Yes, Are Drinking Water Samples Submitted? YES NO NA

If Yes, Have You Met Minimum Field QC Requirements? YES NO NA

Lab Sample Number	GEI Sample ID	Collection		Matrix	No. of Bottles	Sampler(s) Initials	PFOS	PFOA	Analysis											
		Date	Time																	
21627653-01	1607530-B101(MW)	9/1/2016	10:00	water	2	CRC	x	x												
09	1607530-B102(MW)	9/1/2016	10:10	water	2	MEG	x	x												
03	1607530-SW1	9/1/2016	10:35	water	2	CRC	x	x												

MCP Level Needed: GEI requires the most stringent Method 1 MCP standard be met for all analytes whenever possible

Turnaround Time (Business days):

Before submitting rush turnaround samples, you must notify the laboratory to confirm that the TAT can be achieved.

Normal  Other   
10-Day  7-Day   
5-Day  3-Day

Relinquished by: (signature)	Date:	Time:	Received by: (signature)
1. Molly E Green	9/1/16	12:53	1. GEI Sample Fridge
2. GEI Fridge	9/2/16	9:56	2. Sabulis EOD
3. Sabulis EOD	9/2/16	9:57	3. Lab Mgr AAL 9-2-16 9:56
4. Lab Mgr AAL	9-2-16	13:40	4. Well McEwen

Additional Requirements/Comments/Remarks:



## ANALYTICAL REPORT

Lab Number:	L1718562
Client:	GEI Consultants 400 Unicorn Park Drive Woburn, MA 01801
ATTN:	Mike Sabulis
Phone:	(781) 721-4114
Project Name:	EVERSOURCE NH SRP
Project Number:	1607530
Report Date:	06/21/17

The original project report/data package is held by Alpha Analytical. This report/data package is paginated and should be reproduced only in its entirety. Alpha Analytical holds no responsibility for results and/or data that are not consistent with the original.

Certifications & Approvals: MA (M-MA086), NH NELAP (2064), NJ NELAP (MA935), CT (PH-0574), IL (200077), ME (MA00086), MD (348), NY (11148), NC (25700/666), PA (68-03671), RI (LAO00065), TX (T104704476), VT (VT-0935), VA (460195), USDA (Permit #P330-14-00197).

---

320 Forbes Boulevard, Mansfield, MA 02048-1806  
508-822-9300 (Fax) 508-822-3288 800-624-9220 - [www.alphalab.com](http://www.alphalab.com)





**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1718562  
**Report Date:** 06/21/17

<b>Alpha Sample ID</b>	<b>Client ID</b>	<b>Matrix</b>	<b>Sample Location</b>	<b>Collection Date/Time</b>	<b>Receive Date</b>
L1718562-01	1607530-B101(MW)	WATER	NEWINGTON, NH	06/02/17 15:15	06/06/17
L1718562-02	1607530-B102(MW)	WATER	NEWINGTON, NH	06/02/17 12:45	06/06/17
L1718562-03	1607530-B103(MW)	WATER	NEWINGTON, NH	06/02/17 17:40	06/06/17
L1718562-04	1607530-FB	WATER	NEWINGTON, NH	06/02/17 15:15	06/06/17



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1718562  
**Report Date:** 06/21/17

### Case Narrative

The samples were received in accordance with the Chain of Custody and no significant deviations were encountered during the preparation or analysis unless otherwise noted. Sample Receipt, Container Information, and the Chain of Custody are located at the back of the report.

Results contained within this report relate only to the samples submitted under this Alpha Lab Number and meet NELAP requirements for all NELAP accredited parameters unless otherwise noted in the following narrative. The data presented in this report is organized by parameter (i.e. VOC, SVOC, etc.). Sample specific Quality Control data (i.e. Surrogate Spike Recovery) is reported at the end of the target analyte list for each individual sample, followed by the Laboratory Batch Quality Control at the end of each parameter. Tentatively Identified Compounds (TICs), if requested, are reported for compounds identified to be present and are not part of the method/program Target Compound List, even if only a subset of the TCL are being reported. If a sample was re-analyzed or re-extracted due to a required quality control corrective action and if both sets of data are reported, the Laboratory ID of the re-analysis or re-extraction is designated with an "R" or "RE", respectively. When multiple Batch Quality Control elements are reported (e.g. more than one LCS), the associated samples for each element are noted in the grey shaded header line of each data table. Any Laboratory Batch, Sample Specific % recovery or RPD value that is outside the listed Acceptance Criteria is bolded in the report. All specific QC information is also incorporated in the Data Usability format of our Data Merger tool where it can be reviewed along with any associated usability implications. Soil/sediments, solids and tissues are reported on a dry weight basis unless otherwise noted. Definitions of all data qualifiers and acronyms used in this report are provided in the Glossary located at the back of the report.

In reference to questions H (CAM) or 4 (RCP) when "NO" is checked, the performance criteria for CAM and RCP methods allow for some quality control failures to occur and still be within method compliance. In these instances the specific failure is not narrated but noted in the associated QC table. The information is also incorporated in the Data Usability format of our Data Merger tool where it can be reviewed along with any associated usability implications.

Please see the associated ADEx data file for a comparison of laboratory reporting limits that were achieved with the regulatory Numerical Standards requested on the Chain of Custody.

#### HOLD POLICY

For samples submitted on hold, Alpha's policy is to hold samples (with the exception of Air canisters) free of charge for 21 calendar days from the date the project is completed. After 21 calendar days, we will dispose of all samples submitted including those put on hold unless you have contacted your Client Service Representative and made arrangements for Alpha to continue to hold the samples. Air canisters will be disposed after 3 business days from the date the project is completed.

Please contact Client Services at 800-624-9220 with any questions.

---

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1718562  
**Report Date:** 06/21/17

### Case Narrative (continued)


#### Semivolatile Organics

WG1012571-3 LCSD: The internal standard (IS) response for 13C2-PFOA was below the acceptance criteria when compared to the continuing calibration, but within criteria when compared to the initial calibration. Target analytes recovered within criteria, therefore no further action was taken.

The WG1012571-4 Laboratory Duplicate RPD, performed on L1718562-01, is above the acceptance criteria for perfluorooctanesulfonic acid (pfos) (36%); however, the sample and duplicate results are less than five times the reporting limit. Therefore, the RPD is valid.

I, the undersigned, attest under the pains and penalties of perjury that, to the best of my knowledge and belief and based upon my personal inquiry of those responsible for providing the information contained in this analytical report, such information is accurate and complete. This certificate of analysis is not complete unless this page accompanies any and all pages of this report.

Authorized Signature:



Susan O'Neil

Title: Technical Director/Representative

Date: 06/21/17

# ORGANICS

# SEMIVOLATILES

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1718562  
**Report Date:** 06/21/17

**SAMPLE RESULTS**

Lab ID: L1718562-01  
 Client ID: 1607530-B101(MW)  
 Sample Location: NEWINGTON, NH

Date Collected: 06/02/17 15:15  
 Date Received: 06/06/17  
 Field Prep: Not Specified  
 Extraction Method: EPA 537  
 Extraction Date: 06/13/17 10:00

Matrix: Water  
 Analytical Method: 122,537  
 Analytical Date: 06/20/17 18:56  
 Analyst: AR

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Perfluorinated Alkyl Acids by EPA 537 - Mansfield Lab</b>						
Perfluorooctanoic Acid (PFOA)	2.48		ng/l	1.78	--	1
Perfluorooctanesulfonic Acid (PFOS)	3.05		ng/l	1.78	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
Perfluoro-n-[1,2-13C2]hexanoic Acid (13C-PFHxA)	102		70-130
Perfluoro-n-[1,2-13C2]decanoic Acid (13C-PFDA)	127		70-130
N-Deuterioethylperfluoro-1-octanesulfonamidoacetic Acid (d5-NEtFOSAA)	97		70-130

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1718562  
**Report Date:** 06/21/17

**SAMPLE RESULTS**

Lab ID: L1718562-02  
 Client ID: 1607530-B102(MW)  
 Sample Location: NEWINGTON, NH

Date Collected: 06/02/17 12:45  
 Date Received: 06/06/17  
 Field Prep: Not Specified  
 Extraction Method: EPA 537  
 Extraction Date: 06/13/17 10:00

Matrix: Water  
 Analytical Method: 122,537  
 Analytical Date: 06/20/17 19:15  
 Analyst: AR

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Perfluorinated Alkyl Acids by EPA 537 - Mansfield Lab</b>						
Perfluorooctanoic Acid (PFOA)	7.11		ng/l	1.85	--	1
Perfluorooctanesulfonic Acid (PFOS)	14.2		ng/l	1.85	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
Perfluoro-n-[1,2-13C2]hexanoic Acid (13C-PFHxA)	83		70-130
Perfluoro-n-[1,2-13C2]decanoic Acid (13C-PFDA)	72		70-130
N-Deuterioethylperfluoro-1-octanesulfonamidoacetic Acid (d5-NEtFOSAA)	74		70-130

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1718562  
**Report Date:** 06/21/17

**SAMPLE RESULTS**

Lab ID: L1718562-03  
 Client ID: 1607530-B103(MW)  
 Sample Location: NEWINGTON, NH  
 Matrix: Water  
 Analytical Method: 122,537  
 Analytical Date: 06/20/17 19:33  
 Analyst: AR

Date Collected: 06/02/17 17:40  
 Date Received: 06/06/17  
 Field Prep: Not Specified  
 Extraction Method: EPA 537  
 Extraction Date: 06/13/17 10:00

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Perfluorinated Alkyl Acids by EPA 537 - Mansfield Lab</b>						
Perfluorooctanoic Acid (PFOA)	ND		ng/l	1.85	--	1
Perfluorooctanesulfonic Acid (PFOS)	1.87		ng/l	1.85	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
Perfluoro-n-[1,2-13C2]hexanoic Acid (13C-PFHxA)	77		70-130
Perfluoro-n-[1,2-13C2]decanoic Acid (13C-PFDA)	85		70-130
N-Deuterioethylperfluoro-1-octanesulfonamidoacetic Acid (d5-NEtFOSAA)	86		70-130

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1718562  
**Report Date:** 06/21/17

**SAMPLE RESULTS**

Lab ID: L1718562-04  
 Client ID: 1607530-FB  
 Sample Location: NEWINGTON, NH  
 Matrix: Water  
 Analytical Method: 122,537  
 Analytical Date: 06/20/17 18:47  
 Analyst: AR

Date Collected: 06/02/17 15:15  
 Date Received: 06/06/17  
 Field Prep: Not Specified  
 Extraction Method: EPA 537  
 Extraction Date: 06/13/17 10:00

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor
<b>Perfluorinated Alkyl Acids by EPA 537 - Mansfield Lab</b>						
Perfluorooctanoic Acid (PFOA)	ND		ng/l	1.78	--	1
Perfluorooctanesulfonic Acid (PFOS)	ND		ng/l	1.78	--	1

Surrogate	% Recovery	Qualifier	Acceptance Criteria
Perfluoro-n-[1,2-13C2]hexanoic Acid (13C-PFHxA)	87		70-130
Perfluoro-n-[1,2-13C2]decanoic Acid (13C-PFDA)	97		70-130
N-Deuterioethylperfluoro-1-octanesulfonamidoacetic Acid (d5-NEtFOSAA)	98		70-130



Project Name: EVERSOURCE NH SRP

Lab Number: L1718562

Project Number: 1607530

Report Date: 06/21/17

**Method Blank Analysis  
Batch Quality Control**

Analytical Method: 122,537  
 Analytical Date: 06/20/17 18:38  
 Analyst: AR

Extraction Method: EPA 537  
 Extraction Date: 06/13/17 10:00

Parameter	Result	Qualifier	Units	RL	MDL
Perfluorinated Alkyl Acids by EPA 537 - Mansfield Lab for sample(s): 01-04 Batch: WG1012571-1					
Perfluorooctanoic Acid (PFOA)	ND		ng/l	2.00	--
Perfluorooctanesulfonic Acid (PFOS)	ND		ng/l	2.00	--

Surrogate	%Recovery	Qualifier	Acceptance Criteria
Perfluoro-n-[1,2-13C2]hexanoic Acid (13C-PFHxA)	96		70-130
Perfluoro-n-[1,2-13C2]decanoic Acid (13C-PFDA)	116		70-130
N-Deuterioethylperfluoro-1-octanesulfonamidoacetic Acid (d5-NEtFOSAA)	99		70-130

### Lab Control Sample Analysis Batch Quality Control

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1718562  
**Report Date:** 06/21/17

Parameter	LCS %Recovery	Qual	LCSD %Recovery	Qual	%Recovery Limits	RPD	Qual	RPD Limits
Perfluorinated Alkyl Acids by EPA 537 - Mansfield Lab Associated sample(s): 01-04 Batch: WG1012571-2 WG1012571-3								
Perfluorooctanoic Acid (PFOA)	94		108		70-130	14		30
Perfluorooctanesulfonic Acid (PFOS)	86		110		70-130	24		30

Surrogate	LCS %Recovery	Qual	LCSD %Recovery	Qual	Acceptance Criteria
Perfluoro-n-[1,2-13C2]hexanoic Acid (13C-PFHxA)	95		111		70-130
Perfluoro-n-[1,2-13C2]decanoic Acid (13C-PFDA)	98		112		70-130
N-Deuterioethylperfluoro-1-octanesulfonamidoacetic Acid (d5-NEtFOSAA)	92		122		70-130

## Matrix Spike Analysis

*Batch Quality Control*

**Project Name:** EVERSOURCE NH SRP

**Lab Number:** L1718562

**Project Number:** 1607530

**Report Date:** 06/21/17

<i>Parameter</i>	<i>Native Sample</i>	<i>MS Added</i>	<i>MS Found</i>	<i>MS %Recovery</i>	<i>Qual</i>	<i>MSD Found</i>	<i>MSD %Recovery</i>	<i>Qual</i>	<i>Recovery Limits</i>	<i>RPD</i>	<i>Qual</i>	<i>RPD Limits</i>
Perfluorinated Alkyl Acids by EPA 537 - Mansfield Lab Associated sample(s): 01-04 QC Batch ID: WG1012571-5 QC Sample: L1718562-02 Client ID: 1607530-B102(MW)												
Perfluorooctanoic Acid (PFOA)	7.11	463	454	96		-	-		70-130	-		30
Perfluorooctanesulfonic Acid (PFOS)	14.2	428	444	100		-	-		70-130	-		30

<i>Surrogate</i>	<i>MS % Recovery</i>	<i>Qualifier</i>	<i>MSD % Recovery</i>	<i>Qualifier</i>	<i>Acceptance Criteria</i>
N-Deuterioethylperfluoro-1-octanesulfonamidoacetic Acid (d5-NEtFOSAA)	86				70-130
Perfluoro-n-[1,2-13C2]decanoic Acid (13C-PFDA)	90				70-130
Perfluoro-n-[1,2-13C2]hexanoic Acid (13C-PFHxA)	94				70-130

## Lab Duplicate Analysis

Batch Quality Control

Project Name: EVERSOURCE NH SRP

Project Number: 1607530

Lab Number: L1718562

Report Date: 06/21/17

Parameter	Native Sample	Duplicate Sample	Units	RPD	Qual	RPD Limits
Perfluorinated Alkyl Acids by EPA 537 - Mansfield Lab Associated sample(s): 01-04 QC Batch ID: WG1012571-4 QC Sample: L1718562-01 Client ID: 1607530-B101(MW)						
Perfluorooctanoic Acid (PFOA)	2.48	2.24	ng/l	10		30
Perfluorooctanesulfonic Acid (PFOS)	3.05	2.13	ng/l	36	Q	30

Surrogate	%Recovery	Qualifier	%Recovery	Qualifier	Acceptance Criteria
Perfluoro-n-[1,2-13C2]hexanoic Acid (13C-PFHxA)	102		88		70-130
Perfluoro-n-[1,2-13C2]decanoic Acid (13C-PFDA)	127		104		70-130
N-Deuterioethylperfluoro-1-octanesulfonamidoacetic Acid (d5-NEtFOSAA)	97		88		70-130

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

Serial\_No:06211716:15  
**Lab Number:** L1718562  
**Report Date:** 06/21/17

**Sample Receipt and Container Information**

Were project specific reporting limits specified?

YES

**Cooler Information**

**Cooler**                      **Custody Seal**  
A                                      Absent

**Container Information**

<b>Container ID</b>	<b>Container Type</b>	<b>Cooler</b>	<b>Initial pH</b>	<b>Final pH</b>	<b>Temp deg C</b>	<b>Pres</b>	<b>Seal</b>	<b>Frozen Date/Time</b>	<b>Analysis(*)</b>
L1718562-01A	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-01B	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-01C	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-02A	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-02B	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-02C	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-03A	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-03B	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-03C	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)
L1718562-04A	3 Plastic Trizma/1 Plastic/1 H20+Trizma	A	NA		3.7	Y	Absent		A2-537-PFOA/PFOS(14)

\*Values in parentheses indicate holding time in days



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1718562  
**Report Date:** 06/21/17

## GLOSSARY

### Acronyms

EDL	- Estimated Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The EDL includes any adjustments from dilutions, concentrations or moisture content, where applicable. The use of EDLs is specific to the analysis of PAHs using Solid-Phase Microextraction (SPME).
EPA	- Environmental Protection Agency.
LCS	- Laboratory Control Sample: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
LCSD	- Laboratory Control Sample Duplicate: Refer to LCS.
LFB	- Laboratory Fortified Blank: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
MDL	- Method Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The MDL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
MS	- Matrix Spike Sample: A sample prepared by adding a known mass of target analyte to a specified amount of matrix sample for which an independent estimate of target analyte concentration is available.
MSD	- Matrix Spike Sample Duplicate: Refer to MS.
NA	- Not Applicable.
NC	- Not Calculated: Term is utilized when one or more of the results utilized in the calculation are non-detect at the parameter's reporting unit.
NDPA/DPA	- N-Nitrosodiphenylamine/Diphenylamine.
NI	- Not Ignitable.
NP	- Non-Plastic: Term is utilized for the analysis of Atterberg Limits in soil.
RL	- Reporting Limit: The value at which an instrument can accurately measure an analyte at a specific concentration. The RL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
RPD	- Relative Percent Difference: The results from matrix and/or matrix spike duplicates are primarily designed to assess the precision of analytical results in a given matrix and are expressed as relative percent difference (RPD). Values which are less than five times the reporting limit for any individual parameter are evaluated by utilizing the absolute difference between the values; although the RPD value will be provided in the report.
SRM	- Standard Reference Material: A reference sample of a known or certified value that is of the same or similar matrix as the associated field samples.
STLP	- Semi-dynamic Tank Leaching Procedure per EPA Method 1315.
TIC	- Tentatively Identified Compound: A compound that has been identified to be present and is not part of the target compound list (TCL) for the method and/or program. All TICs are qualitatively identified and reported as estimated concentrations.

### Footnotes

- 1 - The reference for this analyte should be considered modified since this analyte is absent from the target analyte list of the original method.

### Terms

**Analytical Method:** Both the document from which the method originates and the analytical reference method. (Example: EPA 8260B is shown as 1,8260B.) The codes for the reference method documents are provided in the References section of the Addendum.

**Final pH:** As it pertains to Sample Receipt & Container Information section of the report, Final pH reflects pH of container determined after adjustment at the laboratory, if applicable. If no adjustment required, value reflects Initial pH.

**Frozen Date/Time:** With respect to Volatile Organics in soil, Frozen Date/Time reflects the date/time at which associated Reagent Water-preserved vials were initially frozen. Note: If frozen date/time is beyond 48 hours from sample collection, value will be reflected in 'bold'.

**Initial pH:** As it pertains to Sample Receipt & Container Information section of the report, Initial pH reflects pH of container determined upon receipt, if applicable.

**Total:** With respect to Organic analyses, a 'Total' result is defined as the summation of results for individual isomers or Aroclors. If a 'Total' result is requested, the results of its individual components will also be reported. This is applicable to 'Total' results for methods 8260, 8081 and 8082.

### Data Qualifiers

- A** - Spectra identified as "Aldol Condensation Product".
- B** - The analyte was detected above the reporting limit in the associated method blank. Flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For MCP-related

**Report Format:** Data Usability Report



**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1718562  
**Report Date:** 06/21/17

#### Data Qualifiers

projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For DOD-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank AND the analyte was detected above one-half the reporting limit (or above the reporting limit for common lab contaminants) in the associated method blank. For NJ-Air-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte above the reporting limit. For NJ-related projects (excluding Air), flag only applies to associated field samples that have detectable concentrations of the analyte, which was detected above the reporting limit in the associated method blank or above five times the reporting limit for common lab contaminants (Phthalates, Acetone, Methylene Chloride, 2-Butanone).

- C** - Co-elution: The target analyte co-elutes with a known lab standard (i.e. surrogate, internal standards, etc.) for co-extracted analyses.
- D** - Concentration of analyte was quantified from diluted analysis. Flag only applies to field samples that have detectable concentrations of the analyte.
- E** - Concentration of analyte exceeds the range of the calibration curve and/or linear range of the instrument.
- G** - The concentration may be biased high due to matrix interferences (i.e. co-elution) with non-target compound(s). The result should be considered estimated.
- H** - The analysis of pH was performed beyond the regulatory-required holding time of 15 minutes from the time of sample collection.
- I** - The lower value for the two columns has been reported due to obvious interference.
- M** - Reporting Limit (RL) exceeds the MCP CAM Reporting Limit for this analyte.
- NJ** - Presumptive evidence of compound. This represents an estimated concentration for Tentatively Identified Compounds (TICs), where the identification is based on a mass spectral library search.
- P** - The RPD between the results for the two columns exceeds the method-specified criteria.
- Q** - The quality control sample exceeds the associated acceptance criteria. For DOD-related projects, LCS and/or Continuing Calibration Standard exceedences are also qualified on all associated sample results. Note: This flag is not applicable for matrix spike recoveries when the sample concentration is greater than 4x the spike added or for batch duplicate RPD when the sample concentrations are less than 5x the RL. (Metals only.)
- R** - Analytical results are from sample re-analysis.
- RE** - Analytical results are from sample re-extraction.
- S** - Analytical results are from modified screening analysis.
- J** - Estimated value. This represents an estimated concentration for Tentatively Identified Compounds (TICs).
- ND** - Not detected at the reporting limit (RL) for the sample.

**Project Name:** EVERSOURCE NH SRP  
**Project Number:** 1607530

**Lab Number:** L1718562  
**Report Date:** 06/21/17

## REFERENCES

- 122 Determination of Selected Perfluorinated Alkyl Acids in Drinking Water by Solid Phase Extraction and Liquid Chromatography/Tandem Mass Spectrometry (LC/MS/MS). EPA Method 537, EPA/600/R-08/092. Version 1.1, September 2009.

## LIMITATION OF LIABILITIES

Alpha Analytical performs services with reasonable care and diligence normal to the analytical testing laboratory industry. In the event of an error, the sole and exclusive responsibility of Alpha Analytical shall be to re-perform the work at its own expense. In no event shall Alpha Analytical be held liable for any incidental, consequential or special damages, including but not limited to, damages in any way connected with the use of, interpretation of, information or analysis provided by Alpha Analytical.

We strongly urge our clients to comply with EPA protocol regarding sample volume, preservation, cooling, containers, sampling procedures, holding time and splitting of samples in the field.





## Certification Information

The following analytes are not included in our Primary NELAP Scope of Accreditation:

### Westborough Facility

**EPA 624:** m/p-xylene, o-xylene

**EPA 8260C:** NPW: 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene, Azobenzene; SCM: Iodomethane (methyl iodide), Methyl methacrylate, 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene.

**EPA 8270D:** NPW: Dimethylnaphthalene,1,4-Diphenylhydrazine; SCM: Dimethylnaphthalene,1,4-Diphenylhydrazine.

**EPA 300:** DW: Bromide

**EPA 6860:** NPW and SCM: Perchlorate

**EPA 9010:** NPW and SCM: Amenable Cyanide Distillation

**EPA 9012B:** NPW: Total Cyanide

**EPA 9050A:** NPW: Specific Conductance

**SM3500:** NPW: Ferrous Iron

**SM4500:** NPW: Amenable Cyanide, Dissolved Oxygen; SCM: Total Phosphorus, TKN, NO<sub>2</sub>, NO<sub>3</sub>.

**SM5310C:** DW: Dissolved Organic Carbon

### Mansfield Facility

**SM 2540D:** TSS

**EPA 3005A** NPW

**EPA 8082A:** NPW: PCB: 1, 5, 31, 87,101, 110, 141, 151, 153, 180, 183, 187.

**EPA TO-15:** Halothane, 2,4,4-Trimethyl-2-pentene, 2,4,4-Trimethyl-1-pentene, Thiophene, 2-Methylthiophene,

3-Methylthiophene, 2-Ethylthiophene, 1,2,3-Trimethylbenzene, Indan, Indene, 1,2,4,5-Tetramethylbenzene, Benzothiophene, 1-Methylnaphthalene.

**Biological Tissue Matrix:** EPA 3050B

The following analytes are included in our Massachusetts DEP Scope of Accreditation

### Westborough Facility:

#### Drinking Water

**EPA 300.0:** Nitrate-N, Fluoride, Sulfate; **EPA 353.2:** Nitrate-N, Nitrite-N; **SM4500NO3-F:** Nitrate-N, Nitrite-N; **SM4500F-C, SM4500CN-CE, EPA 180.1, SM2130B, SM4500CI-D, SM2320B, SM2540C, SM4500H-B**

**EPA 332:** Perchlorate; **EPA 524.2:** THMs and VOCs; **EPA 504.1:** EDB, DBCP.

**Microbiology:** **SM9215B; SM9223-P/A, SM9223B-Colilert-QT, SM9222D.**

#### Non-Potable Water

**SM4500H,B, EPA 120.1, SM2510B, SM2540C, SM2320B, SM4500CL-E, SM4500F-BC, SM4500NH3-BH, EPA 350.1:** Ammonia-N, **LACHAT 10-107-06-1-B:** Ammonia-N, **SM4500NO3-F, EPA 353.2:** Nitrate-N, **EPA 351.1, SM4500P-E, SM4500P-B, E, SM4500SO4-E, SM5220D, EPA 410.4, SM5210B, SM5310C, SM4500CL-D, EPA 1664, EPA 420.1, SM4500-CN-CE, SM2540D.**

**EPA 624:** Volatile Halocarbons & Aromatics,

**EPA 608:** Chlordane, Toxaphene, Aldrin, alpha-BHC, beta-BHC, gamma-BHC, delta-BHC, Dieldrin, DDD, DDE, DDT, Endosulfan I, Endosulfan II, Endosulfan sulfate, Endrin, Endrin Aldehyde, Heptachlor, Heptachlor Epoxide, PCBs

**EPA 625:** SVOC (Acid/Base/Neutral Extractables), **EPA 600/4-81-045:** PCB-Oil.

**Microbiology:** **SM9223B-Colilert-QT; Enterolert-QT, SM9221E.**

### Mansfield Facility:

#### Drinking Water

**EPA 200.7:** Ba, Be, Cd, Cr, Cu, Ni, Na, Ca. **EPA 200.8:** Sb, As, Ba, Be, Cd, Cr, Cu, Pb, Ni, Se, TL. **EPA 245.1 Hg.**

#### Non-Potable Water

**EPA 200.7:** Al, Sb, As, Be, Cd, Ca, Cr, Co, Cu, Fe, Pb, Mg, Mn, Mo, Ni, K, Se, Ag, Na, Sr, TL, Ti, V, Zn.

**EPA 200.8:** Al, Sb, As, Be, Cd, Cr, Cu, Pb, Mn, Ni, Se, Ag, TL, Zn.

**EPA 245.1 Hg.**

**SM2340B**

For a complete listing of analytes and methods, please contact your Alpha Project Manager.

<b>Chain-of-Custody Record</b>	<b>Laboratory:</b> Alpha	<b>Laboratory Job #</b> L1718562 <small>(Lab use only)</small>
--------------------------------	--------------------------	---



Project Information	
Project Name: Eversource NH SRP	Project Location: Newington, NH
Project Number: 1607530	Project Manager: Mike Sabulis (office: 781-721-4114) (cell: 508-633-9544)
Send Report to: Jess Englehart	<b>Preservative</b>
Send EDD to: labdata@geiconsultants.com	<b>Analysis</b>

Page 1 of 1

Sample Handling

Samples Field Filtered  
YES NO **NA**

Sampled Shipped  
With Ice  
YES NO

Sample Specific Remarks

**MCP PRESUMPTIVE CERTAINTY REQUIRED -- YES NO**

If Yes, Are MCP Analytical Methods Required?      **YES**    NO    NA

If Yes, Are Drinking Water Samples Submitted?      **YES**    NO    NA

If Yes, Have You Met Minimum Field QC Requirements?      **YES**    NO    NA

Lab Sample Number	GEI Sample ID	Collection		Matrix	No. of Bottles	Sampler(s) Initials	PFOS	PFOA													
		Date	Time																		
18562.01	1607530-B101(MW)	6/2/2017	1515	water	3	JAW	x	x													
.02	1607530-B102(MW)	6/2/2017	1245	water	3	JAW	x	x													
.03	1607530-B103(MW)	6/2/2017	1740	water	3	JAW	x	x													
.04	1607530-FB	6/2/2017	1515	water	1	JAW	x	x												Field Blank	

**MCP Level Needed:** GEI requires the most stringent Method 1 MCP standard be met for all analytes whenever possible.

Turnaround Time (Business days):	Before submitting rush turnaround samples, you <b>must</b> notify the laboratory to confirm that the TAT can be achieved.
Normal <u>  X  </u> Other <u>    </u> 10-Day <u>    </u> 7-Day <u>    </u> 5-Day <u>    </u> 3-Day <u>    </u>	

Relinquished by: (signature)	Date:	Time:	Received by: (signature)
1. <i>[Signature]</i>	6/2/17	2010	1. <i>[Signature]</i>
2. <i>[Signature]</i>	6/6	1132	2. <i>[Signature]</i>
3. <i>[Signature]</i>	6/6	1133	3. <i>[Signature]</i>
4. <i>[Signature]</i>	6-6-17	17540	4. <i>[Signature]</i>

Additional Requirements/Comments/Remarks:

*Nmyer*      *6/7/17 4:45*      *Paul Parry 6/7/17 4:45*

# **Appendix D**

---

## **Groundwater Model Description**

# NEWINGTON NH – SRP INSTALLATION DEWATERING FLOW ESTIMATE FOR INSTALLATION TRENCH GW MODFLOW MODEL DESCRIPTION

## **Objective:**

A trench excavation for a 115 kV transmission main installation is proposed across a farm field. Objective is to estimate dewatering rates to maintain dry excavation for utility trench.

## **Method:**

Three-dimensional MODFLOW groundwater model used that directly outputs flow rate. Visual MODFLOW® is a graphical user interface that runs the industry standard USGS MODFLOW code solving the groundwater continuity equation.

## **Assumptions:**

Groundwater flow into excavations was modeled as steady state flow, assuming excavation open to full depth. Model space is shown on Figure 1. The model extends downward to elevation +10 ft. NAVD, which corresponds to an approximate 50 – 65-ft. aquifer thickness with impermeable base.

The water table aquifer is of relatively large extent such that a steady state cone of depression from dewatering is not expected to extend to the aquifer boundary during the dewatering period. The model therefore represents partial drawdown. For predictive model, the modeled east and west trench segments were boxed in with head boundaries relatively close to the trenches (40 ft.) to represent assumed extent of aquifer influence from temporary dewatering (Figure 2). A close head boundary provides a higher, more conservative flow rate estimate than infinite-extent assumptions. In a sensitivity analysis, moving the head boundary closer to the excavation (20 feet) resulted in a 30% increase in estimated flow. As the sensitivity prediction is within an order of magnitude, head boundary distance is not considered significant in this range.

Soil data: Soil borings indicate the water table aquifer is comprised of fine-grained alluvium, with occasional thin sand lenses. Hydraulic conductivity testing was performed at two locations, where values of 0.06 and 0.22 ft./day were estimated for monitoring wells in the western and eastern project areas, respectively. Hydraulic conductivity zones are shown on Figure 1.

The predictive model was run using dry and wet weather water table conditions. Depths to water in

## **Method:**

Dewatering rates were estimated assuming a 25-foot trench length open at a time, with 5-foot width. Two trench lengths were modeled separately, representing the two soil conductivity zones, where shown on Figure 2. The computational grid is also shown on Figure 2. The model contains 61 vertical layers for discretization of vertical flow.

# NEWINGTON NH – SRP INSTALLATION DEWATERING FLOW ESTIMATE FOR INSTALLATION TRENCH GW MODFLOW MODEL DESCRIPTION

## **Method (continued):**

The model was bounded to include the full run of trench. Constant head cells were assigned within trench segments assuming sumps control water level. Both segments were boxed in with head boundaries approximately 40 feet from the trench (Figure 2), assuming a cone of influence would not extend very far during the period of open excavation. Head boundaries were assigned the elevations shown on Figure 3. The head boundaries create two separate model domains for each segment.

Site-specific elevations and the head boundary enclosures were used for reference purposes as shown on Figure 2. A 25-foot trench segment two feet below water table in soil of similar hydraulic conductivity would yield similar results. Similarly, smaller models the size of the head boundary enclosures would yield similar results.

For both trench segments, dewatering estimates were computed with and without inclusion of an approximately 6-inch sand seam (hydraulic conductivity = 5 ft./d) about a foot above excavation base.


## **Results:**

Results shown and tabulated on Figure 4. Comparatively, predicted rates increase disproportionately higher with the sand seam assumption in the east segment.



## **Limitations:**

Model simulations represent seepage from soil strata represented as uniform, homogeneous, and isotropic. The soil properties modeled are represented by two borings and two hydraulic conductivity test results, which is a relatively low data density. Flow rate estimates may vary with additional information. Actual variability encountered may result in dewatering rates different than those predicted.


Potential water sources not modeled may also need to be considered for planning purposes, including but not limited to free drainage from soil while being excavated, storm runoff, channeling from high conductivity zones or other hydraulic connections to surface water, and subsurface features with contained or perched water.



BASE PLAN SOURCE:  
 "115KV F107 UNDERGROUND TRANSMISSION LINE",  
 PLAN AND PROFILE VIEW, REVISION 7, 6/24/16

<p>TRANSMISSION MAIN TRENCH DEWATERING          SEACOAST RELIABILITY PROJECT          NEWINGTON, NEW HAMPSHIRE</p>		<p>MODEL SPACE</p>
	<p>Project 1607530</p>	<p>June 2017 <span style="float: right;">Figure 1</span></p>





**LEGEND**




MODEL COMPUTATIONAL GRID



MODELED TRENCH SEGMENT



MODELED CONSTANT-HEAD BOUNDARY LOCATION



SCALE, FEET



BASE PLAN SOURCE:  
 "115KV F107 UNDERGROUND TRANSMISSION LINE",  
 PLAN AND PROFILE VIEW, REVISION 7, 6/24/16

TRANSMISSION MAIN TRENCH DEWATERING  
 SEACOAST RELIABILITY PROJECT  
 NEWINGTON, NEW HAMPSHIRE




COMPUTATIONAL GRID

Project 1607530

June 2017

Figure 2

NEWINGTON



EAST – WEST CROSS SECTION ALONG TRENCH

**LEGEND**

- WATER TABLE ELEVATION USED IN MODEL FOR RESPECTIVE TRENCH SEGMENT. WEST USES MW101, EAST USES MW102.
- IDEALIZED WATER TABLE



DRAWING SOURCE:  
"115kV F107 UNDERGROUND TRANSMISSION LINE",  
PLAN AND PROFILE VIEW, REVISION 7, 6/24/16

TRANSMISSION MAIN TRENCH DEWATERING  
SEACOAST RELIABILITY PROJECT  
NEWINGTON, NEW HAMPSHIRE

**EVERSOURCE**  
ENERGY



Project 1607530

**IDEALIZED WATER TABLE  
PROFILE**

June 2017


Figure 3



## RESULTS SUMMARY

Trench Segment	Units	LOW GROUNDWATER		HIGH GROUNDWATER	
		West	East	West	East
Station	Ft.	500+00 to 500+25	503+75 to 504+00	500+00 to 500+25	503+75 to 504+00
Assumed Ground Surface	Ft.	41	55	41	55
Static Depth to Water (a)	Ft.	4.8	3.8	0.83	1.12
Static GW elev	ft. NAVD	37	51	40.2	54
Depth of Trench	Ft.	7	8	7	8
Drawdown	Ft.	3	4	6.2	7
Hyd. Conductivity	ft./day	0.06	0.22	0.06	0.22
Target GW elev	ft. NAVD	34	47	34	47
Dewatering Rate - no sand seam	gpd	45	486	104	942
Dewatering Rate - with sand seam	gpd	82	770	187	1466

a. Depth below ground surface at MW101 (west segment) or MW102 (east segment).



TRANSMISSION MAIN TRENCH DEWATERING  
SEACOAST RELIABILITY PROJECT  
NEWINGTON, NEW HAMPSHIRE

**EVERSOURCE**  
ENERGY



Project 1607530

**DEWATERING  
ESTIMATE AND  
DRAWDOWN PLOTS**

June 2017

Figure 4

## **Appendix B**

---

**Pease Area of Special Notice Documents**



DEPARTMENT OF THE AIR FORCE  
AIR FORCE CIVIL ENGINEER CENTER



11 Aug 17

Jared Sheehan  
Pease Development Authority  
55 International Drive  
Portsmouth, NH 03801

Re: Area of Special Notice for Eversource Utility Easement – May 23, 2017

Dear Jared.

With regard to the subject Area of Special Notice (ASN) request, the Air Force (AF) reviewed the information provided in order to identify potential impact to ongoing AF remedial activities. As noted in your request, segments of the project area east of Arboretum Drive are located within two Groundwater Management Zones (GMZ): the Landfill 5 GMZ and the Site 13 GMZ. Additionally, Air Force delineation efforts have identified perfluorooctane sulfonate (PFOS) and perfluorooctanoic acid (PFOA) in groundwater originating from the former Pease Air Force Base. Two figures are attached to this letter depicting presumed extent of combined PFOS + PFOA concentrations in overburden and bedrock units. As you can see, there are areas where the proposed work is likely to encounter PFOS + PFOA at concentrations greater than the New Hampshire Department of Environmental Services (NH DES) Ambient Groundwater Quality Standards (AGQS). Saturated soils may also contain PFOS or PFOA due to the presence of these chemicals in the groundwater. The contractor must follow NH DES requirements for managing contaminated groundwater and soils in these areas. Please note the Air Force operated treatment system at Site 8 is not available to treat water generated by this activity. Otherwise, the AF concurs with the work as presented in the ASN letter. Please feel free to contact me at (207) 328-7109 x7 or by email at [Peter.Forbes@us.af.mil](mailto:Peter.Forbes@us.af.mil) if you have any questions

PETER W. FORBES, GS-13  
Environmental Program Manager

2 Attachments:

1. Extent of PFOS + PFOA Concentration in Overburden Groundwater above AGQS
2. Extent of PFOS + PFOA Concentration in Bedrock Groundwater above AGQS

## Jared Sheehan

---

**From:** Hilton, Scott <Scott.Hilton@des.nh.gov>  
**Sent:** Wednesday, August 09, 2017 5:34 PM  
**To:** Comstock, Gregg; Pelletier, Rene; Wiggin, Dori; Mauck, Ridge  
**Cc:** Locker, Mitch; Jared Sheehan; FORBES, PETER W GS-13 USAF HAF AFCEC/CIBE; 'Daly, Michael'; Mongeon, Robin; Sandin, Peter  
**Subject:** Eversource Seacoast Reliability Project  
**Attachments:** PFOS+PFOA in Bedrock GW above AGQS.PDF; PFOS+PFOA in Overburden GW above AGQS.pdf

**Follow Up Flag:** Follow up  
**Flag Status:** Flagged

Hi Gregg

The Waste Management Division, DOD Sites Section has completed reviewing the Eversource Seacoast Reliability Project Soil and Groundwater Management Plan (Plan) as it pertains to proposed construction work in areas of Newington and the Pease Tradeport potentially impacted with PFC's or other contamination from past Air Force activities at the Former Pease AFB.

Comments.

- 1) The Frink Farm Property Soil and Groundwater Management Plan is located in Appendix A and was developed based upon specific boring and sampling work undertaken to better understand the conditions at the site. The data Eversource collected supports their proposed soil and groundwater management approach. It appears groundwater generated from the Knights Brook crossing area will be assumed to be contaminated with PFCs and will be treated either on or offsite and discharged under an applicable permit program . Given the PFC contamination associated with the Knights Brook area, these measures are appropriate. In the report's discussion of this dewatering and treatment location we note a discrepancy between the alignment station numbers between the "Project Area Plan" and the "Cross Section Knights Brook Tributary" and could not verify the exact area where groundwater treatment will be implemented. As an example HA-1 in the Project Area Plan is located at station 498+78.61, however in the Knights Brook Cross Section HA-1 is located at 497+60.5. This discrepancy needs to be clarified so the assumed area needing treatment can be verified.
- 2) Work outside the Frink property is addressed in the general Plan. On page 4, the Dewatering Section states that "We have assumed that groundwater generated during dewatering is acceptable for recharge within the Project Area." There does not appear to be any discussion regarding sampling procedures for the generated water to determine if contaminants are present above the AGQS and if treatment is needed. The Air Force has developed the attached PFC groundwater contamination maps for bedrock and overburden groundwater. The location of the Eversource work is also shown on the maps. While the maps are preliminary, and a GMZ has not been finalized, it is evident that nearly all of the Eversource work locations are within or near the inferred AGQS PFC groundwater contamination boundary and under these circumstances Eversource needs to include in the Plan a water sampling and testing program to determine the appropriate method of handling generated water.
- 3) Eversource should contact the Air Force to determine if water treatment at the Site 8 plant is an option as described in the Plan.

- 4) An Area of Special Notice approval from the Air Force/PDA is needed for work being conducted on the Pease Tradeport property. These comments do not supersede the ASN requirements and procedures. In addition to the PFC contamination, several of the Eversource excavations appear to be located within or on the established GMZ boundary of 2 Pease contaminated sites; Landfill 5 and the BFSAs. Any excavation dewatering in these GMZ areas should also be sampled for metals and VOC's.
- 5) While our review focused on Pease related contamination, Eversource should evaluate if other contamination related to the past maintenance of powerlines could be associated with the soils or groundwater and if so this should be addressed in the Plan. For example past herbicide use should be examined, one concern would be the transport of potentially contaminated soils to off-site locations.

If you have any questions regarding these comments please give me a call.

Thanks  
Scott

Scott Hilton  
Waste Management Division  
DOD Sites Section  
603-559-1512

**From:** Comstock, Gregg  
**Sent:** Tuesday, August 01, 2017 2:59 PM  
**To:** Hilton, Scott; Locker, Mitch  
**Cc:** Wiggin, Dori; Mauck, Ridge; Pelletier, Rene  
**Subject:** SRP Soil and GW Mgmt Plan

Hi Scott and Mitch:

Please review the Soil and Groundwater Management Plan for the Eversource Seacoast Reliability Project which is before the Site Evaluation Committee (SEC).


Please let Ridge, Dori and I know by August 15<sup>th</sup> if you have any comments. If that date doesn't work for you, please let me know when you think can get to it.

Thank you gents.



Best,  
Gregg

**Gregg Comstock, P.E.**  
**Supervisor, Water Quality Planning Section**  
NH Department of Environmental Services, Watershed Management Bureau  
29 Hazen Drive, PO Box 95  
Concord, NH 03302-0095  
603-271-2983  
[gregg.comstock@des.nh.gov](mailto:gregg.comstock@des.nh.gov)






Document: P:\Projects\AGOS\GIS\Map\PFOS+PFOA in Bedrock\_GW\_AboveAGOS.mxd 07/05/2017 4:03 PM brain@briars.com

 <p><b>Air Force Civil Engineer Center</b>          2261 Hughes Avenue          Building 171, Ste 155          JBSA Lackland, Texas 78236</p>	<p><b>Extent of PFOS + PFOA Concentration          in Bedrock Groundwater above AGQS</b></p> <p>Former Pease Air Force Base, Portsmouth, New Hampshire</p>							
<p>0 150 300 600 900 1,200 1,500 Meters</p> <p>0 750 1,500 3,000 4,500 6,000 Feet</p>	 <p><b>NOTES:</b>          -Aerial Imagery obtained through ESRI Online Services</p>	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 33%;">7/5/2017</td> <td style="width: 33%;">Rev:</td> <td style="width: 33%;">GMZ_11x17P</td> </tr> <tr> <td>Drawn: BRP</td> <td>Chk: RS</td> <td>PROJ: 775361201</td> </tr> </table>	7/5/2017	Rev:	GMZ_11x17P	Drawn: BRP	Chk: RS	PROJ: 775361201
7/5/2017	Rev:	GMZ_11x17P						
Drawn: BRP	Chk: RS	PROJ: 775361201						






<p><b>Air Force Civil Engineer Center</b>        2261 Hughes Avenue        Building 171, Ste 155        JBSA Lackland, Texas 78236</p>	<p><b>Extent of PFOS + PFOA Concentration          in Overburden Groundwater above AGQS</b></p> <p>Former Pease Air Force Base, Portsmouth, New Hampshire</p>			
	<p>0 150 300 600 900 1,200 1,500 Meters</p> <p>0 750 1,500 3,000 4,500 6,000 Feet</p>			<p>NOTES:        -Aerial Imagery obtained through ESRI Online Services</p>
		<p>Drawn: BRP</p>	<p>Chk: RS</p>	<p>PROJ: 775361201</p>



REVISION	DESCRIPTION	DATE	BY
1	Combined PDA base map of current conditions w/ AF Parcel boundaries. Added "Excepted Parcels", "Use Restriction Zones", and "GMZ Boundaries"	9/5/01	V.E.N.
2	Revisions per electronic mail request dated 1/7/02 (i.e. Site 49 GMZ boundary, Zone 3 URZ, etc.)	1/23/02	V.E.N.
3	Revisions to Zone 3 GMZ and Site 49 URZ	6/18/02	V.E.N.
4	Revisions to Zone 3 and Site 49 Excepted Parcel Areas	9/30/02	V.E.N.
5	Revisions Site 49 Excepted Parcel Areas	3/25/04	V.E.N.
6	General Revisions	1/6/06	V.E.N.

PARCEL ID	CONV. TYPE	PROPERTY RECIPIENT	ACRES
L.M	FAT	U.S. FISH AND WILDLIFE SERVICE	1054.00
J	PBC	STATE OF NEW HAMPSHIRE, DEPT OF TRANSPORTATION	19.19
F	PBC	PEASE DEVELOPMENT AUTHORITY	151.88
OLD STONE SCHOOL A (PARTIAL)	S	TOWN OF NEWINGTON	1.41
C	PBC	PEASE DEVELOPMENT AUTHORITY	1160.5
D	PBC	PEASE DEVELOPMENT AUTHORITY	171.0
E	PBC	PEASE DEVELOPMENT AUTHORITY	75.00
G	PBC	PEASE DEVELOPMENT AUTHORITY	165.00
G.T	PBC	PEASE DEVELOPMENT AUTHORITY	150.00
H	PBC	PEASE DEVELOPMENT AUTHORITY	35.00
I	PBC	PEASE DEVELOPMENT AUTHORITY	400.00
I.T	PBC	PEASE DEVELOPMENT AUTHORITY	202.00
K	PBC	PEASE DEVELOPMENT AUTHORITY	184.00
MCINTYRE ROAD	S	PEASE DEVELOPMENT AUTHORITY	280.00
B	NONE	TOWN OF NEWINGTON	8.30
		AIR FORCE RETAINED	218.00



**LEGEND**


- BA BURN AREA
  - BFSA BULK FUEL STORAGE AREA
  - CRD CONSTRUCTION RUBBLE DUMP
  - FAT FEDERAL AGENCY TRANSFER
  - FDTA FIRE DEPARTMENT TRAINING AREA
  - FLRS FLIGHTLINE REFUELING SYSTEM
  - GMZ GROUNDWATER MANAGEMENT ZONE
  - JETC JET ENGINE TEST CELL
  - LF LANDFILL
  - LFTS LEADED FUEL TANK SLUDGE AREA
  - OJETS OLD JET ENGINE TEST STAND
  - PBC PUBLIC BENEFIT CONVEYANCE
  - PCB POLYCHLORINATED BIPHENYL
  - S STATUTE
  - UST UNDERGROUND STORAGE TANK
  - URZ USE RESTRICTION ZONE
- 
- GMZ BOUNDARY
  - ▨ RECHARGE TRENCH
  - ▨ USE RESTRICTION ZONE
  - ▨ WETLAND RESTORATION/PRESERVATION AREA
  - ▨ NEWINGTON TOWN FOREST
  - ▨ ASBESTOS BURIAL SITE
  - STREAM/DITCH
  - BASE BOUNDARY
  - A** PARCEL IDENTIFICATION

**FORMER PEASE AFB, NEW HAMPSHIRE**

**INSTITUTIONAL CONTROLS MAP**

DATE  
**JANUARY 13, 2006**

**MWH**





certain environmental conditions, the Grantor shall not be liable for any latent or patent defects in the Property, except to the extent required by applicable law.

VI. NOTICES AND COVENANTS RELATED TO SECTION 120(h)(3) OF THE COMPREHENSIVE ENVIRONMENTAL RESPONSE, COMPENSATION AND LIABILITY ACT (CERCLA), AS AMENDED, (42 U.S.C. §9620(h)(3)).

A. Pursuant to section 120(h)(3)(A)(i) of CERCLA, the following is notice of hazardous substances on the Property, and a description of remedial action taken by the Grantor concerning the Property.

1. The Grantor has made a complete search of its files and records. Exhibit B contains a table with the name of hazardous substances stored for one year or more, or known to have been released or disposed of, on the Property; the quantity in kilograms and pounds of the hazardous substance stored for one year or more, or known to have been released, or disposed of, on the Property; and the date(s) on which such storage, release, or disposal took place.

2. A description of the remedial action(s) taken by the Grantor on the Property regarding hazardous substances is contained in Exhibit B.

3. Pursuant to section 120(h)(3)(A)(ii) of CERCLA, the United States covenants and warrants:

(a) that all remedial action necessary to protect human health and the environment with respect to hazardous substances remaining on the Property has been taken before the date of this Deed; and

(b) any additional remedial action found to be necessary after the date of this Deed for contamination on the Property existing prior to the date of this Deed will be conducted by the United States.

This warranty will not apply in any case in which any grantee of the Property, or any part thereof, is a potentially responsible party under CERCLA with respect to the Property before the date on which such grantee acquired its interest in the Property, or is a potentially responsible party as a result of an act or omission affecting the Property. For the purposes of this warranty, the phrase "remedial action necessary" does not include any performance by the United States, or payment to the Grantee from the United States, for additional remedial action that is required to facilitate use of the Property for uses and activities prohibited by those environmental use restrictive covenants set forth in section VI.B. below, as may be modified or released pursuant to section VI.C.

4. The United States has reserved a no-cost right of access to the Property in the Reservation section of this Deed in order to perform any remedial or corrective action as required by CERCLA section 120(h)(3)(A)(iii).

## NOTICE

### BREACH OF ANY ENVIRONMENTAL USE RESTRICTIVE COVENANT IN SECTION VI.B. BELOW, MAY AFFECT THE FOREGOING WARRANTY

#### B. Environmental Use Restrictive Covenants

1. For purposes of the environmental use restrictive covenants in this section, the term "Property" includes any part of the Property specifically described on Exhibit A to this Deed to which one or more of these environmental restrictive covenants may apply.

2. The following environmental use restrictive covenants are being created to protect human health and the environment with regard to residual contamination remaining on the property and are a component of the remedial action referred to in Section A.2 above:

(a) The groundwater within the areas described in Exhibit C as "Groundwater Management Zones" (hereafter GMZs) is contaminated with chlorinated volatile organic compounds, petroleum related hydrocarbons, or other substances deemed potentially harmful to human health. In order to protect the public and site personnel (from exposure to the contaminants), and to protect the integrity of the Grantor's remedial activities and systems, and to prevent interference with such remedial activities, subject to paragraph VI.C. below, the Grantee is prohibited from installing a well within a GMZ except for the purpose of determining or monitoring groundwater quality or quantity.. In addition, subject to paragraph VI.C. below and subparagraphs (b) and (c) below, in those areas on the Property located outside the GMZs described in Exhibit C, the Grantee is prohibited from extracting any groundwater, injecting water into the ground or applying surface water in a manner that causes the migration of any contaminated groundwater in excess of ambient groundwater quality standards to a point beyond the applicable GMZ. Nothing contained in this section shall prohibit the Grantee from creating new drinking water supply wells to replace in kind drinking water supply wells existing on the Property on or before the date hereof, namely, the Smith Well, the Harrison Well, and the Haven Well.

(b) The Grantee may extract groundwater from the Smith and Harrison wells, and any replacement thereof, up to the sustainable yield for each well. With respect to the so-called Haven Well, or any replacement thereof, the Grantee shall not exceed the water consumption rates through the year 2010, which are described in Exhibit D hereto. Notwithstanding the foregoing limitations, the Grantor may grant exceptions to the pumping limits referred to in Exhibit D upon the written request of the Grantee. The Grantee shall bear all costs whatsoever in obtaining approval to exceed these pumping limitations.

(1). The Grantor shall release the pumping restrictions on the so-called Haven Well, or any replacement thereof, if at any time the Grantor determines such restriction is no longer needed. If at the end of the period described in Exhibit D, the Grantor determines a limitation on use of the Haven Well or any replacement is still required, the Grantee shall be limited to use of the Haven Well and/or replacement up to the limits authorized in the year 2010.

(2). During the period of the restriction described in paragraph 2(b) above, the Grantee shall consult with the Grantor at least annually regarding the usage of the Haven Well, or any such replacement well, and its potential to move contamination from various plumes within the well's zone of influence. The foregoing consultation shall occur during March, prior to the Grantee's peak water demand season. This requirement to consult with the Grantor may be waived upon the Grantee obtaining the written approval of the Grantor.

(3). As long as the Grantee is operating within the limits authorized under either Exhibit D or paragraph VIB2(b)(1) of the deed, the Grantor shall operate a treatment plant to address any contaminated groundwater extracted from the Haven Well. Notwithstanding the foregoing, the Grantor will not be responsible for the cost of operating the treatment plant if the Grantee extracts water in excess of the pumping restrictions contained in this deed and such excess withdrawal is the sole reason that operation of the treatment plant is required.

(c) The surface and subsurface soils within the areas described in Exhibit C as "Use Restriction Zones" (hereafter URZs) are contaminated with chlorinated volatile organic compounds, petroleum related hydrocarbons, or other substances deemed potentially harmful to human health. In order to prevent direct exposure to and protect the public and site personnel (from exposure to the contaminants), and to protect the integrity of the Grantor's remedial activities, and to prevent interference with such remedial activities, subject to paragraph VI.C. below, the Grantee is prohibited from using any portion of the Property within the URZs for residential use, childcare centers, playgrounds, athletic fields, or elementary or secondary schools. The Grantee is also prohibited from any digging, excavation, or construction within the URZs unless the Grantee obtains approval from the Grantor as provided in the Memorandum of Understanding between the Pease Development Authority and the U.S. Air Force attached hereto as Exhibit E or paragraph V.C. below in the event this restriction may be released.

(d) In order to protect the integrity of the Grantor's remedies with respect to the URZs described as Construction Rubble Dump 1 (CRD-1 Site 9) Construction Rubble Dump 2 (CRD - 2 Site 17), and Landfill 5 (Site 5), as described in Exhibit C, the Grantee shall take no action that impacts the integrity of the landfill cover system at these URZs. Such prohibited activities include but are not limited to use of ATV or other similar vehicles, excavation or other activities that lead to erosion or damage of the landfill cover system.

(e) The Grantee covenants not to disturb, move, damage, mar, tamper with, interfere with, obstruct, or impede any monitoring wells, treatment facilities, piping, and other facilities associated with any environmental investigation, response action or other corrective action on the Property. The Grantee covenants not to disturb buried asbestos-containing material (ACM) or associated cover material in the ACM Zones described on Exhibit C without the prior written approval of the NHDES Waste Management Division.

3. It is the intent of the Grantor and the Grantee that the Environmental Use Restrictive Covenants in this section bind the Grantee and shall run with the land. It is also the intent of the Grantor and the Grantee that the Grantor will retain the right to enforce any restrictive covenant in this section through the chain of title, in addition to any State law that requires the State

to enforce any restrictive covenant in this section. The Grantee covenants to insert all of this section in any deed to the Property that it delivers.

### C. Release of Environmental Use Restrictive Covenants.

1. The Grantee may request from the United States a modification or release of one or more of the environmental use restrictive covenants in whole or in part in this section, subject to the notification and concurrence or approval of the NHDES and EPA Region 1. In the event the request of the Grantee for modification or release is approved by the United States, NHDES, and EPA Region 1, the United States agrees to modify or release the covenant (the "Covenant Release") giving rise to such environmental use restriction in whole or in part. The Grantee understands and agrees that all costs associated with the Covenant Release shall be the sole responsibility of the Grantee, without any cost whatsoever to the United States. The United States shall deliver to the Grantee in recordable form the Covenant Release. The execution of the Covenant Release by the United States shall modify or release the environmental use restrictive covenant with respect to the Property in the Covenant Release.

2. In the event that the environmental use restrictive covenants contained in this section are no longer necessary, the United States will record any appropriate document modifying or removing such use restrictions, as appropriate.

## VII. OTHER COVENANTS

A. Airport Obligations. By the acceptance of this Deed or any rights hereunder, the Grantee, for itself, its successors and assigns, agrees that the transfer of all the Property transferred by this Deed, is accepted subject to the following terms, restrictions, reservations, covenants, and conditions set forth in subparagraphs 1 and 2 of this paragraph, which shall run with the land, provided that the Property transferred hereby may be successively transferred only with the proviso that, unless otherwise approved by the Federal Aviation Administration (FAA), any such subsequent transferee assumes all of the obligations upon the Grantee by the provisions of this Deed:

1. That, except as provided in subparagraph 1 of the below paragraph B, the property transferred by this instrument shall be used for public airport purposes for the use and benefit of the public, on fair and reasonable terms and without unjust discrimination and without grant or exercise for any exclusive right for use of the airport within the meaning of the term "exclusive right" as used in subparagraph 3 of the below paragraph B. As used in this instrument, the term "airport" shall be deemed to include all land, buildings, structures, improvements and equipment used for public airport purposes.

2. That, except as provided in subparagraph 1 of the below paragraph B, the entire landing area, as defined in 49 U.S.C. 40102(28) and Federal Aviation Regulations pertaining thereto, and all structures, improvements, facilities and equipment in which this Deed transfers any interest shall be maintained for the use and benefit of the public at all times in safe and serviceable condition,