


GRADING NOTES:

1. REFER TO SHEET NPTT602-G001 FOR ADDITIONAL GENERAL NOTES, ABBREVIATIONS, AND LEGENDS.
2. REFER TO SHEET NPTT609-C300 FOR GRADING CROSS SECTIONS.
3. NEW HAMPSHIRE STATE PLANE COORDINATE SYSTEM
HORIZONTAL DATUM - NAD83
VERTICAL DATUM - NAVD88
4. PROPOSED CONTOURS AND SPOT ELEVATIONS INDICATED REFER TO TOP OF FINISH SURFACE.
5. ALL FILL AND CUT SLOPES ARE 3-FT HORIZONTAL TO 1-FT VERTICAL (3:1) UNLESS NOTED OTHERWISE.



6. CONTRACTOR SHALL PLACE 4" TOPSOIL AND SEED ON ALL CUT AND FILL SLOPES AS SPECIFIED UNLESS ANOTHER SURFACE MATERIAL IS INDICATED. EROSION CONTROL BLANKETS (NORTH AMERICAN GREEN SC250 OR ENGINEER APPROVED EQUAL) SHALL BE PLACED OVER ALL SEEDED SIDE SLOPES.
7. AFTER COMPLETION OF YARD SUBGRADE WORK, THE SURFACE COURSE FOR THE SUBSTATION (INSIDE THE FENCE, 3-FT OUTSIDE THE FENCE, AND WHERE INDICATED ON THE PLANS) SHALL CONSIST OF A 4-INCH LAYER OF CRUSHED BASALT (ANGULAR STONE) STONE MEETING THE GRADATION REQUIREMENTS EXPLAINED IN THE SPECIFICATIONS.
8. CONTRACTOR SHALL PROTECT/REPAIR ALL SLOPES UNTIL FINAL VEGETATIVE OR STONE STABILIZATION.

9. ALL EXCAVATIONS SHALL BE THOROUGHLY SECURED AND STABILIZED ON A DAILY BASIS BY THE CONTRACTOR AT THE COMPLETION OF CONSTRUCTION OPERATIONS.
10. STABILIZE ALL DITCHES, SWALES, AND PONDS PRIOR TO DIRECTING STORMWATER RUNOFF TO THEM.
11. TURF REINFORCEMENT MAT (TRM) SHALL BE INSTALLED ON ALL 3-FT HORIZONTAL TO 1-FT VERTICAL SLOPES (3:1) OR STEEPER, AND BE NORTH AMERICAN GREEN SC250 OR APPROVED EQUAL.
12. EARTHWORK AND COMPACTION SHALL BE IN ACCORDANCE WITH THE RECOMMENDATIONS MADE IN THE GEOTECHNICAL ENGINEERING REPORT BY OTHERS.



LAYOUT POINTS TABLE				
POINT #	NORTHING	EASTING	ELEVATION	DESCRIPTION
100	233660.85	1111918.54	387.00	CL 2' DITCH
101	233981.72	1112146.85	385.00	CL 2' - 4' DITCH
102	234014.26	1112170.12	381.00	CL 4' DITCH
103	234001.90	1112177.80	385.00	TSLOPE
104	233962.14	1112234.39	385.00	TSLOPE
105	233966.26	1112267.96	385.00	TSLOPE
106	233994.22	1112291.77	385.00	TSLOPE
107	234029.07	1112317.52	384.00	TSLOPE
108	234032.51	1112319.92	384.00	TSLOPE
109	234072.08	1112345.81	384.00	32' SPILLWAY
110	234100.96	1112361.77	384.00	32' SPILLWAY
111	234156.87	1112324.10	385.00	TSLOPE
112	234175.94	1112305.24	386.00	TSLOPE
113	234159.75	1112280.76	380.00	BSLOPE
114	234161.24	1112294.82	380.00	BSLOPE
115	234119.94	1112345.95	380.00	BSLOPE
116	234107.24	1112348.37	380.00	BSLOPE
117	234036.85	1112308.38	380.00	BSLOPE
118	233975.99	1112256.54	380.00	BSLOPE
119	233974.34	1112243.11	380.00	BSLOPE
120	234023.45	1112174.46	380.00	BSLOPE
121	234030.68	1112176.70	380.00	BSLOPE
122	234095.40	1112228.76	380.00	BSLOPE
123	234028.61	1112324.61	384.00	TSLOPE
124	234152.06	1112390.41	384.00	TSLOPE
125	234174.86	1112388.80	384.00	TSLOPE
126	234189.89	1112402.08	384.00	TSLOPE
127	234130.41	1112429.68	377.00	TSLOPE
128	234030.26	1112356.97	383.00	TSLOPE
129	233988.17	1112345.26	383.00	TSLOPE
130	233955.67	1112357.16	383.00	TSLOPE
131	233921.60	1112395.11	383.00	TSLOPE
132	233870.77	1112356.18	385.00	TSLOPE
133	233853.39	1112359.15	384.00	TSLOPE
134	233829.69	1112407.22	380.00	TSLOPE
135	233888.72	1112443.26	378.00	FOREBAY/FILTER
136	233860.69	1112378.12	378.00	CL 4' DITCH
137	233916.25	1112420.70	376.00	CL 4' DITCH
138	233972.78	1112381.87	374.00	CL 4' DITCH
139	233896.80	1112489.81	370.00	CL 4' DITCH
140	233838.33	1112405.51	378.00	FOREBAY/FILTER
141	233856.88	1112389.53	381.00	T/SLOPE
142	233906.33	1112428.62	379.00	T/SLOPE
143	233864.72	1112457.23	379.00	T/SLOPE
144	233826.65	1112424.67	379.00	T/SLOPE
145	233844.28	1112338.45	385.00	BSLOPE
146	233888.95	1112451.52	379.00	13' SPILLWAY
147	233787.26	1112470.95	375.00	BSLOPE
148	233855.65	1112470.76	374.00	BSLOPE

LAYOUT POINTS TABLE				
POINT #	NORTHING	EASTING	ELEVATION	DESCRIPTION
149	233889.86	1112472.07	371.00	BSLOPE
150	233852.15	1112501.67	373.00	TSLOPE
151	233831.63	1112507.07	373.00	TSLOPE
152	233802.86	1112490.30	373.00	TSLOPE
153	233858.19	1112491.30	373.00	TSLOPE
154	233744.18	1112540.95	373.00	TSLOPE
155	233749.47	1112570.18	373.00	TSLOPE
156	233806.25	1112609.55	373.00	TSLOPE
157	233832.46	1112607.73	373.00	TSLOPE
158	233877.89	1112569.87	373.00	32' SPILLWAY
159	233907.88	1112536.31	373.00	TSLOPE
160	233914.86	1112524.33	373.00	TSLOPE
161	233910.88	1112496.11	373.00	TSLOPE
162	233916.00	1112492.76	373.00	TSLOPE
163	233922.70	1112520.55	370.00	TSLOPE
164	233913.07	1112539.33	373.00	TSLOPE
165	233901.41	1112548.17	373.00	32' SPILLWAY
166	233836.53	1112612.13	373.00	TSLOPE
167	233802.83	1112614.48	373.00	TSLOPE
168	233888.20	1112538.09	373.00	TSLOPE
169	233750.14	1112527.09	374.00	BSLOPE
170	233694.18	1112538.39	374.00	BSLOPE
171	233756.51	1112549.50	368.00	BSLOPE
172	233758.02	1112557.85	368.00	BSLOPE
173	233814.80	1112597.23	368.00	BSLOPE
174	233822.29	1112596.70	368.00	BSLOPE
175	233893.66	1112530.60	368.00	BSLOPE
176	233901.91	1112516.78	368.00	BSLOPE
177	233899.02	1112505.84	368.00	BSLOPE
178	233882.09	1112495.97	368.00	BSLOPE
179	233871.15	1112498.85	368.00	BSLOPE
180	233865.10	1112509.22	368.00	BSLOPE
181	233824.08	1112520.03	368.00	BSLOPE
182	233795.30	1112503.26	368.00	BSLOPE
183	233787.35	1112505.03	368.00	BSLOPE
184	233717.26	1112574.49	368.00	BSLOPE
185	233794.28	1112626.81	368.00	BSLOPE
186	233846.71	1112623.16	368.00	BSLOPE
187	233916.56	1112558.68	368.00	BSLOPE
188	233914.78	1112573.93	367.00	TSLOPE
189	233853.49	1112630.50	367.00	TSLOPE
190	233800.73	1112641.26	367.00	TSLOPE
191	233772.32	1112644.44	367.00	TSLOPE
192	233745.55	1112626.48	367.00	TSLOPE
193	233738.84	1112601.08	367.00	TSLOPE
194	233715.19	1112576.73	367.00	TSLOPE
195	233797.78	1112437.29	378.00	BSLOPE
196	233959.46	1112417.62	375.00	TSLOPE
197	233941.05	1112442.30	374.00	TSLOPE



FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION

THE NORTHERN PASS

Transmission Business

#


DEERFIELD SUBSTATION
GRADING PLAN

DES: LRW | CHK: LRW
DRAW: FP | APR: BSS
TOWN: DEERFIELD, NH
TRANSMISSION LINE:

MILE NO:
SHEET 4 OF 19
NPTT604-C101

REVISION: 11/15/2013

1 ISSUED FOR PERMITTING
10/1/15
DATE
NO.
R/R
CHG
APPROV.



- NOTES:**
- 1. SEE SHEET NPTT610-C500 FOR EROSION AND SEDIMENTATION NOTES.**
 - 2. TOTAL LIMIT OF DISTURBANCE = 363,902 SF = 8.40 ACRES**

**FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION**

DEERFIELD SUBSTATION EROSION AND SEDIMENTATION CONTROL PLAN		DATE: 10/7/2015	
DES: LRM CHK: RLR		SCALE: H 1" = 40'	
DRAW: FP APR: BSS			
TOWN: DEERFIELD, NH			
TRANSMISSION LINE:			
MILE NO:			
SHEET 5 OF 19			
NP17805-C102			

1. REFER TO SHEET NPTT602-G001 FOR ADDITIONAL GENERAL NOTES, ABBREVIATIONS, AND LEGENDS.
2. THIS DRAWING IS INTENDED TO DESCRIBE THE STORMWATER SYSTEM ONLY.
3. NEW HAMPSHIRE STATE PLANE COORDINATE SYSTEM
HORIZONTAL DATUM - NAD83
VERTICAL DATUM - NAVD88
4. STORM DRAINAGE SYSTEM CONNECTIONS, MATERIALS, AND METHODS SHALL BE IN ACCORDANCE WITH THE NH DOT STANDARDS AND NH DOT SPECIFICATION SECTIONS 603 AND 604, AS WELL AS OTHER APPLICABLE INDUSTRY CODES AND GOVERNING AGENCY REQUIREMENTS.

5. THE CONTRACTOR SHALL VISIT THE SITE AND VERIFY THE ELEVATION AND LOCATION OF ALL UTILITIES BY VARIOUS MEANS PRIOR TO BEGINNING ANY EXCAVATION. TEST PITS SHALL BE DUG AT ALL LOCATIONS WHERE PROPOSED STORM PIPING WILL CROSS EXISTING UTILITIES, AND THE HORIZONTAL AND VERTICAL LOCATIONS OF THE UTILITIES SHALL BE DETERMINED. THE CONTRACTOR SHALL CONTACT THE ENGINEER IN THE EVENT OF ANY DISCOVERED OR UNFORESEEN CONFLICTS BETWEEN EXISTING AND PROPOSED SANITARY SEWERS, STORM PIPING AND UTILITIES SO THAT AN APPROPRIATE MODIFICATION MAY BE MADE.
6. MANHOLE RIMS AND CATCH BASIN GRATES SHALL BE SET TO ELEVATIONS SHOWN. SET ALL EXISTING MANHOLE RIMS, GRATES AND OTHER UTILITY TOPS TO BE RAISED OR LOWERED FLUSH WITH FINAL GRADE AS NECESSARY.

7. THE CONTRACTOR SHALL ARRANGE FOR AND COORDINATE WITH APPLICABLE REGULATORY AGENCIES FOR STORM DRAINAGE INSTALLATIONS AND CONNECTIONS.
8. THE CONTRACTOR SHALL COORDINATE WORK TO BE PERFORMED BY THE VARIOUS UTILITY PROVIDERS AND SHALL PAY ALL FEES FOR CONNECTIONS, DISCONNECTIONS, RELOCATIONS, INSPECTIONS, AND DEMOLITION UNLESS OTHERWISE STATED IN THE PROJECT SPECIFICATIONS MANUAL AND/OR GENERAL CONDITIONS OF THE CONTRACT.
9. ALL PIPES SHALL BE LAID ON STRAIGHT ALIGNMENTS AND EVEN GRADES USING A PIPE LASER OR OTHER ACCURATE METHOD.

10. ALL UTILITY CONSTRUCTION IS SUBJECT TO INSPECTION FOR APPROVAL PRIOR TO BACKFILLING, IN ACCORDANCE WITH THE APPROPRIATE OWNER, UTILITY PROVIDER, AND APPLICABLE REGULATORY AGENCY REQUIREMENTS.
11. A ONE-FOOT MINIMUM VERTICAL CLEARANCE BETWEEN ELECTRICAL AND TELEPHONE LINES TO STORM PIPING SHALL BE PROVIDED.
12. SITE CONTRACTOR SHALL PROVIDE ALL BENDS, FITTINGS, ADAPTERS, ETC., AS REQUIRED FOR PIPE CONNECTIONS.
13. THE CONTRACTOR SHALL MAINTAIN ALL FLOWS AND UTILITY CONNECTIONS WITHOUT INTERRUPTION UNLESS/UNTIL AUTHORIZED BY THE OWNER, THE ENGINEER, UTILITY PROVIDERS AND GOVERNING AUTHORITIES.

14. STORM DRAINAGE SHALL BE RATED FOR HS-20 LOADING.
15. LAY UNDERDRAINS BELOW CABLE TRENCH AS SPECIFIED. PROVIDE MINIMUM 0.5% SLOPE ON ALL UNDERDRAINS. ADDITIONAL UNDERDRAINS MAY BE REQUIRED AS DEEMED NECESSARY BY THE OWNER, GEOTECHNICAL ENGINEER AND/OR ENGINEER BASED ON FINDINGS AFTER EARTHWORK AND EXCAVATION OPERATIONS COMMENCE. PROVIDE UNDERDRAIN CLEANOUTS AT A MINIMUM OF EVERY 200' OF PIPE OR ONE CLEANOUT PER PIPE RUN WHERE THE PIPE RUN IS LESS THAN 200'.


UNDERDRAIN SCHEDULE		
PIPE #	LENGTH (FT)	SLOPE
UD-1	205	0.005
UD-2	205	0.005
UD-3	370	0.005
UD-4	192	0.016
UD-5	218	0.015
UD-6	370	0.005
UD-7	200	0.015
UD-8	200	0.015
UD-9	200	0.010
UD-10	200	0.005
UD-11	200	0.005
UD-12	200	0.005
UD-13	255	0.015
UD-14	175	0.019

(*) APPROXIMATE SLOPE TO MATCH EXISTING 12" CMP.

NOTES:


1. UNDERDRAINS WITHIN SUBSTATION ARE 8" PERFORATED HDPE.
2. UNDERDRAIN WITHIN SAND FILTER ARE 6" PERFORATED HDPE.

UNDERDRAIN LAYOUT POINT TABLE				
POINT #	NORTHING	EASTING	INVERT ELEV	DESCRIPTION
100	233659.68	1111936.95	383.52	UNDERDRAIN
101	233537.75	1112101.94	382.50	UNDERDRAIN
102	233415.83	1112266.92	383.52	UNDERDRAIN
103	233713.56	1112486.59	381.71	UNDERDRAIN
104	233827.82	1112331.98	378.58	UNDERDRAIN
105	233957.24	1112156.85	381.71	UNDERDRAIN
106	233887.99	1112112.03	382.60	UNDERDRAIN
107	233769.18	1112272.92	379.60	UNDERDRAIN
108	233834.92	1112072.81	383.20	UNDERDRAIN
109	233716.11	1112233.70	380.20	UNDERDRAIN
110	233781.85	1112033.59	382.90	UNDERDRAIN
111	233663.04	1112194.48	380.90	UNDERDRAIN
112	233728.76	1111994.36	382.60	UNDERDRAIN
113	233609.96	1112155.25	381.60	UNDERDRAIN
114	233579.53	1112132.76	382.00	UNDERDRAIN
115	233460.67	1112293.61	383.00	UNDERDRAIN
116	233621.29	1112163.62	381.50	UNDERDRAIN
117	233502.43	1112324.47	382.50	UNDERDRAIN
118	233520.20	1112319.19	385.01	UNDERDRAIN
119	233725.27	1112470.74	381.26	UNDERDRAIN
120	233685.95	1112429.25	382.80	UNDERDRAIN
121	233790.12	1112288.29	379.40	UNDERDRAIN




A circular professional engineer seal for the State of New Hampshire. The outer ring contains the text "STATE OF NEW HAMPSHIRE" at the top and "PROFESSIONAL ENGINEER" at the bottom. The inner circle contains the name "BRIAN S. SANKOWICH" and the license number "No. 14328". The word "LICENSED" is written below the name. The seal is stamped over a signature.

This document has been digitally sealed.
Oct 5 2015



**FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION**

[illegible]Transmission
Business

	#
--	---


DEERFIELD SUBSTATION
STORMWATER SYSTEM PLAN

DES: LRM	CHK:RLR
DRW: FP	APR: BSS



DEERFIELD, NH
TRANSMISSION LINE:

MILE NO:

NPTT607-C104




- ACCESS ROAD PROFILE NOTES:
- REFER TO SHEET NPTT602-G001 FOR ADDITIONAL GENERAL NOTES, ABBREVIATIONS, AND LEGENDS.
 - THIS DRAWING IS INTENDED TO DESCRIBE THE STATION ACCESS ROAD GEOMETRY ONLY.
 - NEW HAMPSHIRE STATE PLANE COORDINATE SYSTEM
HORIZONTAL DATUM - NAD83
VERTICAL DATUM - NAVD88
 - PROPOSED CONTOURS AND SPOT ELEVATIONS INDICATED REFER TO TOP OF FINISH SURFACE.



**FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION**

NO.	ISSUED FOR PERMITTING	DATE	FP	DRWN	CHKD	APPRV.
1	ISSUED FOR PERMITTING	10/1/15	FP	DRWN	CHKD	BSS



Transmission
Business

#

DEERFIELD SUBSTATION
ACCESS ROAD PROFILE

DES: LRM | CHK: LRM
DRW: FP | APR: BSS
TOWN: DEERFIELD, NH
TRANSMISSION LINE:

MILE NO:
SHEET 8 OF 19

NPTT608-C200

REVISION: 11/10/2013

EROSION AND SEDIMENTATION CONTROL GENERAL NOTES:

1.

THE SEDIMENT AND EROSION CONTROL PLAN IS ONLY INTENDED TO DESCRIBE THE SEDIMENT AND EROSION CONTROL TREATMENT FOR THIS SITE. SEE SEDIMENT AND EROSION CONTROL DETAILS AND CONSTRUCTION SEQUENCE. REFER TO SITE PLAN FOR GENERAL INFORMATION AND OTHER CONTRACT PLANS FOR APPROPRIATE INFORMATION.
2.

CONSTRUCTION ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE GENERAL NOTES, SEQUENCE PROVIDED ON THE PLAN DRAWINGS. DEVIATION FROM THAT SEQUENCE MUST BE APPROVED IN WRITING BY THE OWNER, QUALIFIED PROFESSIONAL, AND APPROPRIATE REGULATORY AGENCY PRIOR TO IMPLEMENTATION.
3.

THE EROSION AND SEDIMENTATION CONTROL MEASURES, CONSTRUCTION SEQUENCE AND PHASING IS THE MINIMUM RECOMMENDED. THE CONTRACTOR SHALL INSTALL AND MAINTAIN ADDITIONAL MEASURES AND SEQUENCING AS REQUIRED BASED ON ACTUAL FIELD OPERATIONS AND CONDITIONS AND BE CONSISTENT WITH THE NEW HAMPSHIRE STORMWATER MANUAL. SIGNIFICANT ADDITIONS AND/OR MODIFICATIONS FROM THE PLANS SHALL BE SUBMITTED, REVIEWED AND APPROVED BY THE OWNER, QUALIFIED PROFESSIONAL AND APPLICABLE REGULATORY AGENCIES.
4.

THE SEDIMENT AND EROSION CONTROL PLAN WAS DEVELOPED TO HELP PROTECT THE EXISTING ROADWAY AND STORM DRAINAGE SYSTEMS, ADJACENT PROPERTIES, AND ADJACENT WETLAND AREA FROM SEDIMENT LADEN SURFACE RUNOFF AND EROSION.
5.

APPROPRIATE EROSION/SEDIMENT CONTROL MEASURES AS DESCRIBED HEREIN, SHALL BE INSTALLED BY THE CONTRACTOR PRIOR TO THE COMMENCEMENT OF ALL CLEARING, DEMOLITION AND CONSTRUCTION ACTIVITY WITHIN THE APPROVED LIMITS OF DISTURBANCE. SCHEDULE WORK TO MINIMIZE THE LENGTH OF TIME THAT BARE SOIL WILL BE EXPOSED. CONTRACTOR SHALL ONLY EXCAVATE AS MUCH UTILITY AND STORM PIPE TRENCH WORK AS CAN BE COMPLETED, BACKFILLED AND STABILIZED IN ONE DAY SO AS TO LIMIT THE AMOUNT OF OPEN, DISTURBED TRENCHING. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION, BUT IN NO CASE SHALL EXCEED 5 ACRES AT ANY ONE TIME BEFORE DISTURBED AREAS ARE STABILIZED.
6.

THE CONTRACTOR SHALL INSTALL ALL SPECIFIED EROSION/SEDIMENT CONTROL MEASURES AND WILL BE REQUIRED TO MAINTAIN THEM IN THEIR INTENDED FUNCTIONING CONDITION AND BE IN STRICT CONFORMANCE WITH THE STANDARDS BELOW. THE CONTRACTOR SHALL SUPPLY AND MAINTAIN THESE STANDARDS AND HAVE THEM AVAILABLE ONSITE FOR THE DURATION OF CONSTRUCTION. THE OWNER, AGENTS OF THE REGULATORY AGENCIES AND/OR QUALIFIED PROFESSIONAL SHALL HAVE THE AUTHORITY TO REQUIRE SUPPLEMENTAL MAINTENANCE OR ADDITIONAL MEASURES IF FIELD CONDITIONS ARE ENCOUNTERED BEYOND WHAT WOULD NORMALLY BE ANTICIPATED.

A.

EVERSOURCE BEST MANAGEMENT PRACTICES MANUAL (TO BE FURTHER DEVELOPED).

B.

NEW HAMPSHIRE DEPARTMENT OF ENVIRONMENTAL SERVICES STORMWATER MANUAL, DECEMBER 2008.
7.

IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE CONTRACTOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO ELIMINATE THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION.
8.

THE CONTRACTOR SHALL KEEP A SUPPLY OF EROSION CONTROL MATERIAL (STRAW BALES, SILT FENCE, JUTE MESH, RIP RAP ETC.) ON-SITE FOR MAINTENANCE AND EMERGENCY REPAIRS.
9.

STONE CONSTRUCTION ENTRANCE/EXIT SHALL BE INSTALLED AT START OF CONSTRUCTION AND MAINTAINED THROUGHOUT THE DURATION OF CONSTRUCTION. THE LOCATION OF THE TRACKING PADS MAY CHANGE AS VARIOUS PHASES OF CONSTRUCTION ARE COMPLETED.
10.

TOPSOIL SHALL BE STRIPPED AND STOCKPILED FOR USE IN FINAL LANDSCAPING. ALL EARTH STOCKPILES SHALL HAVE STRAW BALES OR SILT FENCE AROUND THE LIMIT OF PILE. PILES SHALL BE TEMPORARILY SEEDED IF PILE IS TO REMAIN IN PLACE FOR MORE THAN 2 MONTHS.
11.

COMPLY WITH REQUIREMENTS OF THE EPA FOR NPDES AND RECORD KEEPING.
12.

VISUAL SITE INSPECTIONS SHALL BE CONDUCTED WEEKLY, AND AFTER EACH MEASURABLE PRECIPITATION EVENT OF 0.50 INCHES OR GREATER BY QUALIFIED PERSONNEL, TRAINED AND EXPERIENCED IN EROSION AND SEDIMENT CONTROL, TO ASCERTAIN THAT THE EROSION AND SEDIMENT CONTROL (E&S) BMPS ARE OPERATIONAL AND EFFECTIVE IN PREVENTING POLLUTION. PROVIDE WRITTEN REPORTS IN ACCORDANCE WITH ANY APPLICABLE OWNER, QUALIFIED PROFESSIONAL, AND/OR REGULATORY AGENCY REQUIREMENTS.
13.

STOCKPILES OF EARTH MATERIALS SHALL CONFORM TO SOIL STOCKPILE PRACTICES IN SECTION 4.1 OF THE NH DES STORMWATER MANUAL VOLUME 3.
14.

DEWATERING SUMP PITS SHALL BE INSTALLED WHEN WATER COLLECTS DURING DURING EXCAVATION TO TRAP AND FILTER WATER FOR PUMPING INTO A SUITABLE DISCHARGE AREA. A PERFORATED VERTICAL STANDPIPE WRAPPED IN NON-WOVEN FILTER FABRIC IS PLACED IN THE CENTER OF THE PIT TO COLLECT FILTERED WATER WHERE IT IS THEN REMOVED FROM THE SUMP PIT IN AN AUTHORIZED MANNER. UNDER NO CIRCUMSTANCES SHALL DEWATERING DRAINAGE BE DISCHARGED INTO A SANITARY SEWER. CONSTRUCTION DEWATERING SHALL CONFORM TO CONSTRUCTION DEWATERING REQUIREMENTS OF THE NH DES STORMWATER MANUAL VOLUME 3 SECTION 4.2.

15.

WATER SHALL BE USED FOR DUST CONTROL IN APPROPRIATE AREAS.
16.

ALL REGULATORY AGENCY PERMITS REQUIRED FOR THE SITE SHALL BE OBTAINED PRIOR TO SITE WORK COMMENCES.
17.

ALL OFF-SITE WASTE AND BORROW AREAS MUST HAVE AN E&S PLAN APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT FULLY IMPLEMENTED PRIOR TO BEING ACTIVATED.
18.

E&S BMPS SHALL REMAIN FUNCTIONAL AS SUCH UNTIL ALL AREAS TRIBUTARY TO THEM ARE PERMANENTLY STABILIZED OR UNTIL THEY ARE REPLACED BY ANOTHER BMP APPROVED BY THE LOCAL CONSERVATION DISTRICT OR THE DEPARTMENT.
19.

MAXIMUM SLOPES SHALL NOT EXCEED 3-FT HORIZONTAL TO 1-FT VERTICAL (3:1), UNLESS OTHERWISE NOTED. THE CONTRACTOR SHALL VERIFY SLOPE STABILITY OF ALL SLOPES PRIOR TO CONSTRUCTION. UNSTABLE SLOPES SHALL BE LAID BACK (FLATTENED) UNTIL STABLE OR PROVIDE REINFORCING TO ACHIEVE STABILIZATION. SLOPE BENCHES SHALL BE IN ACCORDANCE WITH THE NHDES STORMWATER MANUAL.
20.

THE CONTRACTOR SHALL MAINTAIN EMERGENCY ACCESS TO ALL AREAS AFFECTED BY HIS WORK AT ALL TIMES.
21.

TEMPORARY AND PERMANENT SEEDING SHALL BE IN ACCORDANCE WITH THE PLANTING PLAN, NH DES STORMWATER MANUAL VOLUME 3, AND NH DOT STANDARD SPECIFICATIONS SECTION 644.

ALTERATION OF TERRAIN STANDARD NOTES:

1.

THE PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER AGR 3800 RELATIVE TO INVASIVE SPECIES.
2.

PERIMETER CONTROLS SHALL BE INSTALLED PRIOR TO EARTH MOVING OPERATIONS. INSTALL TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES AS NECESSARY PRIOR TO FURTHER EARTH MOVING OPERATIONS. PREVENTION OF EROSION AND SEDIMENT TRANSPORTATION ISSUES WILL BE FACILITATED BY THE PROMPT EMPLOYMENT OF EFFECTIVE TEMPORARY AND PERMANENT CONTROL DEVICES, AS CONDITIONS WARRANT. ADDITIONAL CONTROL DEVICES THAT ARE DETERMINED NECESSARY, NOT OUTLINED HEREIN, MAY BE INSTALLED BY THE OWNER OR OPERATOR.
3.

PONDS AND SWALES SHALL BE INSTALLED EARLY ON IN THE CONSTRUCTION SEQUENCE PRIOR TO ROUGH GRADING THE SITE AND OTHER EARTH MOVING ACTIVITIES.
4.

DITCHES AND SWALES SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.
5.

ROADWAYS SHALL BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.
6.

CUT AND FILL SLOPES SHALL BE SEEDED/LOAMED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE.
7.

INSPECT AND MAINTAIN ALL EROSION AND SEDIMENTATION CONTROL MEASURES WEEKLY AND AFTER EVERY HALF-INCH OF RAINFALL DURING THE LIFE OF THE PROJECT. REMOVE TRAPPED SEDIMENT FROM COLLECTOR DEVICES AS NEEDED.
8.

STABLE IS DEFINED AS:

A.

BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED,

B.

A MINIMUM OF 85 PERCENT VEGETATED GROWTH HAS BEEN ESTABLISHED,

C.

A MINIMUM 3-INCHES OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIPRAP HAS BEEN INSTALLED,

D.

OR EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.
9.

ALL AREAS SHALL BE STABILIZED WITHIN 45 DAYS OF INITIAL DISTURBANCE.
10.

TEMPORARY AND PERMANENT SEEDING SPECIFICATIONS ARE AS NOTED IN THE "VEGETATION MEASURES" SECTION ON THIS SHEET.
11.

STANDARD WINTER NOTES:

A.

ALL PROPOSED VEGETATED AREAS THAT DO NOT EXHIBIT A MINIMUM 85 PERCENT VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE. THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS.

B.

ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85 PERCENT VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS.

C.

AFTER NOVEMBER 15, INCOMPLETE ROAD OR PARKING SURFACES, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAVEL PER NHDOT ITEM 304.3.

WINTER CONSTRUCTION NOTES:

1.

WINTER EXCAVATION AND EARTHWORK SHALL BE COMPLETED AS SUCH THAT NO MORE THAN 1 ACRE OF THE SITE IS WITHOUT STABILIZATION AT ANY ONE TIME.
2.

AN AREA WITHIN 100 FEET OF A PROTECTED NATURAL RESOURCE SHALL BE PROTECTED WITH A DOUBLE ROW OF SEDIMENT BARRIER.
3.

TEMPORARY MULCH SHALL BE APPLIED WITHIN 7 DAYS OF SOIL EXPOSURE OR PRIOR TO ANY STORM EVENT, BUT AFTER EVERY WORKDAY IN AREAS WITHIN 100 FEET FROM A PROTECTED NATURAL RESOURCE.
4.

AREAS THAT HAVE BEEN BROUGHT TO FINAL GRADE SHALL BE PERMANENTLY MULCHED THE SAME DAY.
5.

IN THE EVENT OF A SNOWFALL GREATER THAN 1 INCH (FRESH OR CUMULATIVE), THE SNOW SHALL BE REMOVED FROM THE AREAS DUE TO BE SEEDED AND MULCHED.
6.

LOAM SHALL BE FREE OF FROZEN CLUMPS BEFORE IT IS APPLIED.
7.

A DITCH THAT WILL BE CONSTRUCTED DURING THE WINTER MUST BE STABILIZED WITH RIPRAP.
8.

PERMANENT STABILIZATION CONSISTS OF AT LEAST 85% VEGETATION, PAVEMENT/GRAVEL BASE OR RIPRAP.
9.

DO NOT EXPOSE SLOPES OR LEAVE SLOPES EXPOSED OVER THE WINTER OR FOR ANY OTHER EXTENDED TIME OF WORK SUSPENSION UNLESS FULLY PROTECTED WITH MULCH AND EROSION CONTROLS.
10.

APPLY STRAW MULCH AT TWICE THE STANDARD RATE (150 LBS. PER 1,000 SF). THE MULCH MUST BE THICK ENOUGH SUCH THAT THE GROUND SURFACE WILL NOT BE VISIBLE AND MUST BE ANCHORED.
11.

USE MULCH AND MULCH NETTING OR AN EROSION CONTROL MULCH BLANKET OR MIX FOR ALL SLOPES GREATER THAN 8% OR OTHER AREAS EXPOSED TO DIRECT WIND.
12.

INSTALL AN EROSION CONTROL BLANKET IN ALL DRAINAGE WAYS (BOTTOM AND SIDES) WITH A SLOPE GREATER THAN 3%.
13.

SEE THE VEGETATION MEASURES FOR MORE INFORMATION ON SEEDING DATES AND TYPES.

CONSTRUCTION SEQUENCE:

- THE FOLLOWING CONSTRUCTION SEQUENCE IS RECOMMENDED (COORDINATE ALL SITE ACTIVITIES AND CONSTRUCTION SEQUENCE WITH THAT OF THE STATION ELECTRICAL EQUIPMENT, OVERHEAD AND UNDERGROUND TRANSMISSION LINES, AND OTHER STATION RELATED CONSTRUCTION):
1.

CONTACT THE OWNER, QUALIFIED PROFESSIONAL, AND REGULATORY AGENT AT LEAST FORTY-EIGHT (48) HOURS PRIOR TO COMMENCEMENT OF ANY DEMOLITION, CONSTRUCTION OR REGULATED ACTIVITY ON THIS PROJECT SITE.
2.

CLEARING LIMITS SHALL BE PHYSICALLY MARKED IN THE FIELD AND APPROVED BY THE REGULATORY AGENT PRIOR TO THE START OF WORK ON THE SITE. INSTALL PERIMETER EROSION/SEDIMENT CONTROL MEASURES.
3.

CONSTRUCT STONE CONSTRUCTION ENTRANCES/EXITS AND INSTALL INLET PROTECTION FOR CATCH BASINS OR INSTALL SILT SACKS ON CATCH BASIN INLETS LOCATED IN OFF-SITE ROADS. INSTALL SILT FENCE AND OTHER EROSION CONTROL DEVICES INDICATED ON THESE PLANS AT PERIMETER OF PROPOSED SITE DISTURBANCE AND INSTALL ALL EROSION/SEDIMENT CONTROL MEASURES AND TREE PROTECTION INDICATED ON THESE PLANS. INSTALL SEDIMENT BASINS AND SEDIMENT TRAPS IF REQUIRED AT LOW AREAS OF SITE OR AS ORDERED BY THE QUALIFIED PROFESSIONAL OR AS SHOWN ON THESE PLANS.
4.

CLEAR AND GRUB SITE. STOCKPILE CHIPS. STOCKPILE TOPSOIL. INSTALL EROSION CONTROLS AT STOCKPILES.
5.

COMMENCE INSTALLATION OF STORM DRAINAGE SYSTEM.
6.

COMMENCE EARTHWORK. CONSTRUCT FILL SLOPE. INSTALL ADDITIONAL EROSION CONTROLS AS WORK PROGRESSES AND CONTINUE STORM DRAINAGE SYSTEM CONSTRUCTION, TOPSOIL AND SEED SLOPES WHICH HAVE ACHIEVED FINAL SITE GRADING.
7.

CONSTRUCTION STAKING OF ALL FOUNDATION CORNERS, UTILITIES, ACCESS DRIVES, FENCES AND OTHER SITE APPURTENANCES.
8.

ROUGH GRADING AND FILLING OF SUBGRADES AND SLOPES.
9.

BEFORE DISPOSING OF SOIL OR RECEIVING BORROW FOR THE SITE, THE CONTRACTOR MUST PROVIDE EVIDENCE THAT EACH SPOIL OR BORROW AREA HAS AN EROSION AND SEDIMENT CONTROL PLAN APPROVED BY THE APPROPRIATE REGULATORY AGENCIES AND WHICH IS BEING IMPLEMENTED AND MAINTAINED. THE CONTRACTOR SHALL ALSO NOTIFY THE APPROPRIATE REGULATORY AGENCIES IN WRITING OF ALL RECEIVING SPOIL AND BORROW AREAS WHEN THEY HAVE BEEN IDENTIFIED.
10.

CONTINUE INSTALLATION OF STORM DRAINAGE AS SUBGRADE ELEVATIONS ARE ACHIEVED.
11.

CONSTRUCT PAD SUBGRADE PREPARATION AND BEGIN FOUNDATION CONSTRUCTION.

12.

THROUGHOUT CONSTRUCTION SEQUENCE, REMOVE SEDIMENT FROM BEHIND SILT FENCES, STRAW BALES AND OTHER EROSION CONTROL DEVICES, AND FROM SEDIMENT TRAPS AS REQUIRED. REMOVAL SHALL BE ON A PERIODIC BASIS (EVERY SIGNIFICANT RAINFALL OF 0.50 INCH OR GREATER). INSPECTION OF EROSION/SEDIMENT CONTROL MEASURES SHALL BE ON A WEEKLY BASIS AND AFTER EACH RAINFALL OF 0.50 INCHES OR GREATER. SEDIMENT COLLECTED SHALL BE DEPOSITED AND SPREAD EVENLY UPLAND ON SLOPES DURING CONSTRUCTION.
13.

COMPLETE GRADING TO SUBGRADES AND COMPLETE CONSTRUCTION OF FOUNDATIONS.
14.

CONSTRUCT CURBS, PAVEMENT STRUCTURE AND SIDEWALKS
15.

CONDUCT FINE GRADING.
16.

PAVING OF ACCESS ROAD
17.

CONSTRUCT OFF-SITE ROADWAY IMPROVEMENTS, AS NECESSARY.
18.

INSTALL YARD SURFACE STONE. FINAL FINE GRADING OF SLOPE AND NON-PAVED AREAS.
19.

PLACE 4" TOPSOIL ON SLOPES AFTER FINAL GRADING IS COMPLETED. FERTILIZE, SEED, AND MULCH.
20.

LANDSCAPE INTERIOR NON-PAVED AREAS, NON-GRAVELED AREAS, AND PERIMETER AREAS.
21.

INSTALL ON-SITE SIGNAGE AND PAVEMENT MARKINGS
22.

CLEAN STORM DRAINAGE PIPE STRUCTURES, DETENTION SYSTEMS AND WATER QUALITY DEVICES OF DEBRIS AND SEDIMENT.
23.

UPON DIRECTION OF THE OWNER, QUALIFIED PROFESSIONAL, AND REGULATORY AGENT, EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED FOLLOWING STABILIZATION OF THE SITE.

ROUGH GRADING OPERATIONS

1.

DURING THE REMOVAL AND/OR PLACEMENT OF EARTH AS INDICATED ON THE GRADING PLAN, TOPSOIL SHALL BE STRIPPED AND APPROPRIATELY STOCKPILED FOR REUSE.
2.

ALL STOCKPILED TOPSOIL SHALL BE SEEDED, APPLY MULCH OR STRAW, AND ENCLOSED BY A SILTATION FENCE.

FILLING OPERATIONS

1.

PRIOR TO FILLING, ALL SEDIMENTATION AND EROSION CONTROL DEVICES SHALL BE PROPERLY IMPLEMENTED, MAINTAINED AND FULLY INSTALLED, AS DIRECTED BY THE QUALIFIED PROFESSIONAL AND AS SHOWN ON THIS PLAN.

PLACEMENT OF DRAINAGE STRUCTURES, UTILITIES, AND FOUNDATION CONSTRUCTION OPERATIONS

1.

SILT FENCES SHALL BE INSTALLED AT THE DOWNHILL SIDES OF EXCAVATIONS, MUD PUMP DISCHARGES, AND UTILITY TRENCH MATERIAL STOCKPILES. STRAW BALES MAY BE USED IF SHOWN ON THE EROSION CONTROL PLANS OR IF DIRECTED BY THE QUALIFIED PROFESSIONAL.

FINAL GRADING AND PAVING OPERATIONS

1.

ALL INLET AND OUTLET PROTECTION SHALL BE PLACED AND MAINTAINED AS SHOWN ON EROSION CONTROL PLANS AND DETAILS, AND AS DESCRIBED IN SPECIFICATIONS AND AS DESCRIBED HEREIN.
2.


NO CUT OR FILL SLOPES SHALL EXCEED 2:1 EXCEPT WHERE STABILIZED BY ROCK FACED EMBANKMENTS OR EROSION CONTROL BLANKETS, JUTE MESH AND VEGETATION. ALL SLOPES SHALL BE SEEDED, AND ANY ROAD OR DRIVEWAY SHOULDER AND BANKS SHALL BE STABILIZED IMMEDIATELY UPON COMPLETION OF FINAL GRADING UNTIL TURF IS ESTABLISHED.
3.

PAVEMENT SUB-BASE AND BASE COURSES SHALL BE INSTALLED OVER AREAS TO BE PAVED AS SOON AS FINAL SUB-GRADES ARE ESTABLISHED AND UNDERGROUND UTILITIES AND STORM DRAINAGE SYSTEMS HAVE BEEN INSTALLED.
4.

AFTER CONSTRUCTION OF PAVEMENT, TOPSOIL, FINAL SEED, MULCH AND LANDSCAPING, REMOVE ALL TEMPORARY EROSION CONTROL DEVICES ONLY AFTER ALL AREAS HAVE BEEN PAVED AND/OR GRASS HAS BEEN WELL ESTABLISHED AND THE SITE HAS BEEN INSPECTED AND APPROVED BY THE OWNER AND THE APPLICABLE REGULATORY AGENCIES.
5.

AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM OF 85% UNIFORM PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING OR OTHER MOVEMENTS.
6.


MAINTAIN ALL PERMANENT AND TEMPORARY SEDIMENT CONTROL DEVICES IN EFFECTIVE CONDITION THROUGHOUT THE CONSTRUCTION PERIOD. UPON COMPLETION OF WORK SWEEP PARKING LOT AND REMOVE ALL TEMPORARY SEDIMENT CONTROLS WHEN AUTHORIZED BY LOCAL GOVERNING AUTHORITY. FILE NOT (NOTICE OF TERMINATION) WITH GOVERNING AUTHORITY RESPONSIBLE FOR REGULATING STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES PER NPDES.



This document has been digitally sealed.
Oct 5 2015

FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION

ISSUED FOR PERMITTING	10/7/15	DATE	NO.
REVISION			
CHG			
BSS			
R/R			
DRWN			
APPRV.			



Transmission
Business

#

DEERFIELD SUBSTATION
EROSION AND SEDIMENTATION
CONTROL NOTES


DES: LRM | CHK:RLR
DRW: FP | APR: BSS

TOWN:
DEERFIELD, NH

TRANSMISSION LINE:

MILE NO:
SHEET 10 OF 19

NPTT610-C500



1. REMOVE ALL LOAM, CLAY, MUCK, STUMPS, AND OTHER IMPROPER ROAD FOUNDATION MATERIAL WITHIN 2' OF SUBGRADE. REPLACE WITH COMPACTED GRANULAR FILL MATERIAL ACCEPTABLE TO APPROVING AGENCY. COMPACTION TO BE AT LEAST 95% OF STANDARD PROCTOR.
2. SUBSTATION SURFACE STONE SHALL EXTEND 3-FT OUTSIDE THE SUBSTATION PERIMETER FENCE.
3. GRAVEL ACCESS ROADS SHALL HAVE AT LEAST 8 INCHES OF PROCESSED AGGREGATE BASE.

NOT TO SCALE

AD

3

C100

C101-C104




1. FOR LOCATION OF AREAS TO BE PROTECTED SEE SHEET C102.
2. SAFETY FENCE SHALL BE FASTENED SECURELY TO THE T-POSTS.
3. THE FENCING MUST REMAIN IN PLACE DURING ALL PHASES OF CONSTRUCTION AND UNTIL ALL DISTURBED AREAS HAVE BEEN STABILIZED.

NOT TO SCALE

4
C102

**FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION**

[illegible]Transmission
Business

	#
--	---

DEERFIELD SUBSTATION
CONSTRUCTION DETAILS

S	
ES: LRM	CHK:RLR
NRW: FP	APR: BSS
TOWN:	
DEERFIELD, NH	
TRANSMISSION LINE	


MILE NO:

SHEET 13 OF 19

REVISION: 11/10/2013


DIAMETER	WALL THICKNESS (MIN.)	FLOOR THICKNESS (MIN.)
4'	5"	6"
5'	6"	8"
6'	7"	8"
8'	9"	10"

CORE HOLE SIZE				
PIPE SIZE	RCP CORE HOLE DIA.		PLASTIC CORE HOLE DIA.	
INCHES	INCHES	FEET	INCHES	FEET
6			7	0.6
12	18	1.5	18	1.5
15	22	1.8	20	1.7
18	26	2.2	24	2.0
24	34	2.8	32	2.7
30	42	3.5	42	3.5
36	48	4.0	48	4.0
42	54	4.5	54	4.5
48	64	5.3	64	5.3
54	72	6.0		
60	78	6.5		



NOTE:
No. 4 REBAR ENCASED IN CORROSION RESISTANT RUBBER OR OTHER MATERIAL APPROVED BY THE OWNER'S REPRESENTATIVE.


MANHOLE STEP
NOT TO SCALE



NOTES:

- ALL DIMENSIONS ARE NOMINAL.
- LABEL TYPE OF MANHOLE WITH 3" HIGH LETTERS IN THE CENTER OF THE COVER.

MANHOLE FRAME AND COVER
NOT TO SCALE




SECTION B-B

NOTES:


- ALL DIMENSIONS ARE NOMINAL.
- FREE OPEN AREA = 1.80 S.F.

PIPE DIAMETER INCHES	THROAT DEPTH "A" INCHES	
	ONE THROAT	ONE THROAT
12"	8"	8"
15"	8"	8"
18"	16"	8"
24"	18"	16"

IN A SERIES OF CONNECTING C.B.'S OR D.I.'S, THE OUTLET PIPES MAY INCREASE IN DIAMETER, BUT THE SURFACE THROAT OPENINGS ARE NOT AFFECTED.




SECTION A-A




PLAN


TYPE "E" GRATE
NOT TO SCALE



SECTION B-B



PLAN



PLAN




* FOR 6' Ø STRUCTURES
USE 16" & 12" DIMENSIONS

SECTION B-B
FLAT SLAB TOP

GENERAL NOTES:

- CATCH BASIN TO CONFORM TO NH DOT SECTION 604.1 REQUIREMENTS.
- FITTING FRAME TO GRADE MAY BE DONE WITH PREFABRICATED ADJUSTMENT RINGS OR CLAY BRICKS (2 COURSES MAX.).
- CONE SECTIONS MAY BE EITHER CONCENTRIC OR ECCENTRIC, OR FLAT SLAB TOPS MAY BE USED WHERE PIPE WOULD OTHERWISE ENTER INTO THE CONE SECTION OF THE STRUCTURE AND WHERE PERMITTED.
- PIPE ELEVATIONS SHOWN ON PLANS SHALL BE FIELD VERIFIED PRIOR TO PRECASTING.
- OUTSIDE EDGES OF PIPES SHALL PROJECT NO MORE THAN 3" BEYOND INSIDE WALL OF STRUCTURE.
- PRECAST SECTIONS SHALL HAVE A TONGUE AND GROOVE JOINT 4" HIGH AT AN 11° ANGLE CENTERED IN THE WIDTH OF THE WALL AND SHALL BE ASSEMBLED USING AN APPROVED FLEXIBLE SEALANT IN JOINTS.
- ALL STRUCTURES WITH MULTIPLE PIPES SHALL HAVE A MINIMUM OF 12" OF INSIDE SURFACE BETWEEN HOLES, NO MORE THAN 75% OF A HORIZONTAL CROSS-SECTION SHALL BE HOLES, AND THERE SHALL BE NO HOLES CLOSER THAN 3" TO JOINTS.



SECTION A-A


PRECAST CONCRETE
MANHOLE AND CATCH BASIN
NOT TO SCALE

1
C104

This document has been digitally sealed.
Oct 5 2015

FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION

NO.	REVISION	DATE	DRWN	CHKD	APPRV.
1	ISSUED FOR PERMITTING	10/1/15	FP	BSS	



Transmission
Business

#

DEERFIELD SUBSTATION
CONSTRUCTION DETAILS

DES: LRM | CHK: RLR
DRW: FP | APR: BSS

TOWN:
DEERFIELD, NH





TRANSMISSION LINE:

MILE NO:


SHEET 14 OF 19

NPTT614-C504

REVISION: 11/10/2013



**FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION**

[illegible]Transmission
Business

	#
--	---

DATE: 10/1/2006

DEERFIELD SUBSTA
CONSTRUCTION DE

WES: LRM	CHK:RLR
PRW: FR	APP: BSS

TOWN: DEERFIELD, NH






TRANSMISSION LINE:

MILE NO:

SHEET 15 OF 19


NPTT615-C505

REVISION: 11/10/2013



**FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION**


[illegible]



BASIN NO.	WATER SURFACE ELEVATION			BOTTOM BASIN ELEVATION	Z1 (FT)	Z2 (FT)	BARREL				EMBANKMENT			
	2 YEAR	10 YEAR	50 YEAR				DIA Bd (IN)	INLET ELEV BIE (FT)	MAT'L	LENGTH BL (FT)	OUTLET ELEV BOE (FT)	TOP ELEV ETE (FT)	TOP WIDTH ETw (FT)	CREST (FT)
DT-1	380.56	381.61	382.36	380.00	3	3	18	379.00	CLASS III RCP	53	378.00	384.00	6	383.00
DT-2	369.78	370.47	371.36	368.00	3	3	24	367.50	CLASS III RCP	31	367.25	373.00	6	372.00

DETENTION BASIN CROSS SECTION
NOT TO SCALE

1
C104




SECTION A-A

ANTI SEEP COLLAR
NOT TO SCALE


2
C104

NOTES:

1. WRAP PIPE WITH "RAM-NEK" OR EQUIVALENT WHERE PIPE IS EXPOSED TO CONCRETE PRIOR TO POURING.
2. EXCAVATION & BACKFILL SHALL BE AS SPECIFIED.
3. DO NOT PLACE WITHIN 2 FEET OF A PIPE JOINT.
4. REFER TO DETAIL 1 FOR LOCATION.




PLAN



- NOTES**
1. SEE SECTION THROUGH SPILLWAY FOR FURTHER INFORMATION.

SPILLWAY APRON
NOT TO SCALE

3
C104




SECTION A-A

BASIN NO.	WEIR						LINING		CHANNEL	
	Z3 (FT)	Z4 (FT)	TOP ELEV WTE (FT)	CREST ELEV WCE (FT)	WIDTH Ww (FT)	PI (FT)	RIPRAP SIZE (d ₅₀)	RIPRAP THICK. LRT (IN)	Z5 (FT)	DEPTH Cd (FT)
DT-1	3	3	384.00	383.00	32	1	12	36	3	0.50
DT-2	3	3	373.00	372.00	32	1	12	36	3	0.50
SF-1	3	3	379.00	378.00	13	1	12	36	3	0.50


SECTION THROUGH SPILLWAY
NOT TO SCALE

4
C104



PLAN

PROFILE



SECTION A-A

TRENCH DRAIN
NOT TO SCALE

5
C104

NOTES:

1. TRENCH DRAIN SHALL BE HEAVY DUTY TYPE DESIGNED FOR HS-20 LOADING.
2. CONCRETE SHALL BE COMPRESSIVE STRENGTH 4000 PSI, TYPE II CEMENT.



This document has been digitally sealed.
Oct 5 2015

FOR PERMITTING PURPOSES ONLY
NOT FOR CONSTRUCTION

NO.	DATE	REVISION	ISSUED FOR PERMITTING	DATE	CHG	APPROV.
1	10/1/15	FP	BSS			
			R/R			
			BSS			

Transmission Business

#

DEERFIELD SUBSTATION CONSTRUCTION DETAILS

DATE: 10/1/2015

SCALE: NTS

DES: LRM | CHK: LRM
DRW: FP | APR: BSS

TOWN: DEERFIELD, NH


TRANSMISSION LINE:

MILE NO:

SHEET 18 OF 19

NPTT618-C508

REVISION: 11/10/2013



5

10 YR. EL 378.42
WQV EL 378.00

FOREBAY

EL 377.00

RIPRAP

STONE FILL

CLEANOUT

GEOTEXTILE FABRIC

SANDFILTER SF-1

EL 376.90

EL 374.75

INV 373.00

UNDERDRAIN

PIPE TO DT-2
(SOLID WALL PIPE)

SPILLWAY
EL 378.00

CLEANOUT, TYP.

4
C507

1

2
C507


3
C104

**FOREBAY / SAND FILTER
SCHEMATIC SECTION**

NOT TO SCALE

LOW FLOW PIPE FROM
SWALE SW-1B

FOREBAY / SAND FILTER
SCHEMATIC SECTION
NOT TO SCALE



1. PERFORATIONS SHALL BE MADE IN THE 90 DEGREE BEND TO ASSURE THE DETENTION AREA COMPLETELY DRAINS TO THE SAND FILTER AREA.
2. POSITIVE DRAINAGE IS TO BE MAINTAINED FROM THE FOREBAY TO THE SAND FILTER AREA.

**FOR PERMITTING
PURPOSES ONLY
NOT FOR CONSTRUCTION**